

JOB LOG

SWIFT Services, Inc.

DATE 10-5-13 PAGE NO. 1

CUSTOMER TDI WELL NO. #1 LEASE Raymond Trust JOB TYPE Deep Surface TICKET NO. 25130

CHART NO.	TIME	RATE (BPM)	VOLUME (BBL) (GAL)	PUMPS		PRESSURE (PSI)		DESCRIPTION OF OPERATION AND MATERIALS
				T	C	TUBING	CASING	
	1210							on loc w/FE
								TD 1503'
								8 5/8" x 23# x 1503' x 45'
	1430							Start FE
	1630							Break Circ
	1700	5	0				150	Start 500 gal Mudflush
	1702	5	12/0				150	Start 450 sks SMD @ 11.8#
	1717	5	69/0				150	Start 150 sks SMD @ 12.5#
	1730	5	57/0				150	Start 100 sks SMD @ 13.5#
	1737	5	31/0				150	Start 75 sks SMD @ 14.5#
	1742		19					End Cement
								Drop Plug
	1750	1.5	0				50	Start Displacement
	1830	2	65				350	Circulate Cement
	1840		93.3				400 450 500	Land Plug Shot In
								circ. 50 sks to Pit
								Thank you
								Nick, David E. & Isaac

