



**#1 Lampe 3B**  
3140' FSL & 1320' FWL  
Irregular Section - Section 3-26S-22W  
Ford County, Kansas  
API# 15-057-20912-00-00  
Elevation: 2401' GL, 2411' KB

Sample Tops			Ref. Well
Anhydrite	1487'	+924	-6
B/Anhydrite	1519'	+892	-6
Stotler	3484'	-1073	+1
Heebner	4105'	-1694	Flat
Lansing	4217'	-1806	-1
Muncie Shale	4395'	-1984	-6
Stark Shale	4513'	-2102	-7
Hush	4562'	-2151	-3
BKC	4596'	-2185	Flat
Marmaton	4600'	-2189	Flat
Altamont	4650'	-2239	-4
Pawnee	4715'	-2304	+3
Fort Scott	4745'	-2334	+3
Cherokee Shale	4769'	-2358	Flat
Huck	4836'	-2425	-1
Atoka	4854'	-2443	-4
Mississippian	4906'	-2495	-9
RTD	5000'	-2589	

# ALLIED OIL & GAS SERVICES, LLC 061825

Federal Tax I.D. # 20-8651475

REMIT TO P.O. BOX 93999  
SOUTHLAKE, TEXAS 76092

SERVICE POINT:  
*Greene Bend, KS*

DATE <i>9-27-13</i>	SEC <i>3</i>	TWP. <i>26S</i>	RANGE <i>22W</i>	CALLED OUT	ON LOCATION	JOB START <i>11:00am</i>	JOB FINISH <i>12:00AM</i>
LEASE <i>Amey 3B</i>		WELL # <i>1</i>	LOCATION <i>Spearville 1E 35 1/2E</i>		COUNTY <i>Ford</i>	STATE <i>KS</i>	
OLD OR NEW (Circle one) <input checked="" type="radio"/> OLD			15 Etno				

CONTRACTOR *Vol Energy #1*

TYPE OF JOB *Surface*

HOLE SIZE *12 1/4* T.D. \_\_\_\_\_

CASING SIZE *4 1/2* DEPTH *360*

TUBING SIZE \_\_\_\_\_ DEPTH \_\_\_\_\_

DRILL PIPE *4 1/2* DEPTH \_\_\_\_\_

TOOL \_\_\_\_\_ DEPTH \_\_\_\_\_

PRES. MAX \_\_\_\_\_ MINIMUM \_\_\_\_\_

MEAS. LINE \_\_\_\_\_ SHOE JOINT \_\_\_\_\_

CEMENT LEFT IN CSG. *15Ft*

PERFS. \_\_\_\_\_

DISPLACEMENT *21.97 bbl's Freshwater*

**EQUIPMENT**

PUMP TRUCK # *395* CEMENTER *Dustin Chambers*  
HELPER *Mike Scarborough*

BULK TRUCK # *609-112* DRIVER *Kevin Weighaus*

BULK TRUCK # \_\_\_\_\_ DRIVER \_\_\_\_\_

OWNER \_\_\_\_\_

CEMENT AMOUNT ORDERED *225 sks class A*  
*3-4cc 2 stage 1*

COMMON	<i>225</i>	@ <i>17.90</i>	<i>4027.50</i>
POZMIX		@ _____	_____
GEL	<i>4</i>	@ <i>23.40</i>	<i>93.60</i>
CHLORIDE	<i>8</i>	@ <i>64.00</i>	<i>512.00</i>
ASC		@ _____	_____
_____		@ _____	_____
_____		@ _____	_____
_____		@ _____	_____
_____		@ _____	_____
_____		@ _____	_____
_____		@ _____	_____
_____		@ _____	_____
_____		@ _____	_____
HANDLING	<i>243.29</i>	@ <i>2.48</i>	<i>603.25</i>
MILEAGE	<i>11.10 X 40 X</i>	@ <i>2.60</i>	<i>1154.16</i>
<b>TOTAL</b>			<i>6391.31</i>

**REMARKS:**

*plug 5 bbl's Freshwater ahead  
mix 225 sks cement  
Displace 21.97 bbl's Freshwater & shut in  
Cement did circulate  
plug down 11:30 pm  
R29 Down*

**SERVICE**

DEPTH OF JOB \_\_\_\_\_

PUMP TRUCK CHARGE *1512.25*

EXTRA FOOTAGE @ \_\_\_\_\_

MILEAGE *Hum 40* @ *7.70* *308.00*

MANIFOLD @ \_\_\_\_\_

*Hum 40* @ *4.40* *176.00*

\_\_\_\_\_ @ \_\_\_\_\_

**TOTAL** *1996.25*

CHARGE TO: *Birch Exploration*

STREET \_\_\_\_\_

CITY \_\_\_\_\_ STATE \_\_\_\_\_ ZIP \_\_\_\_\_

**PLUG & FLOAT EQUIPMENT**

\_\_\_\_\_ @ \_\_\_\_\_

\_\_\_\_\_ @ \_\_\_\_\_

\_\_\_\_\_ @ \_\_\_\_\_

\_\_\_\_\_ @ \_\_\_\_\_

\_\_\_\_\_ @ \_\_\_\_\_

**TOTAL** \_\_\_\_\_

To: Allied Oil & Gas Services, LLC.  
You are hereby requested to rent cementing equipment and furnish cementer and helper(s) to assist owner or contractor to do work as is listed. The above work was done to satisfaction and supervision of owner agent or contractor. I have read and understand the "GENERAL TERMS AND CONDITIONS" listed on the reverse side.

PRINTED NAME *x Walter Jurell*

SIGNATURE *x Walter Jurell*

*Thank you!!*


SALES TAX (If Any) \_\_\_\_\_

TOTAL CHARGES *8387.46*

DISCOUNT *1677.48* IF PAID IN 30 DAYS

*6709.96*

*R*



PO Box 884, Chanute, KS 66720  
620-431-9210 or 800-467-8676

263269

TICKET NUMBER 38063  
LOCATION Oakley  
FOREMAN Fuzz  
DONE R TRAINER

FIELD TICKET & TREATMENT REPORT

CEMENT

DATE	CUSTOMER #	WELL NAME & NUMBER	SECTION	TOWNSHIP	RANGE	COUNTY
10-14-13	7173	Lampe 3-B #1	3	26	22	Ford
CUSTOMER			TRUCK #	DRIVER	TRUCK #	DRIVER
R. Lake Exploration			399	Tim W		
MAILING ADDRESS			529	Cody R		
CITY						
STATE						
ZIP CODE						

JOB TYPE Port Collar HOLE SIZE \_\_\_\_\_ HOLE DEPTH \_\_\_\_\_ CASING SIZE & WEIGHT 4 1/2  
 CASING DEPTH \_\_\_\_\_ DRILL PIPE \_\_\_\_\_ TUBING 23/8 OTHER \_\_\_\_\_  
 SLURRY WEIGHT 12.5' SLURRY VOL \_\_\_\_\_ WATER gal/sk \_\_\_\_\_ CEMENT LEFT in CASING \_\_\_\_\_  
 DISPLACEMENT 5.57 DISPLACEMENT PSI \_\_\_\_\_ MIX PSI \_\_\_\_\_ RATE Port Collar @ 1429'

REMARKS: Safety meeting on K&M Well Service. Rig up. Test closed Port Collar to 1200'. Open Port Collar establish circulation. Mix 250 SPS 60/40 pos 60 gal 1/4" closed with 300' cottonseed hulls. Displace 5 BSH. Close Port Collar and test to 1200' hold. Cement did circulate approx 10 BSH to pit. Run 5 BSH reverse to clean with 25 BSH. T

Thanks Done & Crew

ACCOUNT CODE	QUANTITY or UNITS	DESCRIPTION of SERVICES or PRODUCT	UNIT PRICE	TOTAL
54015	1	PUMP CHARGE	1785.00	1785.00
5406	60	MILEAGE	5.25	315.00
5407A	1018 ton	Tow mileage - delivery	1.12	1134.00
1131	250 SPS	60/40 pos	15.86	3965.00
1188	1290*	Bentonite	.27	348.30
1107	63*	Flowal	2.97	187.11
1105	300*	Cottonseed Hulls	.58	174.00
		subtotal		7908.91
		less 10%		790.89
		subtotal		7117.92
		7.80%	SALES TAX	328.44
			ESTIMATED TOTAL	7445.71

completed

Ravin 3737

AUTHORIZATION [Signature] TITLE \_\_\_\_\_ DATE \_\_\_\_\_

I acknowledge that the payment terms, unless specifically amended in writing on the front of the form or in the customer's account records, at our office, and conditions of service on the back of this form are in effect for services identified on this form.



PO Box 884, Chanute, KS 66720  
620-431-9210 or 800-467-8676

263061

TICKET NUMBER: 44404  
LOCATION: Oakley KS  
FOREMAN: Damon Trivette  
T2274

FIELD TICKET & TREATMENT REPORT

CEMENT

DATE	CUSTOMER #	WELL NAME & NUMBER	SECTION	TOWNSHIP	RANGE	COUNTY
10-8-13	7173	Lampre 3-B #1	3	26	22	Fond
CUSTOMER			TRUCK #	DRIVER	TRUCK #	DRIVER
Ritchie Exploration			399	Tom W		
MAILING ADDRESS			397	Keith (Ottawa)		
CITY	STATE	ZIP CODE				

JOB TYPE: Production HOLE SIZE: 77/8 HOLE DEPTH: 5000' CASING SIZE & WEIGHT: 4 1/2 10.5  
 CASING DEPTH: 4989.5 DRILL PIPE: TUBING: #85 OTHER P-collar  
 SLURRY WEIGHT: 14.2 SLURRY VOL: 1.42 WATER gal/sk: CEMENT LEFT in CASING: 21.07  
 DISPLACEMENT: 78.9 DISPLACEMENT PSI: MIX PSI: RATE:

REMARKS: Safety meeting on Ual #1 Float equip cont 1-3-6-9-15-84-86  
 102 Baskets 13-85-101 P-collar Top of 85. Rig up and circulate 1 hr.  
 Pump 5 BBL water, 50 gal mud flush, 5 BBL water, mix 200 SKS MN. - 30 SKS  
 RM. Mix 200 SKS OWC w/ 5# Kolsol, 11405170 CDI-26, 114# / SK CAT-38  
 (deformer), wash pump and lines, Drop plug and displace 78 1/4 BBL  
 water, lift press 1000\* land plug @ 1600\*. Float held.

Thanks Damon & crew

ACCOUNT CODE	QUANTITY or UNITS	DESCRIPTION of SERVICES or PRODUCT	UNIT PRICE	TOTAL
5401C	1	PUMP CHARGE	3175.00	3175.00
5406	60	MILEAGE	5.25	315.00
5407A	11.8 ton	Tow Mileage Delivery	1.73	1239.00
1126	250 SKS	OWC	23.20	5925.00
1110A	1250*	Kolsol	.56	700.00
1137	59*	CDI-26	10.20	601.80
1146	35*	CAT-38	10.20	357.00
1146G	500 gal	Mud Flush	1.00	500.00
4161	1	4 1/2" AFU Float shoe (I)	359.25	359.25
4453	1	4 1/2" Latchdown Assy (W)	290.00	290.00
4139	8	4 1/2" Turbolizers (I)	60.00	480.00
4103	3	4 1/2" Baskets (W)	275.00	825.00
4284	1	4 1/2" Port collar (L)	1984.50	1984.50
		(Serial # 1302137)		
		Subtotal		16751.55
		less 10%		1675.15
		Subtotal		15076.39
		7.80%		843.98
		SALES TAX		843.98
		ESTIMATED TOTAL		15920.37

completed

Rev'n 3737

AUTHORIZATION: G. R. Ram TITLE: \_\_\_\_\_ DATE: \_\_\_\_\_

I acknowledge that the payment terms, unless specifically amended in writing on the front of the form or in the customer's account records, at our office, and conditions of service on the back of this form are in effect for services identified on this form.