

# GRAND MESA OPERATING COMPANY

316-265-3000  
FAX: (316) 265-3455

1700 N. WATERFRONT PARKWAY  
BLDG 600  
WICHITA, KANSAS 67206-5514


Scale 1:240 (5'=100') Imperial  
Measured Depth Log

Well Name: Griffith #2-23  
Location: 1429' FSL, 23-16S-33W, Scott County, Kansas  
License Number: API: 15-171-20988 Region: Scott County  
Spud Date: 10/04/2013 Drilling Completed: 10/17/2013  
Surface Coordinates: Lat: 38.6454293 Long: -100.9283027  
Bottom Hole Coordinates: Vertical hole  
Ground Elevation (ft): 2969' K.B. Elevation (ft): 2978'  
Logged Interval (ft): 3700' To: RTD Total Depth (ft): 4810'  
Formation: Mississippian at RTD  
Type of Drilling Fluid: Chemical

Printed by MUD LOG from WellSight Systems 1-800-447-1534 www.WellSight.com

Name: Kent R. Matson  
Company: Matson Geological Services, LLC  
Address: 33300 W. 15th Street S., Garden Plain, Kansas 67050  
316-644-1975

## GEOLOGIST



## COMMENTS

**Contractor:** Duke Drilling Rig #4.  
**Pusher:** Rich Wheeler.  
**Surface Casing:** 8 5/8" set at 210' (KB) w/170stx cement.  
**Production Casing:** Based on field observations of drill cuttings, DST results and electric log review, production casing (5.5") was installed to further evaluate potential oil production.  
**Mud:** MudCo.  
**DST by:** Diamond Testing - Tim Venter.  
**Logs by:** Weatherford (DL w/SP, CN-CD, ML).  
**RTD= 4810'.**  
**LTD= 4814'.**

## FORMATION TOPS

| FORMATION          | SAMPLE TOPS |       | LOG TOPS |       |
|--------------------|-------------|-------|----------|-------|
|                    | Depth       | Datum | Depth    | Datum |
| Queen Hill         | 3824'       | -846  | 3829'    | -851  |
| Heebner Shale      | 3888'       | -910  | 3890'    | -912  |
| Toronto            | 3908'       | -930  | 3909'    | -931  |
| Lansing            | 3927'       | -949  | 3931'    | -953  |
| Muncie Creek Shale | 4103'       | -1125 | 4106'    | -1128 |
| Stark Shale        | 4198'       | -1220 | 4200'    | -1222 |
| Hushpuckney Shale  | 4244'       | -1266 | 4248'    | -1270 |
| Marmaton           | 4317'       | -1339 | 4320'    | -1342 |
| Upper Fort Scott   | 4416'       | -1438 | 4417'    | -1439 |
| Little Osage Shale | 4439'       | -1461 | 4442'    | -1464 |
| Excello Shale      | 4455'       | -1477 | 4458'    | -1480 |
| Johnson Zone       | 4526'       | -1548 | 4528'    | -1550 |
| Morrow             | 4582'       | -1604 | 4586'    | -1608 |
| Mississippian      | 4613'       | -1635 | 4617'    | -1639 |
| RTD                | 4810'       | -1832 | 4814'    | -1836 |

