

JOB LOG

SWIFT Services, Inc.

DATE 9-26-15 PAGE NO. 7

CUSTOMER Downing + Nelson WELL NO. # 1-32 LEASE PBW JOB TYPE Cement 5 1/2" Longstring TICKET NO. # 29030

CHART NO.	TIME	RATE (BPM)	VOLUME (BBL) (GAL)	PUMPS		PRESSURE (PSI)		DESCRIPTION OF OPERATION AND MATERIALS
				T	C	TUBING	CASING	
	0230							on location 5 1/2" 14"
								RTD- 3845 LTD- 3845 TP- 3844 SJ- 15,38 cent- #1"3"5"7"9"11 sts out - #94"95"96
	0400							start 5 1/2" 14" casing in well
	0540							Drop Ball circulate * Rotate *
	0625	6 1/2	12	✓		350		Pump 500 gal Mud Flush
		6 1/2	20	✓		350		Pump 20 bbl HCL Flush
			7.5					Plug RH-MH (30-20)
	0640	4 1/2	30	✓		300		mix 125 sts EA-2 w 1/4" Flo @ 15.5 ppq
								Wash out Pump + Lines Release Latch Down Plug
	0700	6 1/2	0	✓		200		Start Displacement
		6 1/2	70	✓		300		Lift Pressure
		6 1/2	91	✓		800		Max Lift Pressure
	0715	6 1/2	93.5	✓		1600		Land Latch Down Plug
								Release Pressure * plug hold *
								wash up Truck
	0800							Job Complete

Thank You
Dave John Tyler