

810 E 7TH
 PO Box 92
 EUREKA, KS 67045
 (620) 583-5561



Cement or Acid Field Report
 Ticket No. **2551**
 Foreman Rick Ledford
 Camp Eureka Ks

Date	Cust. ID #	Lease & Well Number	Section	Township	Range	County	State
10-1-15	1180	Folsom B 1A				CQ	Ks
Customer SM Oil + GAS INC			Safety Meeting OK OK CB SE Am	Unit #	Driver	Unit #	Driver
Mailing Address P.O. Box 189				105	Dave G.		
City Spartan				110	Chris B		
State OK				112	Sharon F		
Zip Code 74070				140 7147	ALAN M.		

Job Type 1/5 Hole Depth 11051' Slurry Vol. 50 Bbl Tubing _____
 Casing Depth 11044' Hole Size 63/4 Slurry Wt. 12.8" - 13.6" Drill Pipe _____
 Casing Size & Wt. 4 1/2" Cement Left in Casing 0' Water Gal/SK 8.0 Other _____
 Displacement 26' Bbl Displacement PSI 600 Bump Plug to 1000 BPM _____

Remarks: Safety meeting. Rig up to 4 1/2" casing w/wash head. Washdown 20' to P.B.T.D.
Mixed 300# gel-flush, 30 Bbl water spacer. Mixed 110 sks w/1/4 Pozmix cement w/ 6% gel
+ 1# phenoseal/sk @ 12.8" /gal Tail in w/ 60 sks OWC cement @ 13.6" /gal. Washout pump + lines
release plug. Displace w/ 26' Bbl water. Final pump pressure 600 PSI. Bump plug to 1000 PSI.
release pressure, float + plug held. Followed plug to T.D. w/wireline. Colored water to surface
Job complete. Rig down.

"Thank You"

Code	Qty or Units	Description of Product or Services	Unit Price	Total	
C102	1	Pump Charge	1050.00	1050.00	
C107	30	Mileage	3.95	118.50	
C204	110 sks	50/50 Pozmix cement	11.25	1237.50	
C206	555#	6% gel	.20	111.00	
C208	110#	1# phenoseal/sk	1.25	137.50	
C202	60 sks	OWC cement tail cement	19.15	1149.00	
C206	300#	gel-flush	.20	60.00	
C108A	7.74	tan mileage bulk + tax x 2	m/c x 2	690.00	
C114	2 hrs	transport	110.00	220.00	
C224	5,000 gals	city water	10.00/1000	50.00	
C403	1	4 1/2" top rubber plug	45.00	45.00	
Total = 5105.65 - 5% disc. - 255.28 Total 4850.37					
				Subtotal	4868.50
				Sales Tax	237.15
				8.5%	

Authorization John Jones Title _____ Total = **5105.65**

I agree to the payment terms and conditions of services provided on the back of this job ticket. Any amendments to payment terms must be in writing on the front of this job ticket or in the Customer's records at ELITE's office.