



# ALLIED OIL & GAS SERVICES, LLC 062012

Federal Tax I.D. # 20-8651475

REMIT TO P.O. BOX 93999  
SOUTHLAKE, TEXAS 76092

SERVICE POINT: Oakley KS

DATE <u>3-11-14</u>	SEC. <u>31</u>	TWP. <u>14</u>	RANGE <u>31</u>	CALLED OUT	ON LOCATION	JOB START <u>12:00 pm</u>	JOB FINISH <u>12:30 pm</u>
LEASE <u>Krebs F</u>	WELL # <u>1</u>	LOCATION <u>Oakley 22.53 E.F., 56,</u>	COUNTY <u>Logan</u>	STATE <u>KS</u>			
OLD OR <u>NEW</u> (Circle one)		<u>N, N, E into</u>				<u>Gove</u>	

CONTRACTOR Landmark L OWNER Same

TYPE OF JOB Production

HOLE SIZE 7 7/8 T.D. 4505' CEMENT

CASING SIZE 5 1/2 DEPTH 4507' AMOUNT ORDERED 230 sks ASC

TUBING SIZE DEPTH 10% salt 5<sup>th</sup> Gilsomite 2% gel

DRILL PIPE DEPTH

TOOL port collar DEPTH 2122'

PRES. MAX MINIMUM

MEAS. LINE SHOE JOINT 21.52'

CEMENT LEFT IN CSG. 21.52'

PERFS.

DISPLACEMENT 106.75 bbl water.

EQUIPMENT

PUMP TRUCK CEMENTER Paul Beaver

# 120 HELPER Tyler Flipse

BULK TRUCK

# 566 DRIVER Adam Flipse

BULK TRUCK

# DRIVER

COMMON	@		
POZMIX	@		
GEL	<u>4 sks</u>	@ <u>23.40</u>	<u>93.60</u>
CHLORIDE	@		
ASC	<u>230 sks</u>	@ <u>20.90</u>	<u>4807.00</u>
	@		
<u>Gilsomite</u>	<u>1150<sup>th</sup></u>	@ <u>.98</u>	<u>1127.00</u>
	@		
<u>Salt</u>	<u>24 sks</u>	@ <u>26.35</u>	<u>632.40</u>
	@		
<u>KCL</u>	<u>1 gal</u>	@ <u>34.40</u>	<u>34.40</u>
	@		
<u>DV-1100 (Superflush) 12 bbl</u>	@ <u>58.70</u>		<u>704.40</u>
HANDLING <u>294.03 ft<sup>3</sup></u>	@ <u>2.48</u>		<u>729.19</u>
MILEAGE <u>12.84 hours x 20 mi x 2.60</u>			<u>667.68</u>
TOTAL			<u>8795.60</u>

**REMARKS:**

Run Pipe/ Float equip, Drop Ball, Bill went through shoe @ 600<sup>th</sup>, circ 1 hr  
Pump 10 bbl KCL water, mix 12 bbl superflush  
Pump 5 bbl water spacer, mix 30 sks v.o. B.H.  
Mix 200 sks ASC, wash up into pit, release plug  
Displace w/ water, plug did load @ 1200<sup>th</sup>  
w/ 800<sup>th</sup> lift pressure float did hold

Thank You!  
Taylor + Tyler

**SERVICE**

DEPTH OF JOB		
PUMP TRUCK CHARGE		<u>2765.75</u>
EXTRA FOOTAGE	@	
MILEAGE <u>MIAW 20</u>	@ <u>7.70</u>	<u>154.00</u>
MANIFOLD <u>head</u>	@ <u>275.00</u>	<u>N/C.</u>
<u>MILV 20</u>	@ <u>4.40</u>	<u>88.00</u>
	@	
TOTAL		

TOTAL 3007.25

**PLUG & FLOAT EQUIPMENT**

<u>Weatherford 5 1/2</u>		
<u>Port Collar</u>	@	<u>3590.00</u>
<u>AFV Float shoe</u>	@	<u>545.00</u>
<u>Latrod plug Assy</u>	@	<u>610.00</u>
<u>Turbolizers 8</u>	@ <u>95.00</u>	<u>760.00</u>
<u>Baskets 3</u>	@ <u>395.00</u>	<u>1185.00</u>
TOTAL		

TOTAL 6740.00

SALES TAX (If Any) \_\_\_\_\_

TOTAL CHARGES 18,543.35

DISCOUNT 2,300.67 IF PAID IN 30 DAYS

16,182.68 Net.

CHARGE TO: Black Tea  
 STREET \_\_\_\_\_  
 CITY \_\_\_\_\_ STATE \_\_\_\_\_ ZIP \_\_\_\_\_

To: Allied Oil & Gas Services, LLC.  
 You are hereby requested to rent cementing equipment and furnish cementer and helper(s) to assist owner or contractor to do work as is listed. The above work was done to satisfaction and supervision of owner agent or contractor. I have read and understand the "GENERAL TERMS AND CONDITIONS" listed on the reverse side.

PRINTED NAME \_\_\_\_\_

SIGNATURE John V. Ry