

ALLIED OIL & GAS SERVICES, LLC 062020

Federal Tax I.D. # 20-8651475

REMIT TO P.O. BOX 93999
SOUTHLAKE, TEXAS 76092

SERVICE POINT
Oakley Ks

DATE <u>3-20-14</u>	SEC <u>26</u>	TWP. <u>14</u>	RANGE <u>32</u>	CALLED OUT	ON LOCATION	JOB START <u>3:00 p.m.</u>	JOB FINISH <u>3:30 p.m.</u>
LEASE <u>Krebs S</u>	WELL # <u>2</u>	LOCATION <u>Oakley 22 S E</u>			COUNTY <u>Logan</u>	STATE <u>KS</u>	
OLD OR <u>NEW</u> (Circle one)							

CONTRACTOR <u>Landmark L</u>	OWNER <u>Same</u>
TYPE OF JOB <u>Production (long string)</u>	
HOLE SIZE <u>7 7/8</u>	T.D. <u>4500</u>
CASING SIZE <u>5 1/2</u>	DEPTH <u>4495</u>
TUBING SIZE	DEPTH
DRILL PIPE	DEPTH
TOOL <u>Port collar</u>	DEPTH <u>2168</u>
PRES. MAX	MINIMUM
MEAS. LINE	SHOEJOINT <u>21.53</u>
CEMENT LEFT IN CSG. <u>21.53</u>	
PERFS.	
DISPLACEMENT <u>106.47 bbl water</u>	
EQUIPMENT	

CEMENT	
AMOUNT ORDERED <u>230 sks ASC,</u>	
<u>10% salt, 5# Gilsenite, 2% gal</u>	

PUMP TRUCK	CEMENTER <u>Paul Beaver</u>
# <u>120</u>	HELPER <u>Tyler Flippe</u>
BULK TRUCK	
# <u>600</u>	DRIVER <u>Adam Flipse</u>
BULK TRUCK	
#	DRIVER

COMMON	@	
POZMIX	@	
GEL	<u>4 sks</u>	@ <u>23.40</u> <u>93.60</u>
CHLORIDE	@	
ASC	<u>230 sks</u>	@ <u>26.90</u> <u>4807.00</u>
Gilsenite	<u>1150 #</u>	@ <u>.98</u> <u>1127.00</u>
Salt	<u>24 sks</u>	@ <u>26.35</u> <u>622.40</u>
	@	
WFR-II	<u>12 bbl</u>	@ <u>58.70</u> <u>704.40</u>
	@	
KLL	<u>1 gal</u>	@ <u>34.40</u> <u>34.40</u>
	@	
HANDLING <u>294.03 ft³</u>	@ <u>2.48</u>	<u>729.19</u>
MILEAGE <u>12.84 hrs @ 20 mix</u>	<u>2.60</u>	<u>667.68</u>
		TOTAL <u>8795.60</u>

REMARKS:

Run Pipe / Float equip, Break circ, Drop ball went through shoe @ 400 #
Circ 1 hr Pump 10 bbl KLL, mix 12 bbl WFR-II pump 5 bbl water, mix 30 sks in R.H. mix 20 sks, wash-up into pit release plug Displace w/ water, plug did land @ 1200 # lift pressure 800 #
Float did hold

Thank you!
Paul + Tyler

SERVICE

DEPTH OF JOB	<u>4495'</u>
PUMP TRUCK CHARGE	<u>2765.75</u>
EXTRA FOOTAGE	@
MILEAGE <u>mil HV</u>	<u>20</u> @ <u>7.70</u> <u>154.00</u>
MANIFOLD <u>Head</u>	@ <u>275.00</u> <u>N/A</u>
<u>NILV</u>	@ <u>4.40</u> <u>88.00</u>
	@
	TOTAL <u>3007.75</u>

CHARGE TO: Black Tea

STREET _____

CITY _____ STATE _____ ZIP _____

PLUG & FLOAT EQUIPMENT

<u>Weatherford</u>	<u>5 1/2</u>
Part collar	@ <u>3590.00</u>
AFU Float shoe	@ <u>545.00</u>
Letdown plug Assy	@ <u>600.00</u>
Turbolizers	<u>8</u> @ <u>95</u> <u>760.00</u>
Baskets	<u>3</u> @ <u>295</u> <u>1185.00</u>
	TOTAL <u>6740.00</u>

To: Allied Oil & Gas Services, LLC.
You are hereby requested to rent cementing equipment and furnish cementer and helper(s) to assist owner or contractor to do work as is listed. The above work was done to satisfaction and supervision of owner agent or contractor. I have read and understand the "GENERAL TERMS AND CONDITIONS" listed on the reverse side.

SALES TAX (If Any) _____

TOTAL CHARGES 18,543.35

DISCOUNT 2,360.67 IF PAID IN 30 DAYS

16,182.68 Net.

PRINTED NAME _____

SIGNATURE John C. [Signature]