

SKYY DRILLING LLC

DAILY DRILLING REPORT

OPERATOR Haas Petroleum, LLC

DATE 4/4 2014

LEASE NAME Phillips

LOCATION 2305 (EEL)/FWL 1355 (ESL)/FNL

(FROM SECTION LINE)

WELL NO. LIHP RIG NO. _____

SEC. 14 TWP 16 RA 21 COUNTY Miami

FORMATION	FROM	TO	FIRST TOWER:	HOURS WORKED
clay	0	4	DRILLER: _____	
shale	4	15	TOOL DRESSER: _____	
lime	15	17	REMARK: _____	
shale	17	20		
lime	20	25		
shale	25	100		
lime	100	125		
shale	125	215		
lime	215	230		
shale	230	260		
lime	260	275		
shale	275	300		
lime	300	320		

FORMATION	FROM	TO	SECOND TOWER:	HOURS WORKED
shale	320	350	DRILLER: _____	
lime	350	380	TOOL DRESSER: _____	
shale	380	390	REMARK: _____	
lime	390	400		
shale	400	410		
Big shale	410	565		
lime	565	570		
Big shale	570	630		
lime	630	650		
oil sand	650	652		
oil sand	652	663		
white sandy shale	663	680		
shale	680	720		
TD	720			



CONSOLIDATED
Oil Well Services, LLC

267533

TICKET NUMBER 47023

LOCATION Ottawa, KS

FOREMAN Casey Kennedy

PO Box 884, Chanute, KS 66720
620-431-9210 or 800-467-8676

FIELD TICKET & TREATMENT REPORT
CEMENT

DATE	CUSTOMER #	WELL NAME & NUMBER	SECTION	TOWNSHIP	RANGE	COUNTY
4/18/14	3451	Phillips # 1-HP	SE 14	16	21	M1

CUSTOMER
Haas Petroleum

MAILING ADDRESS
11551 Ash St Suite 205

CITY
Leawood

STATE
KS

ZIP CODE
66211

TRUCK #	DRIVER	TRUCK #	DRIVER
727	Casey	✓	Safety Meeting
666	Gar Moo	✓	
548	Mik Haa	✓	
370	Jas Ric	✓	

JOB TYPE long string HOLE SIZE 5 7/8" HOLE DEPTH 700' CASING SIZE & WEIGHT 2 7/8" EUE

CASING DEPTH 704' DRILL PIPE _____ TUBING _____ OTHER _____

SLURRY WEIGHT _____ SLURRY VOL _____ WATER gal/sk _____ CEMENT LEFT In CASING _____

DISPLACEMENT 4.09 bbls DISPLACEMENT PSI _____ MIX PSI _____ RATE 5 bpm

REMARKS: held safety meeting, established circulation, mixed + pumped 200 # Premium Gel followed by 10 bbls fresh water, mixed + pumped 112 sls 50/50 Pozmix cement w/ 2% gel per sk, cement to surface, flushed pump clean, pumped 2 1/2" rubber plug to casing TD w/ 4.09 bbls fresh water, pressured to 800 PSI, released to pressure, shut in casing.

Handwritten signature/initials

ACCOUNT CODE	QUANTITY or UNITS	DESCRIPTION of SERVICES or PRODUCT	UNIT PRICE	TOTAL
5401	1	PUMP CHARGE		1085.00 ✓
5406	20 mi	MILEAGE		84.00 ✓
5402	704'	casing footage		— ✓
5407	minimum	ton mileage		368.00 ✓
5502C	2 hrs	80 Vac		200.00 ✓
1124	112 sls	50/50 Pozmix cement	1288.00 ✓	
1118B	388 #	Premium Gel	85.36 ✓	
		materials	1373.36 ✓	
		-30%	412.01 ✓	
		Subtotal		961.35 ✓
4402	1	2 1/2" rubber plug		29.50 ✓
		<input checked="" type="checkbox"/> completed	3247.18	
		7.65%	SALES TAX	75.80 ✓
			ESTIMATED TOTAL	2803.65 ✓

Ravin 3737

AUTHORIZATION *Sten Jensen* TITLE _____ DATE _____

I acknowledge that the payment terms, unless specifically amended in writing on the front of the form or in the customer's account records, at our office, and conditions of service on the back of this form are in effect for services identified on this form.