



BASICSM
ENERGY SERVICES
PRESSURE PUMPING & WIRELINE

1700 S. Country Estates Rd.
Liberal, Kansas 67905
Phone 620-624-2277

FIELD SERVICE TICKET
1717 05680 A

DATE _____ TICKET NO. _____

DATE OF JOB: 3-17-14	DISTRICT: 1717	NEW WELL <input checked="" type="checkbox"/>	OLD WELL <input type="checkbox"/>	PROD <input type="checkbox"/>	INJ <input type="checkbox"/>	WDW <input type="checkbox"/>	CUSTOMER ORDER NO.:	
CUSTOMER: Oxy USA		LEASE: Enterprises A#5	WELL NO.:					
ADDRESS:		COUNTY: Haskell	STATE: KS					
CITY:	STATE:	SERVICE CREW: E Mendoza, S Chavez, C Garcia						
AUTHORIZED BY: J Bennett		JOB TYPE: 242-8 5/8" Surface						
EQUIPMENT#	HRS	EQUIPMENT#	HRS	EQUIPMENT#	HRS	TRUCK CALLED	DATE	TIME
34726	8						3-17-14	8:00
27462	8					ARRIVED AT JOB		12:00
3811	8					START OPERATION		6:00
37724	8					FINISH OPERATION		8:00
14355	8					RELEASED		9:00
37725	8					MILES FROM STATION TO WELL	30	mi

CONTRACT CONDITIONS: (This contract must be signed before the job is commenced or merchandise is delivered).

The undersigned is authorized to execute this contract as an agent of the customer. As such, the undersigned agrees and acknowledges that this contract for services, materials, products, and/or supplies includes all of and only those terms and conditions appearing on the front and back of this document. No additional or substitute terms and/or conditions shall become a part of this contract without the written consent of an officer of Basic Energy Services LP.

SIGNED: [Signature]
(WELL OWNER, OPERATOR, CONTRACTOR OR AGENT)

ITEM/PRICE REF. NO.	MATERIAL, EQUIPMENT AND SERVICES USED	UNIT	QUANTITY	UNIT PRICE	\$ AMOUNT
CL101	A-Con	sk	300	13.95	4185.00
CL110	Premium Plus	sk	245	12.23	2996.35
CC109	Calcium Chloride	lb	1308	.79	1033.32
CC102	Cellulose	lb	137	2.78	380.86
CC130	CS-1	lb	57	18.75	1068.75
CF253	Regular Guide Shoe	ea	1		285.00
CF1453	8 5/8" Insert		1		210.00
CF4405	Centralizer		17	108.75	1848.75
CF105	Plus		1		168.75
CF4109	Stop Collar		1		75.00
CF4556	Basket		1		987.50
CF3000	Thread Lock		12	25.50	306.00
	D20177				
	Enterprises A-5				
	0102		3023		
	1180081				

SUB TOTAL \$17078.48

CHEMICAL / ACID DATA:			

SERVICE & EQUIPMENT	%TAX ON \$	
MATERIALS	%TAX ON \$	
TOTAL		

SERVICE REPRESENTATIVE: [Signature]

THE ABOVE MATERIAL AND SERVICE ORDERED BY CUSTOMER AND RECEIVED BY: [Signature]

FIELD SERVICE ORDER NO. _____ (WELL OWNER OPERATOR CONTRACTOR OR AGENT)



Cement Report

Customer	Oxy USA	Lease No.		Date	3-17-14
Lease	Enterprises A	Well #	5	Service Receipt	05680
Casing	8 5/8" 24" Depth	County	Haskell	State	KS
Job Type	242-8 5/8" Surface	Formation		Legal Description	21-30-32

Pipe Data		Perforating Data		Cement Data
Casing size	8 5/8" Surface	Tubing Size		Lead 300 sk
Depth	1539'	Depth	From To	A Con
Volume	Disp - 95.5 bbl	Volume	From To	
Max Press	1500#	Max Press	From To	Tail in 245 sk
Well Connection	TD-1533'	Annulus Vol.	From To	Prem, Plus
Plug Depth	51-41'	Packer Depth	From To	

Time	Casing Pressure	Tubing Pressure	Bbls. Pumped	Rate	Service Log
12:30					on loc-site assessment (start csg)
3:00					spot tracks- rig up
4:00					csg on bottom break circ
4:30					safety meeting - JSA
5:00					pressure test 2000#
6:15	200		128	5	Mix + pump 300sk A-Con @ 12.1# - 2.40 A3sk
6:40	200		58.5	5	switch to tail 245 sk Premium Plus @ 14.8# - 1.34 A3sk
6:55	100		0	5	drop plug, disp csg
7:05	500		85	2	slow rate
7:10	1000		95	0	land plug float hold
					psi test csg 1500# 30 min - ok
					circ 75 bbl surface
					job complete

Service Units	34726	27462	3511-37724	14305-37725
Driver Names	A. Overa	E. Medina	S. Chavez	C. Garcia

C. Wylie
Customer Representative
J. Bennett
Station Manager
A. Overa
Cementer