



BASIC
ENERGY SERVICES
PRESSURE PUMPING & WIRELINE

1700 S. Country Estates Rd.
Liberal, Kansas 67905
Phone 620-624-2277

FIELD SERVICE TICKET
1717 05752 A

DATE _____ TICKET NO. _____

DATE OF JOB: 3-25-14		DISTRICT: 1717		NEW WELL <input checked="" type="checkbox"/> OLD WELL <input type="checkbox"/>		PROD <input type="checkbox"/> INJ <input type="checkbox"/> WDW <input type="checkbox"/>		CUSTOMER ORDER NO.:	
CUSTOMER: Oxy USA				LEASE: Hg 11				WELL NO.: 10	
ADDRESS:				COUNTY: Haskell		STATE: KS			
CITY:				STATE:		SERVICE CREW: Ruben - Carlos - Daniel - Gabriel			
AUTHORIZED BY: Tyre Davis				JOB TYPE: 2-24 8 5/8 Surface					
EQUIPMENT#	HRS	EQUIPMENT#	HRS	EQUIPMENT#	HRS	TRUCK CALLED	DATE	AM	TIME
				3875019842	12	3-25-14			0700
				1961519566	12	ARRIVED AT JOB		AM	0330
				14355-37725	12	START OPERATION		AM	1003
				78940	12	FINISH OPERATION		AM	1145
						RELEASED		AM	1200
						MILES FROM STATION TO WELL		PM	30

CONTRACT CONDITIONS: (This contract must be signed before the job is commenced or merchandise is delivered).

The undersigned is authorized to execute this contract as an agent of the customer. As such, the undersigned agrees and acknowledges that this contract for services, materials, products, and/or supplies includes all of and only those terms and conditions appearing on the front and back of this document. No additional or substitute terms and/or conditions shall become a part of this contract without the written consent of an officer of Basic Energy Services LP.

SIGNED: _____
(WELL OWNER, OPERATOR, CONTRACTOR OR AGENT)

ITEM/PRICE REF. NO.	MATERIAL, EQUIPMENT AND SERVICES USED	UNIT	QUANTITY	UNIT PRICE	\$ AMOUNT
CL 101	A - Con Blend	SK	300	13 95	4185 00
CL 110	Premium Plus	SK	245	12 23	2996 35
CC 165	SLS Polymer	gal	840	4 50	3780 00
CC 166	SLS LCM	Lb	396	3 94	1260 80
CC 109	Calcium Chloride	Lb	1308	79	1033 32
CC 102	Cellothake	Lb	137	2 78	380 86
CC 130	C-51	Lb	57	18 75	1068 75
CF 253	8 5/8 guide shoe	Eg	1		285 00
CF 1453	8 5/8 Insert float	Eg	1		210 00
CF 4405	8 5/8 Centralizer	Eg	17	108 75	1848 75
CF 4556	8 5/8 Basket	Eg	1		787 50
CF 105	8 5/8 Plug	Eg	1		168 75
CF 4105	8 5/8 Stop Collar	Eg	1		75 00
E 101	Heavy Equipment Mileage	Mi	90	5 25	472 50
CE 240	Blending & Mixing Charge	SK	545	1 05	572 25
E 113	Proppant & Bulk Delivery	Tm	770	1 20	924 00
CE 202	Depth Charge	4hrs	1		1125 00
CE 504	Plug Container Utilization	Job	1		187 50
E 100	pick up charge	Mi	30	3 19	95 70
SUB TOTAL					21588 28

CHEMICAL / ACID DATA:			

AP LOC: _____ SERVICE & EQUIPMENT %TAX ON \$ _____
 LEASE: _____ MATERIALS Hall #10 _____ %TAX ON \$ _____
 MAXIMO / VOL: _____ TOTAL _____
 TASK: 01-02 ELEMENT: 3023
 PROJECT: 1179700 CAPEX / OP&M - Circle one

SERVICE REPRESENTATIVE:	THE ABOVE MATERIAL AND SERVICE ORDERED BY CUSTOMER AND RECEIVED BY:
-------------------------	---

FIELD SERVICE ORDER NO. _____

SIGNATURE: _____ (WELL OWNER OPERATOR CONTRACTOR OR AGENT)



Cement Report

Customer Oxy USA		Lease No.		Date 3-25-14	
Lease Hall		Well # 10		Service Receipt	
Casing		Depth		County Haskell State KS	
Job Type		Formation		Legal Description 16-30-32	
Pipe Data			Perforating Data		Cement Data
Casing size 8 5/8 24#		Tubing Size		Shots/Ft	
Depth 1580'		Depth			
Volume 97.8 bbl		Volume		From	
Max Press		Max Press		To	
Well Connection 8"		Annulus Vol.		From	
Plug Depth 1538'		Packer Depth		To	
				Lead 300sx @ 12.1 PPG 31-cc, 1/4# Polyflake, 21-WCA-1	
				Tail in 245sx @ 14.8 PPG 21-cc, 1/4# Polyflake	
				Premium Plus Cement	
Time	Casing Pressure	Tubing Pressure	Bbls. Pumped	Rate	Service Log
0330					On Location
0600					Rig up
0930					Safety Meeting
1003	2000				Pressure Test
1004	200		20	5	Pump Stop Loss
1012	250		128	5	Pump 300sx @ 12.1 PPG
1033	250		58	5	Pump 245sx @ 14.8 PPG
1044					Drop Plug
1046	100			5	Start Displacement
1103	400		84	2	Slow Rate
1107	950		97.8	2	Bump Plug
1113	0				Release Pressure - float Held
1115	1500				Test Casing
1145	0				Release Pressure
1146					Shut Down - Rig Down
Service Units		3875019842		14355 37725 19615 19564	
Driver Names		Ruben		Carlos Daniel Gabriel	

Early

Customer Representative

Jerry Bennett

Station Manager

Ruben Martinez

Cementer