

FIELD SERVICE TICKET

1717 05658 A



1700 S. Country Estates Rd.
 Liberal, Kansas 67905
 Phone 620-624-2277

DATE _____ TICKET NO. _____

DATE OF JOB: <u>4/24/14</u>	DISTRICT: _____	NEW WELL <input type="checkbox"/>	OLD WELL <input checked="" type="checkbox"/>	PROD <input type="checkbox"/>	INJ <input type="checkbox"/>	WDW <input type="checkbox"/>	CUSTOMER ORDER NO.: _____
CUSTOMER: <u>Oxy USA</u>	LEASE: <u>Drussel E</u>	WELL NO. <u>5</u>					
ADDRESS: _____	COUNTY: <u>Finney</u>	STATE: <u>KS</u>					
CITY: _____	STATE: _____	SERVICE CREW: <u>Chad, Tommy, Daniel, Norm</u>					
AUTHORIZED BY: <u>Tyce Davis</u>	STATE: _____	JOB TYPE: <u>Squeeze</u>					
EQUIPMENT#	HRS	EQUIPMENT#	HRS	EQUIPMENT#	HRS	TRUCK CALLED	DATE: <u>4/24/14</u> AM/PM: _____ TIME: <u>5:00</u>
<u>78939</u>	<u>3 1/2</u>					ARRIVED AT JOB	AM/PM: _____ TIME: <u>7:00</u>
<u>34223/37726</u>	<u>3 1/2</u>					START OPERATION	AM/PM: _____ TIME: <u>8:00</u>
<u>4355/37725</u>	<u>3 1/2</u>					FINISH OPERATION	AM/PM: _____ TIME: <u>11:25</u>
						RELEASED	AM/PM: _____ TIME: <u>11:5</u>
						MILES FROM STATION TO WELL	<u>60</u>

CONTRACT CONDITIONS: (This contract must be signed before the job is commenced or merchandise is delivered).

The undersigned is authorized to execute this contract as an agent of the customer. As such, the undersigned agrees and acknowledges that this contract for services, materials, and/or supplies includes all of and only those terms and conditions appearing on the front and back of this document. No additional or substitute terms and/or conditions become a part of this contract without the written consent of an officer of Basic Energy Services LP.

SIGNED: [Signature]
 (WELL OWNER, OPERATOR, CONTRACTOR OR AGENT)

ITEM/PRICE REF. NO.	MATERIAL, EQUIPMENT AND SERVICES USED	UNIT	QUANTITY	UNIT PRICE	\$ AMOUNT
CL100	Premium Common	SK	100	12.00	1200
CL100	Premium Common	SK	0		
CE109	Calcium Chloride	CB	0		
E101	Heavy Equipment Mileage	mi	120	5.25	630
CE240	Blending & Mixing Service Charge	SK	300	1.05	315
E113	Proppant and Bulk Delivery Charge	TM	846	1.20	1015
CE205	Depth Charge 4001-5000'	4hrs	1		1890
E100	Unit Mileage Small Pickup	mi	60	3.19	191
3003	Service Supervisor first 8 hrs on job	ea	1		131

AP LOCATION/DEPT: Libecsp D02 NON D02
 LEASE/WELL/FAC: Drussel E-5
 MAXIMO / WSM #: OLB01DX7
 TASK: 0103 ELEMENT: 3023
 PROJECT #: 1180140 CAPEX/OPEX - Circle One
 SPO / BPA: _____ UNSUPPORTED
 PRINTED NAME: WES WILLIMON
 SIGNATURE: [Signature]

I certify that these Services/Materials have been received

SUB TOTAL 5342

SERVICE & EQUIPMENT	%TAX ON \$
MATERIALS	%TAX ON \$
TOTAL	

SERVICE REPRESENTATIVE: Tommy Marullo
 FIELD SERVICE ORDER NO. _____

THE ABOVE MATERIAL AND SERVICE ORDERED BY CUSTOMER AND RECEIVED BY: [Signature]
 (WELL OWNER OPERATOR CONTRACTOR OR AGENT)

NO TO SUBSCRIBE REFER
3539 KA PAMUOJAC
NO TO SUBSCRIBE REFER

ASICSM

ENERGY SERVICES
Liberal, Kansas

Cement Report

Customer Okgr USA		Lease No.		Date 4/24/14	
Lease Drussel E		Well # 5		Service Receipt	
Casing 5 1/2 17#	Depth 4518	County Finney		State KS	
Job Type Squeeze	Formation	Legal Description			

Pipe Data			Perforating Data			Cement Data	
Casing size 5 1/2 17#	Tubing Size 2 5/8		Shots/Ft		Lead		
Depth 4518	Depth 4400	From	To		100 SK 3 Premium		
Volume 2.6482	Volume 17.0280	From	To		1.0847/c 4.35gal/		
Max Press 2000 psi	Max Press 2000 psi	From	To		Tail in		
Well Connection Surge	Annulus Vol. 78.32	From	To				
Plug Depth 4520	Packer Depth 4400.4	From	To				

Time	Casing Pressure	Tubing Pressure	Bbls. Pumped	Rate	Service Log
7:00					On location
8:00					Spot in / Safety Meeting
8:12					Rig up
8:38					Prime up
8:45					Spot Sand + 1 BBL Water
9:04	500 psi		40 1/2 BBL	2 BPM	load Backside
9:36					Pressure Test Manifold 2000 psi
9:58	330 psi		11 BBL	2 BPM	Establish Rate
9:42	270 psi		19.4 BBL	2 BPM	Start Cement
9:56					Shut in + Washup to Pit
10:04	0			.36 BPM	Start Displacement Roll Idle Pump
10:14	0		10 BBL	0 BPM	Shut down Gravity only
10:20	0			.34 BPM	Roll Idle
10:21	100 psi		10 1/2 BBL	.30 BPM	
10:27	750 psi		12 1/2 BBL	.3	
10:30	750 psi		13 1/2 BBL	.3	
10:34	1500 psi		14 1/4 BBL	0	Shut down pressure come down to 1300
10:42	1650 psi		14 1/2 BBL	0	Shut down + flow back 1/4 BBL
10:59	1680 psi		30 BBL	7	Rev. Out
11:15					shut down Pull 5 stands
11:26	1000 psi				pressure upon tubing

Service Units	37223/37426	1982#/1985	178939		
Driver Names	Tommy Havelles	Daniel Beck	Chad Hinz		

Andy Weis Customer Representative
 Jerry Bennett Station Manager
 Tommy Havelles Cementer