

810 E 7<sup>TH</sup>  
 PO Box 92  
 EUREKA, KS 67045  
 (620) 583-5561

**Elite**

**Cementing & Acidizing  
 of Kansas, LLC**



**Cement or Acid Field Report**

Ticket No. **1173**  
 Foreman Rick Ladford  
 Camp Eureka Ks

Date	Cust. ID #	Lease & Well Number	Section	Township	Range	County	State	
4/2/14	1049	Chism 14-2	2	323	13E	MG	KS	
Customer LR Energy Inc.			Safety Meeting Unit # 102		Driver Chris B.		Unit #	Driver
Mailing Address 5602 CR 2700			111		Rudy M.			
City EIK City		State Ks	Zip Code 67344					

Job Type 1/3 Hole Depth 1462' Slurry Vol. 51 Bbl Tubing \_\_\_\_\_  
 Casing Depth 1421' Hole Size 6 3/4" Slurry Wt. 13.7" Drill Pipe \_\_\_\_\_  
 Casing Size & Wt. 4 1/2" Cement Left in Casing 0' Water Gal/SK 9.0 Other \_\_\_\_\_  
 Displacement 22.6 Bbl Displacement PSI 600 Bump Plug to 1000 BPM \_\_\_\_\_

Remarks: Safety meeting. Rig up to 4 1/2" casing. Break circulation w/ 28 Bbl fresh water. Pump 16 sacks gel-flush, 10 Bbl water spacer. Mixed 155 sacks thickset cement w/ 5" Kel-seal/sk + 1" phenoseal/sk @ 13.7"/gal. yield 1.85, washout pump + lines, release plug. Displace w/ 22.6 Bbl fresh water. Final pump pressure 600 PSI. Bump plug to 1000 PSI. release pressure, float + plug held. Good cement, returns to surface = 10 Bbl slurry topit. Job complete Rig down.

Thank You

Code	Qty or Units	Description of Product or Services	Unit Price	Total
C102	1	Pump Charge	1050.00	1050.00
C107	50	Mileage	3.95	197.50
C201	155 sks	thickset cement	19.50	3022.50
C207	775 "	5" Kel-seal/sk	.45	348.75
C208	755 "	1" phenoseal/sk	1.25	193.75
C206	500 "	gel-flush	.20	100.00
C107B	8.53	ton mileage bulk tax	1.35	575.78
C403	1	4 1/2" top rubber plug	45.00	45.00
			Subtotal	5533.28
			Sales Tax	228.17
Authorization <u>[Signature]</u> Title <u>PS</u>			Total	5761.45

I agree to the payment terms and conditions of services provided on the back of this job ticket. Any amendments to payment terms must be in writing on the front of this job ticket or in the Customer's records at ELITE's office.