



BASIC
ENERGY SERVICES
PRESSURE PUMPING & WIRELINE

1700 S. Country Estates Rd.
Liberal, Kansas 67905
Phone 620-624-2277

FIELD SERVICE TICKET
1717 05807 A

DATE _____ TICKET NO. _____

DATE OF JOB: 5-5-14	DISTRICT: 1717	NEW WELL <input checked="" type="checkbox"/>	OLD WELL <input type="checkbox"/>	PROD <input type="checkbox"/>	INJ <input type="checkbox"/>	WDW <input type="checkbox"/>	CUSTOMER ORDER NO.:			
CUSTOMER: Merit Energy	ADDRESS: J	LEASE: Alexander H #2	WELL NO.:							
CITY:	STATE:	COUNTY: Haskell	STATE: KS							
AUTHORIZED BY: J Bennett JRB	SERVICE CREW: E Mendoza, S Chavez, G Echa		JOB TYPE: 742-8 5/8" Surface							
EQUIPMENT#	HRS	EQUIPMENT#	HRS	EQUIPMENT#	HRS	TRUCK CALLED	DATE	AM	PM	TIME
34726	8						5-5-14			1:30
27462	8									3:30
30463	8									10:45
19566	8									12:30
19827	8									2:00
19883	8									8:00
						MILES FROM STATION TO WELL	85			MI

CONTRACT CONDITIONS: (This contract must be signed before the job is commenced or merchandise is delivered).

The undersigned is authorized to execute this contract as an agent of the customer. As such, the undersigned agrees and acknowledges that this contract for services, materials, products, and/or supplies includes all of and only those terms and conditions appearing on the front and back of this document. No additional or substitute terms and/or conditions shall become a part of this contract without the written consent of an officer of Basic Energy Services LP.

SIGNED:
(WELL OWNER, OPERATOR, CONTRACTOR OR AGENT)

ITEM/PRICE REF. NO.	MATERIAL, EQUIPMENT AND SERVICES USED	UNIT	QUANTITY	UNIT PRICE	\$ AMOUNT
CL101	A-Con	sk	340		6324 00
CL110	Premium Plus	sk	245		3993 50
CL109	Calcium Chloride	lb	1422		1493 10
CL102	Cell Flake	lb	147		543 90
CL130	C-51	lb	64		1600 00
CF253	8 5/8 Regular Guide Shoe	ea	1		380 00
CF453	Flapper Type Insert		1		280 00
CF4405	Centralizer		14		2030 00
CF4109	Stop Collar		1		100 00
CF3000	Thread Lock		12		408 00
E101	Heavy Equipment Mileage	mi	255		1785 00
CE240	Slurry & Mix Service	sk	585		819 00
E113	Proppant - Bulk Delivery	ton/mi	2342		5151 85
CE202	Pump Parts 001-20000	4hr	1		1500 00
CE804	Pug Container	ea	1		250 00
E100	Unit Mileage	mi	85		361 25
S003	Service Supervisor	ea	1		175 00
CE803	High Head 12'	ea	1		300 00

AFE# 034160

SUB TOTAL \$ 20620.85

CHEMICAL / ACID DATA:			

SERVICE & EQUIPMENT	%TAX ON \$	
MATERIALS	%TAX ON \$	
TOTAL		

SERVICE REPRESENTATIVE:

THE ABOVE MATERIAL AND SERVICE ORDERED BY CUSTOMER AND RECEIVED BY:
(WELL OWNER OPERATOR CONTRACTOR OR AGENT)

FIELD SERVICE ORDER NO. _____



BASIC™
ENERGY SERVICES
Liberal, Kansas

Cement Report

Customer	Merit Energy	Lease No.		Date	5-5-14
Lease	Alexander A	Well #	2	Service Receipt	05807
Casing	8 5/8" 24#	County	Waskell	State	KS
Job Type	242 8 5/8" surface	Formation		Legal Description	33-27-34

Pipe Data		Perforating Data		Cement Data
Casing size	8 5/8" 24#	Tubing Size		Lead
Depth	1800'	Depth	From To	340 sk A-Con
Volume	112 bbl	Volume	From To	
Max Press	1500#	Max Press	From To	Tail in
Well Connection	10-1890'	Annulus Vol.	From To	245 sk Premium Plus
Plug Depth	SI-40'	Packer Depth	From To	

Time	Casing Pressure	Tubing Pressure	Bbls. Pumped	Rate	Service Log
4:00					on loc-site assessment
8:00					spot trucks - rig up
4:30					start csg + float equipment
9:00					csg on btm, break circ
10:00					safety meeting ISA
10:15					pressure test 2000#
10:45	200		148.3	5	mix + pump 340 sk ACon w/ 3% CC, 1/4# PF, 2% WCA I 12.1 pp - 2.40 A3 sk 14.0 g/sk
11:15	150		58.5	5	switch to fail 245 sk Prem. Plus w/ 2% CC, 1/4 PF 14.8 pp 1.34 g/sk
11:30	100		0	5	drop plug, disp csg
	100		40	0	slow rate, leak in collar fix it continue pump, with caution
12:15	600		100	2	slow rate
12:30	800		112.1	0	land plug, float held circ 74 bbl cut slurry to surface
					job complete did not test csg leak in collar

Service Units	34776	27462	30463	19866	19827	19883
Driver Names	A. Rivera	B. Mendez	S. Chavez	G. Beltrami		

T. Ballew
Customer Representative

T. Bennett
Station Manager