



**BASIC**<sup>SM</sup>  
ENERGY SERVICES  
PRESSURE PUMPING & WIRELINE

1700 S. Country Estates Rd.  
Liberal, Kansas 67905  
Phone 620-624-2277

FIELD SERVICE TICKET  
1717 05790 A

DATE \_\_\_\_\_ TICKET NO. \_\_\_\_\_

DATE OF JOB <b>5-28-14</b> DISTRICT <b>1717</b>		NEW WELL <input checked="" type="checkbox"/> OLD WELL <input type="checkbox"/> PROD <input type="checkbox"/> INJ <input type="checkbox"/> WDW <input type="checkbox"/> CUSTOMER ORDER NO.:				
CUSTOMER <b>Ment Energy</b>		LEASE <b>Dreyer C</b>		WELL NO. <b>1</b>		
ADDRESS		COUNTY <b>Haskell</b>		STATE <b>KS</b>		
CITY STATE		SERVICE CREW <b>Ruben, Carlos, Daniel, Roger</b>				
AUTHORIZED BY <b>Tyce Davis JH</b>		JOB TYPE: <b>2-42 8 5/8 Surface</b>				
EQUIPMENT#	HRS	EQUIPMENT#	HRS	EQUIPMENT#	HRS	TRUCK CALLED <b>5-28-14</b> DATE AM PM TIME <b>2400</b>
				<b>78940</b>	<b>12</b>	ARRIVED AT JOB AM PM <b>0200</b>
				<b>38750 19842</b>	<b>12</b>	START OPERATION AM PM <b>0953</b>
				<b>14355 37225</b>	<b>12</b>	FINISH OPERATION AM PM <b>1138</b>
				<b>30463 19544</b>	<b>12</b>	RELEASED AM PM <b>1200</b>
						MILES FROM STATION TO WELL <b>85</b>

CONTRACT CONDITIONS: (This contract must be signed before the job is commenced or merchandise is delivered).

The undersigned is authorized to execute this contract as an agent of the customer. As such, the undersigned agrees and acknowledges that this contract for services, material products, and/or supplies includes all of and only those terms and conditions appearing on the front and back of this document. No additional or substitute terms and/or conditions shall become a part of this contract without the written consent of an officer of Basic Energy Services LP.

SIGNED: \_\_\_\_\_  
(WELL OWNER, OPERATOR, CONTRACTOR OR AGENT)

ITEM/PRICE REF. NO.	MATERIAL, EQUIPMENT AND SERVICES USED	UNIT	QUANTITY	UNIT PRICE	\$ AMOUNT
CL 101	A-Con Blend ✓	SK	340		6324 0
CL 110	Premium Plus Cement ✓	SK	245		3993 5
CC 109	Calcium Chloride ✓	Lb	1422		1493 11
CC 102	Celloflake ✓	Lb	147		543 9
CC 130	C-51 ✓	Lb	64		1600 0
CF 253	8 5/8 Guide Shoe ✓	Eq	1		380 0
CF 1453	8 5/8 Insert float valve ✓	Eq	1		280 0
CF 4405	8 5/8 Centralizer S ✓	Eq	14		2030 0
CF 4109	8 5/8 Stop collar ✓	Eq	1		100 0
CF 105	8 5/8 Cement Plug ✓	Eq	1		225 0
E 101	Heavy Mileage Equipment	M:	7		1200 0
CE 240	Blending & Mixing Charge	SK	585		819 0
E 113	Proppant & Bulk Delivery Charges	TM	2342		5151 8
CE 202	Depth Charge 1001 - 2000'	4hrs	1		1500 0
CE 504	Plug Container Utilization	Job	1		250 0
E 100	Pick up Charge	M:	85 00		255 00
S003	Service Supervisor	Eq	1		175 0
T 105	Cement Data	Eq	1		550 0
CE 503	High Head Charge	Eq	1		225 0
SUB TOTAL					<b>20036 3</b>

CHEMICAL / ACID DATA:			

SERVICE & EQUIPMENT	%TAX ON \$	
MATERIALS	%TAX ON \$	
TOTAL		

AFE# 034241

SERVICE REPRESENTATIVE <b>Ruben Math</b>	THE ABOVE MATERIAL AND SERVICE ORDERED BY CUSTOMER AND RECEIVED BY <b>Earl J.</b> (WELL OWNER OPERATOR CONTRACTOR OR AGENT)
FIELD SERVICE ORDER NO.	





# Cement Report

Customer	Merit Energy		Lease No.			Date	5-28-14		
Lease	Dreyer 'C'		Well #	1		Service Receipt			
Casing	8 5/8 24#	Depth	1810.87'		County	Haskell		State	KS
Job Type	Z-42		Formation			Legal Description	20-27-34		

Pipe Data		Perforating Data		Cement Data
Casing size	8 5/8 24#	Tubing Size	Shots/Ft	
Depth	1810.87'	Depth	From	To
Volume	112.5 bbl	Volume	From	To
Max Press		Max Press	From	To
Well Connection	1769.32'	Annulus Vol.	From	To
Plug Depth	1769.32'	Packer Depth	From	To

Lead 3405xe 12.1 PPS  
 37. cc, 1/4# Polyflake,  
 27. WCA-1  
 A-Cen Blend  
 Tail in 2455xe 14.8 PPS  
 27. cc,  
 44# Polyflake  
 Premium Plus Cement

Time	Casing Pressure	Tubing Pressure	Bbbs. Pumped	Rate	Service Log
0200					On Location
0900					Rig up
0930					Safety Meeting
0953	2500				Pressure Test
0955	150		145	5	Pump 3405xe 12.1 PPS
1026	200		58	5	Pump 2455xe 14.8 PPS
1037					Drop Plug
1039	150			5	Start Displacement
1058	500		<del>500</del> 100	2	Slow Rate
1103	1050		112	2	Bump Plug
1108	0				Release Pressure - float held
1108	1500				Casing Test
1138	0				Release Pressure - Casing held
					Shut Down - Rig Down

Service Units	78940	38750 19847	30463 12566	14355 37225	
Driver Names	Ruben	Carlos	Daniel	Roger	

Early Customer Representative     
 Jerry Bennett Station Manager     
 Ruben Martinez Cementer