



**BASIC**<sup>SM</sup>  
ENERGY SERVICES  
PRESSURE PUMPING & WIRELINE

1700 S. Country Estates Rd.  
Liberal, Kansas 67905  
Phone 620-624-2277

FIELD SERVICE TICKET  
1717 05892 A

DATE OF JOB: 7-4-14	DISTRIC: 1717	NEW WELL <input checked="" type="checkbox"/>	OLD WELL <input type="checkbox"/>	PROD <input type="checkbox"/>	INJ <input type="checkbox"/>	WDW <input type="checkbox"/>	CUSTOMER ORDER NO.:		
CUSTOMER: Merit Energy	LEASE: Warner G #2		WELL NO.:						
ADDRESS:	COUNTY: Haskell	STATE: KS							
CITY: S	SERVICE CREW: E Mendoza, T DeHuib, M Bosny								
AUTHORIZED BY: J Bennett	JOB TYPE: 242-858 Surface								
EQUIPMENT#	HRS	E	HRS	EQUIPMENT#	HRS	TRUCK CALLED	DATE	AM	TIME
81726	8						7-4-14	AM	5:00
27463	8					ARRIVED AT JOB		AM	8:00
27808	8					START OPERATION		AM	10:00
37724	8					FINISH OPERATION		AM	11:00
30454	8					RELEASED		AM	12:00
19578	8					MILES FROM STATION TO WELL		AM	50 mi

CONTRACT CONDITIONS: (This contract must be signed before the job is commenced or merchandise is delivered).

The undersigned is authorized to execute this contract as an agent of the customer. As such, the undersigned agrees and acknowledges that this contract for services, materials, products, and/or supplies includes all of and only those terms and conditions appearing on the front and back of this document. No additional or substitute terms and/or conditions shall become a part of this contract without the written consent of an officer of Basic Energy Services LP.

SIGNED: \_\_\_\_\_  
(WELL OWNER, OPERATOR, CONTRACTOR OR AGENT)

ITEM/PRICE REF. NO.	MATERIAL, EQUIPMENT AND SERVICES USED	UNIT	QUANTITY	UNIT PRICE	\$ AMOUNT
CL101	A-Con	sk	340		6324 00
CL110	Premium Plus	sk	245		3993 50
CC109	Calcium Chloride	lb	1422		1493 10
CC102	Cellulose	lb	147		543 90
CC130	CS	lb	64		1600 00
CE253	8 5/8 Shoe	ea	1		380 00
CE453	Insert	I	1		280 00
CE440	Centralizer	I	14		2 00
CE4109	Stop Collar	I	1		1 00
CE105	Plug	I	1		225
E101	Heavy Equipment Mileage	mi	150		105 00
CE240	Blandly & Murphy Service	sk	585		819 00
E113	Proppant Bulk Delivery	ton/yr	1378		3030 5
CE202	Pump Depth 1001-2000	hr	1		1500 0
CE503	fish head &	ea	1		300 00
CE504	Pipe Connector	ea	1		250 00
E100	Unit Mileage	mi	50		21 50
S003	Service Supervisor	ea	1		1750

CHEMICAL / ACID DATA:			

MATERIALS	%TAX ON \$

AFE # 34370

SERVICE REPRESENTATIVE: <i>Paul Garcia</i>	THE ABOVE MATERIAL AND SERVICE ORDERED BY CUSTOMER AND RECEIVED BY: <i>[Signature]</i>
FIELD SERVICE ORDER NO.:	OPERATOR OR



### Cement Report

Customer <b>Merit Energy</b>		Lease No.		Date <b>7-9-14</b>	
Lease <b>Warner 61</b>		Well # <b>2</b>		Service Receipt <b>05892</b>	
Casing <b>8 5/8" 24#</b>		Depth <b>1746'</b>		County <b>Maskell</b> State <b>KS</b>	
Job Type <b>242-8 5/8" surface</b>		Formation		Legal Description <b>26-27-34</b>	
<b>Pipe Data</b>			<b>Perforating Data</b>		<b>Cement Data</b>
Casing size <b>8 5/8" 24#</b>	Tubing Size		<b>Shots/Ft</b>		Lead <b>340 sk A-Cen</b>
Depth <b>1746'</b>	Depth	From	To		
Volume <b>Disp-109 bbl</b>	Volume	From	To		
Max Press <b>1500#</b>	Max Press	From	To		Tail in <b>245 sk Prem. Plus</b>
Well Connection <b>ID-1738'</b>	Annulus Vol.	From	To		
Plug Depth <b>SJ-37'</b>	Packer Depth	From	To		
Time	Casing Pressure	Tubing Pressure	Bbls. Pumped	Rate	Service Log
<b>8:00</b>					on loc-site assessment spot trucks-rig up CSG on btwn break circ safety meeting-TSA
<b>10:30</b>					pressure tests 2000 #
<b>10:30</b>			<b>145.3</b>	<b>5</b>	Mix + pump 340 sk A-Cen c 12.1# - 2.40 ft 3/4
<b>10:55</b>			<b>58.5</b>	<b>5</b>	switch to tail 245 sk Prem. Plus @ 14.8# - 1.34 ft 3/4
<b>11:05</b>	<b>0</b>		<b>0</b>	<b>5</b>	drop plug, disp CSG
<b>11:25</b>	<b>600</b>		<b>100</b>	<b>2</b>	slow rate
<b>11:30</b>	<b>1100</b>	<b>1</b>	<b>109</b>	<b>0</b>	land plug, float held job complete
<b>12:00</b>					circ cont to surface 30 min CSG test 1500 - OK
Service Units	<b>34726</b>	<b>27462</b>	<b>27805</b>	<b>37724</b>	<b>30454-14578</b>
Driver Names	<b>A Dura</b>	<b>E Mulvan</b>	<b>M Bosquez</b>	<b>T Peltola</b>	

E Zion  
Customer Representative

J Bennett  
Station Manager