



# ALLIED OIL & GAS SERVICES, LLC 064002

Federal Tax I.D. # 20-8651475

REMIT TO P.O. BOX 93999  
SOUTHLAKE, TEXAS 76092

SERVICE POINT:  
Oakley Ks

DATE <u>5-29-14</u>	SEC <u>26</u>	TWP. <u>14</u>	RANGE <u>32</u>	CALLED OUT	ON LOCATION <u>1:30pm</u>	JOB START <u>4:30pm</u>	JOB FINISH <u>5:00pm</u>
LEASE <u>Woods R</u>	WELL # <u>85</u>	LOCATION <u>Oakley 21 S E, S, E into</u>			COUNTY <u>Logan</u>	STATE <u>Ks</u>	
OLD OR <u>NEW</u> (Circle one)							

CONTRACTOR <u>Landmark 5</u>	OWNER <u>Same</u>
TYPE OF JOB <u>Production (long string)</u>	
HOLE SIZE <u>7 7/8</u>	T.D. <u>4526'</u>
CASING SIZE <u>5 1/2</u>	DEPTH <u>4524'</u>
TUBING SIZE	DEPTH
DRILL PIPE	DEPTH
TOOL Port Collar	DEPTH <u>2142'</u>
PRES. MAX	MINIMUM
MEAS. LINE	SHOE JOINT <u>18.05'</u>
CEMENT LEFT IN CSG. <u>18.05'</u>	
PERFS.	
DISPLACEMENT <u>107.24 bbl water</u>	
EQUIPMENT	

PUMP TRUCK # <u>120</u>	CEMENTER <u>Paul Beaver</u>
BULK TRUCK # <u>566/595</u>	HELPER <u>Tyler Flipse</u>
BULK TRUCK #	DRIVER <u>Ramona (TWS)</u>
BULK TRUCK #	DRIVER

CEMENT AMOUNT ORDERED <u>230 sks ASC 10% salt</u>	
<u>5# gilsonite 2% gel, 12 bbl super flush,</u>	
<u>10# bbl KCL water</u>	
COMMON	@
POZMIX	@
GEL <u>4 sks</u>	@ <u>23.40</u> <u>93.60</u>
CHLORIDE	@
ASC <u>230 sks</u>	@ <u>20.90</u> <u>4807.00</u>
<u>salt</u>	@ <u>26.35</u> <u>632.40</u>
<u>gilsnite</u>	@ <u>1150#</u> <u>.98</u> <u>1127.00</u>
<u>KCL</u>	@ <u>1 gal</u> <u>34.40</u>
<u>WFR-II</u>	@ <u>12 bbl</u> <u>58.70</u> <u>704.40</u>
HANDLING <u>294.03 @</u>	@ <u>2.48</u> <u>729.19</u>
MILEAGE <u>12.84 @ 25 mi x 2.60</u>	@ <u>834.60</u>
TOTAL <u>7,398.20</u>	

REMARKS:  
Run Pipe / Float equip. Drop ball, pumped ball through shoe @ 600# mix 12 bbl super flush Pump to bit KCL water, pump 5 bbl water spacer, mix 30 sks in R.H. Mix 200 sks down casing, washing into pit, release plug. Displace w/ water Plug did hand @ 1400# w 960# Lift, Float did hold  
Thank You!

Material Total		TOTAL
(1,479.76 / 20%)		
SERVICE		
DEPTH OF JOB <u>4526'</u>		
PUMP TRUCK CHARGE		<u>2765.75</u>
EXTRA FOOTAGE	@	
MILEAGE MILV <u>25</u>	@ <u>7.90</u>	<u>197.50</u>
MANIFOLD <u>head</u>	@	<u>225.00</u>
<u>MILV</u>	@ <u>25</u>	<u>4.40</u>
(981.40 / 20%)		<u>4,907.01</u>
		TOTAL

CHARGE TO: Black Tea Oil  
STREET \_\_\_\_\_  
CITY \_\_\_\_\_ STATE \_\_\_\_\_ ZIP \_\_\_\_\_

To: Allied Oil & Gas Services, LLC.  
You are hereby requested to rent cementing equipment and furnish cementer and helper(s) to assist owner or contractor to do work as is listed. The above work was done to satisfaction and supervision of owner agent or contractor. I have read and understand the "GENERAL TERMS AND CONDITIONS" listed on the reverse side.

PLUG & FLOAT EQUIPMENT		
<u>Weatherford</u>	<u>5 1/2</u>	
AFB Float shoe	@	<u>545.00</u>
Latch down plug Assy	@	<u>660.00</u>
Nurbs 112US	@ <u>8</u>	<u>95.00</u> <u>760.00</u>
Baskets	@ <u>3</u>	<u>385.00</u> <u>1185.00</u>
Port Collar	@	<u>3570.00</u>
(0%)		TOTAL <u>6,740.00</u>

PRINTED NAME \_\_\_\_\_  
SIGNATURE [Signature]

SALES TAX (If Any) \_\_\_\_\_  
TOTAL CHARGES 19,045.81  
DISCOUNT 2,461.16 (20%) IF PAID IN 30 DAYS  
16,584.67 Net.