



BASICSM
ENERGY SERVICES
PRESSURE PUMPING & WIRELINE

1700 S. Country Estates Rd.
Liberal, Kansas 67905
Phone 620-624-2277

FIELD SERVICE TICKET
1717 05817 A

DATE _____ TICKET NO. _____

DATE OF JOB: 5-21-14	DISTRICT: 1717	NEW WELL <input checked="" type="checkbox"/>	OLD WELL <input type="checkbox"/>	PROD <input type="checkbox"/>	INJ <input type="checkbox"/>	WDW <input type="checkbox"/>	CUSTOMER ORDER NO.:			
CUSTOMER: Merit Energy		LEASE: Alexander H #1				WELL NO.:				
ADDRESS:		COUNTY: Haskell		STATE: KS						
CITY:		STATE:		SERVICE CREW: E Mendoza, D Beck, J DeAvila						
AUTHORIZED BY: J Bennett		JOB TYPE: 242 85/8" Surface								
EQUIPMENT#	HRS	EQUIPMENT#	HRS	EQUIPMENT#	HRS	TRUCK CALLED	DATE	AM	PM	TIME
34726	8						5-21-14			10:00
27462	8					ARRIVED AT JOB				12:00
27808	8					START OPERATION				11:30
37724	8					FINISH OPERATION				1:00
19827	8					RELEASED				2:00
19883	8					MILES FROM STATION TO WELL	85			mi

CONTRACT CONDITIONS: (This contract must be signed before the job is commenced or merchandise is delivered).

The undersigned is authorized to execute this contract as an agent of the customer. As such, the undersigned agrees and acknowledges that this contract for services, materials, products, and/or supplies includes all of and only those terms and conditions appearing on the front and back of this document. No additional or substitute terms and/or conditions shall become a part of this contract without the written consent of an officer of Basic Energy Services LP.

SIGNED:
(WELL OWNER, OPERATOR, CONTRACTOR OR AGENT)

ITEM/PRICE REF. NO.	MATERIAL, EQUIPMENT AND SERVICES USED	UNIT	QUANTITY	UNIT PRICE	\$ AMOUNT
CL101	A Con	sk	340		6324 00
CL110	Premium Plus	sk	245		3993 50
CL109	Calcium Chloride	lb	1422		1493 10
CL102	Cellulose	lb	147		543 90
CL130	C-51	lb	64		1600 00
CF253	85/8" Regular Guide Shoe	ea	1		350 00
CF1453	Insert Float	l	1		250 00
CF4405	Centralizers	l	14		2030 00
CF4109	Stop Collar	l	1		100 00
CF105	Plug	l	1		225 00
E101	Heavy Equipment Mileage	mi	255		1785 00
CE240	Blending & Mixing Service	sk	585		819 00
E113	Proppant - Bulk Delivery	ton/mi	2342		5151 85
CE202	Pump Depth 1001-2000'	4hr	1		1500 00
CE503	High Head 8"	ea	1		300 00
CE504	Plug Container	ea	1		250 00
E100	Unit Mileage	mi	85		361 25
S003	Service Supervisor	ea	1		175 00
CE403	Additional hours on loc.	ea	4		2000 00
SUB TOTAL					21983.70

CHEMICAL / ACID DATA:			

SERVICE & EQUIPMENT	%TAX ON \$	
MATERIALS	%TAX ON \$	
TOTAL		

AFE# 034244

SERVICE REPRESENTATIVE:	THE ABOVE MATERIAL AND SERVICE ORDERED BY CUSTOMER AND RECEIVED BY:
FIELD SERVICE ORDER NO.:	(WELL OWNER OPERATOR CONTRACTOR OR AGENT)



Cement Report

Customer	Merit Energy	Lease No.		Date	5-21-14
Lease	Alexander	Well #	1	Service Receipt	05817
Casing	8 5/8" 24#	Depth	1806'	County	Haskell
Job Type	242 8 5/8" Surface	Formation		State	KS
		Legal Description	33-27-34		

Pipe Data		Perforating Data		Cement Data
Casing size	8 5/8" 24#	Tubing Size		Lead 340 sk
Depth	1806'	From	To	A-Con
Volume	113 bbl	From	To	
Max Press	1500#	From	To	Tail in 245 sk
Well Connection	10-1798'	Annulus Vol.	From	To
Plug Depth	85-42'	Packer Depth	From	To
				Class C

Time	Casing Pressure	Tubing Pressure	Bbls. Pumped	Rate	Service Log
12:00 AM					on loc-site assessment (wood tank)
10:00 AM					spot trucks-rig up
4:00					start csg + float equip
9:30					csg on bit break circ
11:00					safety meeting - JSA
11:30					pressure test 2000#
11:35	100		145.3	5	mix + pump 340 sk A-Con w/ 3% CC, 1/4# DF, 2% WMA-1 @ 12.1# - 2.40 #/sk
12:05	150		58.5	5	switch to tail 245 sk Premium Plus w/ 2% CC, 1/4# DF @ 14.8# - 1.34 #/sk
12:20	100		0	5	drop plug - disp csg
12:25	100		6	5	saw cut returns to surface
12:55	600		103	2	slow rate
1:00	1200		113	0	land plug, float held
					circ 106' hpl cut slurry to surface
					job complete

Service Units	34726	27462	27808-37724	19827-19873
Driver Names	A Rivera	E Mudeza	D Beck	I Delahia

E Zion J Bennett A Rivera
 Customer Representative Station Manager Cementer