

# ALLIED OIL & GAS SERVICES, LLC 064022

Federal Tax I.D. # 20-8651475

REMIT TO P.O. BOX 93999  
SOUTHLAKE, TEXAS 76092

SERVICE POINT:  
(6-25-14) Bottom - Oakley, KS

DATE <u>6-24-14</u>	SEC <u>30</u>	TWP. <u>18</u>	RANGE <u>31</u>	CALLED OUT	ON LOCATION <u>8:00 AM</u>	JOB START <u>1:30 PM</u>	JOB FINISH <u>12:30 AM</u>
LEASE <u>DR Pennington</u>	WELL # <u>10D30-1831</u>	LOCATION <u>Scott City E to Railroad</u>			COUNTY <u>Scott</u>	STATE <u>KS</u>	
OLD OR NEW (Circle one) <u>NEW</u>				<u>2 S, 3/4 E Ninto</u>			

CONTRACTOR H2 Rig 1 OWNER Same

TYPE OF JOB <u>Production (2 stage)</u>	CEMENT <u>500 gal super flush</u>
HOLE SIZE <u>7 1/2</u> I.D. <u>4800'</u>	AMOUNT ORDERED <u>Bottom stage - 220 sks ASC</u>
CASING SIZE <u>5 1/2 (15.5")</u> DEPTH <u>4797.58'</u>	<u>10% salt, 5% gilsonite 2% gel, 1/4" Flo-seal</u>
TUBING SIZE _____ DEPTH _____	<u>Top stage 465 sks Lite 5% gilsonite, 1/4" Flo-seal</u>
DRILL PIPE _____ DEPTH _____	COMMON _____ @ _____
TOOL <u>DV TOOL</u> DEPTH <u>3004.35'</u>	POZMIX _____ @ _____
PRES. MAX _____ MINIMUM _____	GEL <u>413 #</u> @ <u>1.05</u> <u>433.65</u>
MEAS. LINE _____ SHOE JOINT <u>25.92'</u>	CHLORIDE _____ @ _____
CEMENT LEFT IN CSG <u>25.92'</u>	ASC <u>220 sks</u> @ <u>23.50</u> <u>5170.00</u>
PERFS. _____	Lite <u>465 sks</u> @ <u>19.89</u> <u>9248.85</u>

DISPLACEMENT Bottom 40 bbl water 73.57 bbl mud  
Top 71.50 bbl water EQUIPMENT

PUMP TRUCK # <u>120</u> CEMENTER <u>Paul Beaver</u>	gilsonite (Bottom) <u>1100 #</u> @ <u>.98</u> <u>1078.00</u>
BULK TRUCK # <u>566/595</u> DRIVER _____	Flo-seal (Bottom) <u>55 #</u> @ <u>2.97</u> <u>163.35</u>
BULK TRUCK # <u>603</u> DRIVER <u>Brian Lang (Granddaddy)</u>	gilsonite (Top) <u>2325 #</u> @ <u>.98</u> <u>2278.50</u>
	Flo-seal (Top) <u>116 #</u> @ <u>2.97</u> <u>344.52</u>
	mud flush <u>12 bbl</u> @ <u>41.09</u> <u>493.08</u>
	<u>Material Total</u> @ _____ <u>19,209.90</u>
	<u>(9478.28/23%)</u>
	HANDLING <u>857.78 #</u> @ <u>2.48</u> <u>2127.29</u>
	MILEAGE <u>35.13 hrs @ 55 mph</u> @ <u>21.25</u> <u>5313.41</u>

REMARKS: Bottom - Run Pipe / Float equip, Rig up, mix mud

Flush, mix 220 sks ASC, release plug.

Displace w/ water + mud, plug did land @ 3004'

Lift 900 # float held, Trip start, opened tool @ 900'

circ 4 hrs Top - mix 30 sks in R.H, mix 15 sks in m.H, mix 420 sks Lite, release plug.

displace w/ water, plug did land @ 3000'

Lift 1100 # cement, did circulate

(20 bbl to pit) Thank you!

CHARGE TO: Discovery Natural Res.

STREET \_\_\_\_\_

CITY \_\_\_\_\_ STATE \_\_\_\_\_ ZIP \_\_\_\_\_

	SERVICE Bottom	Top
DEPTH OF JOB	<u>4800'</u>	<u>3004'</u>
PUMP TRUCK CHARGE	<u>2765.75</u>	<u>2558.75</u>
EXTRA FOOTAGE	@ _____	@ _____
MILEAGE MILV	<u>55</u> @ <u>7.70</u> <u>423.50</u>	<u>423.50</u>
MANIFOLD Head	@ _____	<u>275.00</u>
MILV	<u>55</u> @ <u>4.40</u> <u>242.00</u>	<u>242.00</u>
TOTAL	<u>(315231/23%)</u>	<u>13,205.70</u>

PLUG & FLOAT EQUIPMENT

<u>Weatherford (5 1/2)</u>	
Sure Seal Float shoe 1 @	<u>608.00</u>
Sure Seal Float Collar 1 @	<u>725.00</u>
Baskets 2 @	<u>395.00</u> <u>790.00</u>
Centralizers 2.5 @	<u>57.00</u> <u>142.50</u>
DV TOOL 1 @	<u>535.00</u>
lock ring	<u>49.00</u>
TOTAL	<u>8,832.00</u>

To: Allied Oil & Gas Services, LLC.  
You are hereby requested to rent cementing equipment and furnish cementer and helper(s) to assist owner or contractor to do work as is listed. The above work was done to satisfaction and supervision of owner agent or contractor. I have read and understand the "GENERAL TERMS AND CONDITIONS" listed on the reverse side.

PRINTED NAME Gary Dole

SIGNATURE [Signature]

SALES TAX (If Any) \_\_\_\_\_

TOTAL CHARGES 41,847.65

DISCOUNT 7,570.59 (23%) IF PAID IN 30 DAYS

34,277.05 Net