

Lone Jack Oil Company
Blue Mound, KS
1-913-756-2307 1-620-363-0492

Lease: Blakley Operator: Kansas City Oil LLC API # 15-121-31275-00-00
 Contractor: Lone Jack Oil Company Date Started: 7/13/16 Date Completed: 7/20/16
 Total Depth: 658 feet Well # 1-2 Hole Size: 5 5/8
 Surface Pipe: 20' 7" Surface Bit: 9 7/8 Sacks of Cement: 5
 Depth of Seat Nipple: _____ Rag Packer At: _____
 Length and Size of Casing: 644' 2 7/8 Sacks of Cement: 80
 Legal Description: SE SW NW NW Sec: 5 Twp: 17S Range: 22E County: Miami

Thickness	Depth	Type of Formation	Thickness	Depth	Type of Formation
2	2	Top Soil & Clay	3	658	Shale
7	9	Clay		658	TD
11	20	Lime			
20	40	Shale			
20	60	Lime			
3	63	Shale			
19	82	Lime			
92	174	Shale			
18	192	Lime			
31	223	Shale			
3	226	Lime			
36	262	Shale			
14	276	Lime			
14	290	Shale			
26	316	Lime			
13	329	Shale			
17	346	Lime			
4	350	Shale			
5	355	Lime			
4	359	Shale			
5	364	Lime			
108	472	Shale			
2	474	Oil Sand (Fair Bleed)			
1	475	Shaley Sand			
55	530	Shale			
8	538	Lime			
31	569	Shale			
9	578	Lime			
12	590	Shale			
4	594	Lime			
15	609	Shale			
3	612	Lime			
10	622	Shale			
6	628	Lime			
17	645	Shale			
2	647	Oil Sand (Good Bleed)			
2	649	Shaley Sand			
6	655	Oil Sand (Good Bleed)			



250 N. Water, Ste 200 - Wichita, Ks 67202

HURRICANE SERVICES INC

104 Prairie Plaza Parkway - Garnett, Ks 66032

Customer:	KC Oil				Customer Name:	Andy Peoples			Ticket No.:	1405		
Address:					AFE No.:				Date:	8/4/2016		
City, State, Zip:					Job type:	Linear Gel Frac						
Service District:	Garnett, Kansas				Well Details:	New Oil						
Well name & No.:	Blakley #1-2				Well Location:	Paola	County:	Miami	State:	Kansas		
Equipment #	Driver	Equipment #	Driver	Equipment #	Driver	TRUCK CALLED					AM	TIME
158/801	Bon T	145	Pete L			ARRIVED AT JOB					PM	
148/157	Billy L	17	Zach H			START OPERATION					AM	
148/156	Terry B					FINISH OPERATION					PM	
820	Danny P					RELEASED					AM	
24	Ron J					MILES FROM STATION TO WELL					PM	

Treatment Summary

Product/Service Code	Description	Unit of Measure	Quantity	List Price/Unit	Gross Amount	Net Amount
P01203	Hurricane 907	gal	4.00	\$42.00	\$168.00	\$87.36
P01101	Liquid KCL Substitute	gal	1.00	\$27.13	\$27.13	\$14.11
P01076	Biocide	gal	0.50	\$35.12	\$17.56	\$9.13
P01225	Liquid Enzyme Breaker	gal	0.25	\$174.00	\$43.50	\$22.62
P02000	H2O	gal	1,050.00	\$0.01	\$13.65	\$7.10
P01052	Rock Salt	lb	100.00	\$0.28	\$28.00	\$14.56
F80102	Combo Unit No. 1 - Mull @ <1500# (45%)	ea	1.00	\$1,567.50	\$1,567.50	\$391.88
F00101	Heavy Equip. One Way	mi	15.00	\$3.25	\$48.75	\$25.35
F00102	Light Equip. One Way	mi	15.00	\$1.50	\$22.50	\$11.70
F15700	Transports 150 bbl	hr	0.50	\$105.00	\$52.50	\$27.30
F15600	Transports 150 bbl	hr	0.50	\$105.00	\$52.50	\$27.30

TERMS: Cash in advance unless Hurricane Services Inc has approved credit prior to sale. Credit terms of sale for approved accounts are total invoice due on or before the 30th day from the date of invoice. Past due accounts may pay interest on the balance past due at the rate of 1 1/2% per month or the maximum allowable by applicable state or federal laws if such laws limit interest to a lesser amount. In the event it is necessary to employ an agency and/or attorney to effect the collection of said account, Customer hereby agrees to pay all fees directly or indirectly incurred for such collection. In the event that Customer's account with HSI becomes delinquent, HSI has the right to revoke any and all discounts previously applied in arriving at net invoice price. Upon revocation, the full invoice price without discount will become immediately due and owing and subject to collection. Authorization below acknowledges receipt and acceptance of all terms and conditions including the Standard Terms of Sale.

Gross:	\$ 2,041.59	Net:	\$ 638.40
Total Taxable	\$ -	Tax Rate:	7.150%
Frac and Acid service treatments designed with intent to increase production on newly drilled or existing wells are not taxable.		Sale Tax:	\$ -
		Total:	\$ 638.40

X _____
CUSTOMER AUTHORIZED AGENT

Date of Service:
 HSI Representative: *Zach Hansen*
 Customer Representative:

Customer Comments or Concerns: