



BASICSM
ENERGY SERVICES
PRESSURE PUMPING & WIRELINE

1700 S. Country Estates Rd.
Liberal, Kansas 67905
Phone 620-624-2277

FIELD SERVICE TICKET
1717 05886 A

DATE _____ TICKET NO. _____

DATE OF JOB: 6-25-14 DISTRICT: 1717		NEW WELL <input checked="" type="checkbox"/> OLD WELL <input type="checkbox"/> PROD <input type="checkbox"/> INJ <input type="checkbox"/> WDW <input type="checkbox"/> CUSTOMER ORDER NO.:						
CUSTOMER: Stelbar		LEASE: Schrodor #2-14 WELL NO.:						
ADDRESS:		COUNTY: Scott STATE: KS						
CITY: _____ STATE: _____		SERVICE CREW: E Mendoza T DeAvila D Beck						
AUTHORIZED BY: J Bennett JRB		JOB TYPE: 247 5 1/2" Production						
EQUIPMENT#	HRS	EQUIPMENT#	HRS	EQUIPMENT#	HRS	TRUCK CALLED	DATE	TIME
34726	8						6-25-14	12:00
27462	8					ARRIVED AT JOB		4:00
30464	8					START OPERATION		8:00
37847	8					FINISH OPERATION		2:00
30463	8					RELEASED		3:00
19566	8					MILES FROM STATION TO WELL		100 mi

CONTRACT CONDITIONS: (This contract must be signed before the job is commenced or merchandise is delivered).

The undersigned is authorized to execute this contract as an agent of the customer. As such, the undersigned agrees and acknowledges that this contract for services, materials, products, and/or supplies includes all of and only those terms and conditions appearing on the front and back of this document. No additional or substitute terms and/or conditions shall become a part of this contract without the written consent of an officer of Basic Energy Services LP.



SIGNED: 
(WELL OWNER, OPERATOR, CONTRACTOR OR AGENT)

ITEM/PRICE REF. NO.	MATERIAL, EQUIPMENT AND SERVICES USED	UNIT	QUANTITY	UNIT PRICE	\$ AMOUNT
CL105	AA2	✓ sk	150		2730 00
CL101	A-Con	✓ sk	400		7440 00
CL110	Premium Plus	✓ sk	120		1956 00
CL113	Gypsum	✓ lb	705		528 75
CL111	Salt	✓	829		414 50
CL103	C-15	✓	106		1325 00
CL107	C-42P	✓	36		288 00
CL201	Gilsonite	✓	750		502 50
CL102	Gemplake	✓	130		481 00
CL109	Calcium Chloride	✓	1354		1421 70
CF1251	5 1/2" Auto Fill Float Shoe	✓ ea	1		360 00
CF601	Catch Down Plug + Baffle	✓	1		850 00
CF401	Two Stage DV Tool	✓	1		6100 00
CF4452	Turbolizers	✓	10		750 00
CF4552	Basket	✓	1		955 00
CF3000	Thread Lock	✓	1		34 00
CL155	Superflush	✓ gal	500		765 00

SUB TOTAL: **28207.99**

CHEMICAL / ACID DATA:			

SERVICE & EQUIPMENT	%TAX ON \$	
MATERIALS	%TAX ON \$	
TOTAL		

SERVICE REPRESENTATIVE: 	THE ABOVE MATERIAL AND SERVICE ORDERED BY CUSTOMER AND RECEIVED BY: 
FIELD SERVICE ORDER NO. _____	(WELL OWNER OPERATOR CONTRACTOR OR AGENT)



BASICSM
ENERGY SERVICES
Liberal, Kansas

Cement Report

Customer Stellar	Lease No.	Date 6-25-14
Lease Schroder	Well # 2-14	Service Receipt 05886
Casing 5 1/2" 15.5# Depth 4790'	County Scott	State KS
Job Type 242-5 1/2" Production	Formation	Legal Description 14-17-33

Pipe Data		Perforating Data		Cement Data
Casing size 5 1/2" 15.5#	Tubing Size	Shots/Ft		Lead 400sk A Con
Depth 4790'	Depth	From	To	
Volume 113	Volume	From	To	Tail in 120sk Prem Plus
Max Press 1500#	Max Press	From	To	
Well Connection 10-4780'	Annulus Vol.	From	To	
Plug Depth 25-42'	Peaker Depth 2414'	From	To	

Time	Casing Pressure	Tubing Pressure	Bbls. Pumped	Rate	Service Log
2:00					on loc. site assessment
3:00					spot trucks rig up
4:00					start csg + float equip.
7:00					csg on bitum break circ
7:15					safety meeting - JSA
7:40					pressure test 2000#
7:45	200		5	4	Dump 5 bbl H ₂ O spacer
7:50	200		12	4	Dump 12 bbl super flush
7:55	200		5	4	pump 5 bbl H ₂ O spacer
8:00	200		40.3	5	mix + pump 150 sk AA2 @ 14.8# 1.51 ft 3/8sk
8:15	100		60	6	drop plug batch down plug - disp
8:30	1000		53	6	csg 600 bbl H ₂ O 53 Bl mud
9:00	1500		113	0	land plug float hold
9:30	900				open DV tool @ 900# circ to 12:30 pm - plug rest + mouse holes w/ 50 sk Class C
12:30			210	5	mix + pump 400 sk A-Con @ 11.4# @ 2.95 ft 3/8sk
1:15			16.7	5	switch total 70 sk Prem. Plus @ 14.8# - 1.34 ft 3/8sk
1:30			0	6	drop plug disp csg
1:30	1500		57.5	0	land plug float hold

Service Units	34726	27462	30464-3757	30463-19566
Driver Names	A. Rivera	E. Mendoza	E. Delacruz	D. Beck

T. Lund Customer Representative
 J. Bennett Station Manager
 A. Rivera Cementer

