

# ALLIED OIL & GAS SERVICES, LLC 062997

Federal Tax I.D. # 20-8651475

REMIT TO P.O. BOX 93999  
SOUTHLAKE, TEXAS 76092

SERVICE POINT:  
Great Bend

DATE <u>6-8-14</u>	SEC <u>33</u>	TWP <u>25</u>	RANGE <u>10</u>	CALLED OUT <u>1:00 am</u>	ON LOCATION <u>4:30 am</u>	JOB START <u>6:00 am</u>	JOB FINISH <u>7:00 am</u>
LEASE <u>Rock Chalk</u>		WELL # <u>R33-2H</u>		LOCATION <u>Sylvia 85 1/2 W</u>		COUNTY <u>Renov</u>	STATE <u>Ks</u>
OLD OR <input checked="" type="radio"/> NEW (Circle one)							

CONTRACTOR <u>Unit 303</u>		OWNER <u>Same</u>
TYPE OF JOB <u>surface</u>		
HOLE SIZE <u>12 1/2</u>	T.D. <u>1520</u>	
CASING SIZE <u>9 5/8 36#</u>	DEPTH <u>1525</u>	
TUBING SIZE	DEPTH	
DRILL PIPE	DEPTH	
TOOL	DEPTH	
PRES. MAX	MINIMUM	
MEAS. LINE	SHOE JOINT	
CEMENT LEFT IN CSG.		
PERFS.		
DISPLACEMENT <u>H2O 117.88 BBT</u>		
EQUIPMENT		
PUMP TRUCK # <u>597</u>	CEMENTER <u>Charles Kingen</u>	
	HELPER <u>Kevin eddy</u>	
BULK TRUCK # <u>603</u>	DRIVER <u>Dan Casper</u>	
BULK TRUCK # <u>870-844</u>	DRIVER <u>Kevin weighouse</u>	
CEMENT		
AMOUNT ORDERED <u>300-24 AND 21-9999</u>		
<u>21' Mesa Bends 21' CC 1/4 plowent</u>		
<u>280-24 Class A 21' CC 1/4 plowent</u>		
COMMON <u>280-24</u>	@ <u>17.90</u>	<u>5012</u>
POZMIX	@	
GEL <u>4400</u>	@	
CHLORIDE <u>1900 1B</u>	@ <u>1.50</u>	<u>1120</u>
ASC	@	
<u>Amp 300-24</u>	@ <u>25.90</u>	<u>7770</u>
<u>plowent 1951B</u>	@ <u>2.97</u>	<u>430.65</u>
<u>200H Sugar</u>	@ <u>2.00</u>	<u>424</u>
		<u>Materials Total 14756.65</u>
		<u>Disc @ 38% 5607.53</u>
		<u>Service</u>
HANDLING <u>633.42</u>	@ <u>2.49</u>	<u>1570.82</u>
MILEAGE <u>1422.09</u>	@ <u>2.60</u>	<u>3697.42</u>

REMARKS:  
Rig Ran 1525' 9 5/8 Csg Brake  
Circulator w/ Rig mud hook to  
head 5 BBT H2O ahead Max 300-24  
head w/ 12.6 Max 280-24 tail w/ 15.6  
shut down Release plug displac  
117.88 BBT H2O plug del hand  
plug del hold cement did circ  
50 BBT to pit

DEPTH OF JOB <u>1520</u>		
PUMP TRUCK CHARGE		<u>2213.75</u>
EXTRA FOOTAGE	@	
MILEAGE <u>50</u>	@ <u>7.70</u>	<u>385</u>
MANIFOLD	@	<u>275</u>
<u>Lvm 100</u>	@ <u>4.40</u>	<u>440</u>
	@	

CHARGE TO: Unit petroleum  
STREET \_\_\_\_\_  
CITY \_\_\_\_\_ STATE \_\_\_\_\_ ZIP \_\_\_\_\_

TOTAL 85582.04  
38% 3261.18

*Thank you!*  
To: Allied Oil & Gas Services, LLC.  
You are hereby requested to rent cementing equipment and furnish cementer and helper(s) to assist owner or contractor to do work as is listed. The above work was done to satisfaction and supervision of owner agent or contractor. I have read and understand the "GENERAL TERMS AND CONDITIONS" listed on the reverse side.

PLUG & FLOAT EQUIPMENT

<u>sure seal float shoe</u>		<u>1213.29</u>
<u>2-Thread Rock</u>	@ <u>83.07</u>	<u>166.14</u>
<u>5-centrifuge</u>	@ <u>87.75</u>	<u>438.75</u>
<u>1-Basket</u>	@	<u>594.36</u>
<u>Rubber plug</u>	@	<u>184.86</u>
	@	

TOTAL 2597.40  
38% 987.00

PRINTED NAME K Markopoy

SALES TAX (If Any) \_\_\_\_\_  
TOTAL CHARGES 25936.09

SIGNATURE K Markopoy

DISCOUNT 9855.71 (38/38/38)  
16080.38 IF PAID IN 30 DAYS

# ALLIED OIL & GAS SERVICES, LLC 062998

Federal Tax I.D. # 20-8651475

REMIT TO P.O. BOX 93999  
SOUTHLAKE, TEXAS 76092

SERVICE POINT: Great Bend

DATE <u>6-12-14</u>	SEC. <u>33</u>	TWP. <u>25</u>	RANGE <u>10</u>	CALLED OUT <u>9:30</u>	ON LOCATION <u>10:30</u>	JOB START <u>12:00 am</u>	JOB FINISH <u>1:00 am</u>
LEASE <u>Rock chalk</u>			WELL # <u>33-2H</u>	LOCATION <u>ylvia 8 5 1/2 L</u>		COUNTY <u>Reno</u>	STATE <u>KS</u>
OLD OR <input checked="" type="radio"/> NEW (Circle one)							

CONTRACTOR <u>Unit 303</u>	OWNER <u>name</u>
TYPE OF JOB <u>Anteemediate</u>	
HOLE SIZE <u>8-1/2</u> T.D. <u>4330</u>	CEMENT
CASING SIZE <u>7" 23#</u> DEPTH <u>4336</u>	AMOUNT ORDERED <u>160 cu class A 5 1/4</u>
TUBING SIZE _____ DEPTH _____	<u>gyp 10' salt</u>
DRILL PIPE _____ DEPTH _____	
TOOL _____ DEPTH _____	
PRES. MAX _____ MINIMUM _____	COMMON <u>160</u> @ <u>17.90</u> <u>2864.00</u>
MEAS. LINE _____ SHOE JOINT _____	POZMIX _____ @ _____
CEMENT LEFT IN CSG. _____	GEL _____ @ _____
PERFS. _____	CHLORIDE _____ @ _____
DISPLACEMENT <u>168 BBI H2O</u>	ASC _____ @ _____
EQUIPMENT	<u>gyp 10' salt</u> @ <u>37.60</u> <u>601.60</u>
	<u>salt 32</u> @ <u>26.35</u> <u>843.20</u>
	<u>Materials total</u> <u>4308.80</u>
PUMP TRUCK # <u>597</u> CEMENTER <u>Charles King</u>	<u>Disc</u> @ <u>40%</u> <u>1723.52</u>
BULK TRUCK # <u>599</u> HELPER <u>Ben Newell</u>	
BULK TRUCK # _____ DRIVER <u>Brian Rang</u>	
BULK TRUCK # _____ DRIVER _____	<u>Service</u> @ _____
	HANDLING <u>189.84</u> @ <u>2.48</u> <u>470.80</u>
	MILEAGE <u>414.89</u> @ <u>2.60</u> <u>1077.92</u>

REMARKS:  
Ran 4336' 7" cas broke circulation  
Pump 100 BBI H2O mix 160 cu class  
A 5 1/4 gyp 10' salt shut  
down Release Plug Displace  
168 BBI H2O Rand plug @ 1200#  
Release & float held

DEPTH OF JOB <u>4336</u>	
PUMP TRUCK CHARGE _____	<u>2765.25</u>
EXTRA FOOTAGE _____ @ _____	
MILEAGE <u>50</u> @ <u>7.70</u>	<u>385.00</u>
MANIFOLD _____ @ _____	<u>275.00</u>
<u>Lvm 50</u> @ <u>4.40</u>	<u>220.00</u>

CHARGE TO: Unit petroleum  
STREET \_\_\_\_\_  
CITY \_\_\_\_\_ STATE \_\_\_\_\_ ZIP \_\_\_\_\_

TOTAL 5193.97  
40% 2077.59

Thank you!

To: Allied Oil & Gas Services, LLC.  
You are hereby requested to rent cementing equipment and furnish cementer and helper(s) to assist owner or contractor to do work as is listed. The above work was done to satisfaction and supervision of owner agent or contractor. I have read and understand the "GENERAL TERMS AND CONDITIONS" listed on the reverse side.

PRINTED NAME X muk Lopez  
SIGNATURE X muk Lopez

PLUG & FLOAT EQUIPMENT

<u>wire seal float shoe</u>	<u>712.53</u>
<u>2 thread lock</u> @ <u>83.07</u>	<u>166.14</u>
<u>Rubber plug</u> @ <u>99.45</u>	<u>99.45</u>
_____ @ _____	_____
_____ @ _____	_____
TOTAL <u>978.12</u>	<u>40%</u> <u>391.25</u>

SALES TAX (If Any) \_\_\_\_\_  
TOTAL CHARGES 10480.89  
DISCOUNT 4192.36 IF PAID IN 30 DAYS  
6288.53

# ALLIED OIL & GAS SERVICES, LLC 063554

Federal Tax I.D. # 20-8651475

REMIT TO P.O. BOX 93999  
SOUTHLAKE, TEXAS 76092

SERVICE POINT:  
Arrest Road

DATE <u>6-17-14</u>	SEC. <u>33</u>	TWP. <u>25</u>	RANGE <u>10</u>	CALLED OUT <u>8:00 AM</u>	ON LOCATION <u>2:00 PM</u>	JOB START <u>7:00 PM</u>	JOB FINISH <u>8:00 PM</u>
LEASE <u>Rockwell</u>	WELL # <u>33-2H</u>		LOCATION <u>Sylvan 8S, 1/2 W, 5/8</u>		COUNTY <u>Pano</u>	STATE <u>Ks</u>	
OLD OR <del>NEW</del> (Circle one)							

CONTRACTOR DN 303 OWNER Same

TYPE OF JOB liner

HOLE SIZE \_\_\_\_\_ T.D. 8455' CEMENT \_\_\_\_\_

CASING SIZE 4 1/2 - 5 1/2 DEPTH \_\_\_\_\_ AMOUNT ORDERED 400 lbs 50/50 2% H<sub>2</sub>O,

TUBING SIZE \_\_\_\_\_ DEPTH \_\_\_\_\_ 10% Salt, 5% Hypo, .6% FI-110,

DRILL PIPE \_\_\_\_\_ DEPTH \_\_\_\_\_ .3% CO-31, .2% SA-51, .25% Refoamer, 50# Super

TOOL \_\_\_\_\_ DEPTH \_\_\_\_\_

PRES. MAX 2190" MINIMUM 1250" COMMON \_\_\_\_\_ @ \_\_\_\_\_

MEAS. LINE \_\_\_\_\_ SHOE JOINT 44.78 POZMIX \_\_\_\_\_ @ \_\_\_\_\_

CEMENT LEFT IN CSG. 44.78 GEL 6.22 @ 1.05 705.60

PERFS. \_\_\_\_\_ CHLORIDE \_\_\_\_\_ @ \_\_\_\_\_

DISPLACEMENT 4 1/2 = 67.43 - 5 1/2 = 94.33 - (161.76) ASC \_\_\_\_\_ @ \_\_\_\_\_

**EQUIPMENT**

PUMP TRUCK CEMENTER Team Andrew

# 597 HELPER Dustin Smith (Yukon)

BULK TRUCK \_\_\_\_\_

# 870-844 DRIVER Kevin W. Simpson

BULK TRUCK \_\_\_\_\_

# \_\_\_\_\_ DRIVER \_\_\_\_\_

CEMENT \_\_\_\_\_

AMOUNT ORDERED 400 lbs 50/50 2% H<sub>2</sub>O,

10% Salt, 5% Hypo, .6% FI-110,

.3% CO-31, .2% SA-51, .25% Refoamer, 50# Super

COMMON \_\_\_\_\_ @ \_\_\_\_\_

POZMIX \_\_\_\_\_ @ \_\_\_\_\_

GEL 6.22 @ 1.05 705.60

CHLORIDE \_\_\_\_\_ @ \_\_\_\_\_

ASC \_\_\_\_\_ @ \_\_\_\_\_

Super 50 @ \_\_\_\_\_

50/50 Super H @ 21.79 8716.00

Salt 2200 @ .68 1496.00

Gypsum 1180 @ .88 1478.40

FI-110 200 @ 18.90 3780.00

Refoamer 84 @ 3.50 294.00

CO-31 100 @ 9.50 950.00

SA-51 66 @ 17.55 1158.30

**REMARKS:**

Ran 4395.20' of 4 1/2", 4016' of 5 1/2" casing.  
Hooked up a Brake circulation. Pumped  
5 bbls H<sub>2</sub>O, 24 bbls NW1100, 5 bbls H<sub>2</sub>O. Mixed  
400 lbs 50/50 2% H<sub>2</sub>O 10% Salt, 5% Hypo,  
.6% FI-110, .3% CO-31, .2% SA-51, .25% Refoamer.  
Pumped 1 bbl Super H<sub>2</sub>O. Released Plug.  
Displaced with 20 bbl Super H<sub>2</sub>O &  
41.76 H<sub>2</sub>O. Landed plug at 2190". Released  
and float held.

Materials TOTAL 18,578.30  
Disc 40% 7431.32

**SERVICE**

DEPTH OF JOB \_\_\_\_\_

PUMP TRUCK CHARGE \_\_\_\_\_ 4933.50

EXTRA FOOTAGE @ \_\_\_\_\_

MILEAGE 50 @ 7.70 385.00

MANIFOLD @ \_\_\_\_\_

Lyn 50 @ 4.40 220.00

Handling 478.63 @ 2.48 1187.00

Mileage 21.30 x 50 @ 2.75 2928.75

TOTAL 9654.25

Disc 40% 3841.70

**PLUG & FLOAT EQUIPMENT**

\_\_\_\_\_ @ \_\_\_\_\_

\_\_\_\_\_ @ \_\_\_\_\_

\_\_\_\_\_ @ \_\_\_\_\_

\_\_\_\_\_ @ \_\_\_\_\_

\_\_\_\_\_ @ \_\_\_\_\_

0% TOTAL 0

SALES TAX (If Any) \_\_\_\_\_

TOTAL CHARGES \$ 28,232.55

DISCOUNT \$ 11,293.02 IF PAID IN 30 DAYS (40/40/0)

\$ 16,939.53

PRINTED NAME X Colin Monday

SIGNATURE X Colin Monday

SIGNATURE \_\_\_\_\_

SIGNATURE \_\_\_\_\_