

SPUD DATE: 9-8-14  
 FINISH DATE: 9-9-14  
 LEASE: Larry Spratt  
 LEASE OPERATOR: Kingman Oil  
 WELL: K01-2  
 API: 15-059-26811  
 SEC: TWP: RNG:  
 COUNTY: Franklin  
 DRILLERS NAME: Waylon Johns  
 RIG #: 2



2394 UTAH ROAD  
 RANTOUL, KS 66079

SURFACE: SIZE BIT \_\_\_\_\_ LENGTH 20.10' SIZE 7" CEMENT 5 Bags  
 DRILL BIT SIZE 5 7/8" LENGTH 729.45 SIZE 2 7/8 Used BAFFLE 32.10  
 TD 745 CORED 667-687

FORMATIONS	THICKNESS	FROM	TO	FORMATION	THICKNESS	FROM	TO
Soil/Clay	9	0	9	Grey Sand No Oil Show	1	390	391
Shale	8	9	17	Shale	27	391	418
Grey Sand	12	17	29	Lime Soft	7	418	425
Shale	63	29	92	Shale	8	425	433
Lime	1	92	93	Lime	9	433	442
Shale	1	93	94	Shale	1	442	443
Lime	12	94	106	Lime	5	443	448
Shale	1	106	107	Shale	23	448	471
Lime	3	107	110	Lime	7	471	478
Shale	11	110	121	Shale	31	478	509
Grey Sand	3	121	124	Lime	4	509	513
Lime	1	124	125	Shale	15	513	528
Shale	7	125	132	Lime	5	528	533
Lime	1	132	133	Lime Some Sand Good Bleed Soft	5	533	538
Shale	4	133	137	Shale	4	538	542
Lime	3	137	140	Shale 20% Broken Sand No Show	2	542	544
Shale	38	140	178	Shale 50% Broken Sand Good Bleed	4	544	548
Lime	11	178	189	Shale	49	548	597
Shale	2	189	191	Sand Oil Small No Bleed	10	597	607
Lime	4	191	195	Shale	29	607	636
Shale	10	195	205	Lime	1	636	637
Lime	12	205	217	Shale	9	637	646
Shale	1	217	218	Coal	1	646	647
Lime	14	218	232	Shale	2	647	649
Shale	10	232	242	Coal	2	649	651
Lime	4	242	246	Shale	14	651	665
Shale	2	246	248	Shale 20% Broken Sand Some Bleed	1	665	666
Lime	16	248	264	Solid Sand Good Bleed CP	1	666	667
Coal	5	264	269				
Lime KC	12	269	281				
Shale	109	281	390				

START DATE:		
FINISH DATE:		
LEASE:		
LEASE OPERATOR:		
WELL: <i>K01-2</i>		
API:		
SEC:	TWP:	RNG:
COUNTY:		
DRILLERS NAME:		
RIG #:		



**2394 UTAH ROAD  
RANTOUL, KS 66079**

**SURFACE: SIZE BIT** \_\_\_\_\_ **LENGTH** \_\_\_\_\_ **SIZE** \_\_\_\_\_ **CEMENT** \_\_\_\_\_

**DRILL BIT SIZE** \_\_\_\_\_ **LENGTH** \_\_\_\_\_ **SIZE** \_\_\_\_\_ **BAFFLE** \_\_\_\_\_

**TD** \_\_\_\_\_ **CORED** \_\_\_\_\_

FORMATIONS	THICKNESS	FROM	TO	FORMATION	THICKNESS	FROM	TO
<i>Solid Sand Some Bleed</i>	<i>6.5</i>	<i>667</i>	<i>673.5</i>				
<i>Shale</i>	<i>1</i>	<i>673.5</i>	<i>674.5</i>				
<i>Solid Sand Good Bleed</i>	<i>1.5</i>	<i>674.5</i>	<i>676</i>				
<i>Solid Sand Heavy Bleed</i>	<i>6.5</i>	<i>676</i>	<i>682.25</i>				
<i>Solid Sand Good Bleed Very Hard</i>	<i>1.25</i>	<i>682.25</i>	<i>683.5</i>				
<i>Shale Some Broken Sand No Show</i>	<i>61.5</i>	<i>683.5</i>	<i>745</i>				

*TD 745*