



BASICSM
ENERGY SERVICES
PRESSURE PUMPING & WIRELINE

1700 S. Country Estates Rd.
Liberal, Kansas 67905
Phone 620-624-2277

FIELD SERVICE TICKET
1717 05798 A

DATE _____ TICKET NO. _____

DATE OF JOB 6-13-14 DISTRICT 1717		NEW WELL <input type="checkbox"/> OLD WELL <input checked="" type="checkbox"/> PROD <input type="checkbox"/> INJ <input type="checkbox"/> WDW <input type="checkbox"/> CUSTOMER ORDER NO.:								
CUSTOMER Merit Energy		LEASE Purcell D WELL NO. 1								
ADDRESS		COUNTY Stanton STATE KS								
CITY STATE		SERVICE CREW Ruben Carlos-Daniel-Edgar								
AUTHORIZED BY Tyce Davis		JOB TYPE: 2-42 8 5/8 Surface								
EQUIPMENT#	HRS	EQUIPMENT#	HRS	EQUIPMENT#	HRS	TRUCK CALLED	DATE	AM	PM	TIME
				78940	12	6-13-14				0300
				3875019842	12	ARRIVED AT JOB				0300
				27808 37724	12	START OPERATION				1322
				14355 37725	12	FINISH OPERATION				1450
						RELEASED				1500
						MILES FROM STATION TO WELL				90

CONTRACT CONDITIONS: (This contract must be signed before the job is commenced or merchandise is delivered).

The undersigned is authorized to execute this contract as an agent of the customer. As such, the undersigned agrees and acknowledges that this contract for services, materials, products, and/or supplies includes all of and only those terms and conditions appearing on the front and back of this document. No additional or substitute terms and/or conditions shall become a part of this contract without the written consent of an officer of Basic Energy Services LP.

SIGNED:
(WELL OWNER, OPERATOR, CONTRACTOR OR AGENT)

ITEM/PRICE REF. NO.	MATERIAL, EQUIPMENT AND SERVICES USED	UNIT	QUANTITY	UNIT PRICE	\$ AMOUNT
CL 101	✓ 'A' Con Blend	SK	360		6696 00
CL 110	✓ Premium Plus Cement	SK	245		3993 50
CC 109	✓ Calcium Chloride	Lb	1479		1552 95
CC 102	✓ Celloflike	Lb	152		562 40
CC 130	✓ C-51	Lb	68		1700 00
CF 253	✓ 8 5/8 Guide Shoe	Eg	1		380 00
CF 1453	✓ 8 5/8 Insert float Valve	Eg	1		280 00
CF 4405	✓ 8 5/8 Centralizers	Eg	15		2175 00
CF 4109	✓ 8 5/8 Stop Collar	Eg	1		100 00
CF 105	✓ 8 5/8 Cement Plug	Eg	1		225 00
CF 3000	✓ Thread Lock Kit	Eg	12		408 00
CC 165	Stoploss Polymer	Lb	890		5040 00
CC 164	Stoploss LCM	Lb	390		1680 00
E 101	Heavy Equipment M/legge	Mi	270		1890 00
CE 240	Blending & Mixing Charge	SK	605		847 00
E 113	Proppant & Bulk Delivery Charge	TM	2565		5643 00
CE 202	Depth Charge 1001-2000'	4hrs	1		1500 00
CE 504	Plug Container Utilization Charge	Job	1		250 00
E 100	Pick up Charge	Mi	90		382 50

SUB TOTAL **28522 76**

CHEMICAL / ACID DATA:			

SERVICE & EQUIPMENT	%TAX ON \$	
MATERIALS	%TAX ON \$	
TOTAL		

SERVICE REPRESENTATIVE

THE ABOVE MATERIAL AND SERVICE ORDERED BY CUSTOMER AND RECEIVED BY:
(WELL OWNER OR OPERATOR CONTRACTOR OR AGENT)

FIELD SERVICE ORDER NO.



BASICSM
ENERGY SERVICES
Liberal, Kansas

Cement Report

Customer	Merit Energy	Lease No.		Date	6-13-14
Lease	Purcell - D	Well #	1	Service Receipt	
Casing	8 5/8 24#	Depth	1905'	County	Stanton
Job Type	2-42	Formation		State	KS
				Legal Description	26-30-40

Pipe Data		Perforating Data		Cement Data
Casing size	8 5/8 24#	Tubing Size		Lead 360 SX @ 12.1 PPF
Depth	1905'	Depth		3% CC, 1/4# Polyfume, 2% WCA-1
Volume	118.6 bbl	Volume		A - Con Blend
Max Press		Max Press		Tail in 245 SX @ 14.8 PPF
Well Connection		Annulus Vol.		2% CC, 1/4# Polyfume
Plug Depth	1865'	Packer Depth		Premium Plus Cement

Time	Casing Pressure	Tubing Pressure	Bbls. Pumped	Rate	Service Log
0300					On location
1000					Rig up
1300					Safety Meeting
1322	2500				Pressure Test
1325	100		20	5	Pump Stoploss
1330	100		154	5	Pump 360 SX @ 12.1 PPF
1400	150		58	5	Pump 245 SX @ 14.8 PPF
1415					Drop Plug
1417	150			5	Start Displacement
1441	500		105	2	Slow Rate
1445	1000		118	2	Bump Plug
1450	0				Release Pressure - float held
1530	0				Casing Test - collar leak.
					shut down - Rig Down

Service Units	78440	38750 17842	27868 37724	14355 37725	
Driver Names	Ruben	Carlos	Daniel	Edgar	

Jimmy Customer Representative
 Jerry Bennett Station Manager
 Ruben Martinez Cementer