



BASICSM
ENERGY SERVICES
PRESSURE PUMPING & WIRELINE

1700 S. Country Estates Rd.
Liberal, Kansas 67905
Phone 620-624-2277

FIELD SERVICE TICKET
1717 05649 A

DATE _____ TICKET NO. _____

DATE OF JOB 06-19-14 DISTRICT 1717 Liberal, KS		NEW WELL <input checked="" type="checkbox"/> OLD WELL <input type="checkbox"/> PROD <input type="checkbox"/> INJ <input type="checkbox"/> WDW <input type="checkbox"/> CUSTOMER ORDER NO.:						
CUSTOMER Merit Energy		LEASE Orion 'B' 5 WELL NO.						
ADDRESS		COUNTY Haskell STATE KS						
CITY STATE		SERVICE CREW Roger Brown - Carlos - Cesar - Ismael						
AUTHORIZED BY Jerry Bennett JD		JOB TYPE: 242 - 8 5/8" Surface AFE# 034375						
EQUIPMENT#	HRS	EQUIPMENT#	HRS	EQUIPMENT#	HRS	TRUCK CALLED 06-19-14 DATE	AM/PM	TIME
21755	6							0600
38750-19842 -	6 -					ARRIVED AT JOB	1	0800
30463-19566	6					START OPERATION		2000
14355-37725	6					FINISH OPERATION		2200
						RELEASED		2230
						MILES FROM STATION TO WELL		45

CONTRACT CONDITIONS: (This contract must be signed before the job is commenced or merchandise is delivered).

The undersigned is authorized to execute this contract as an agent of the customer. As such, the undersigned agrees and acknowledges that this contract for services, materials, products, and/or supplies includes all of and only those terms and conditions appearing on the front and back of this document. No additional or substitute terms and/or conditions shall become a part of this contract without the written consent of an officer of Basic Energy Services LP.

SIGNED: _____
(WELL OWNER, OPERATOR, CONTRACTOR OR AGENT)

ITEM/PRICE REF. NO.	MATERIAL, EQUIPMENT AND SERVICES USED	UNIT	QUANTITY	UNIT PRICE	\$ AMOUNT
CL101	✓ ACen' Blend	sk	340		6324 00
CL110	✓ Premium Plus Cement	sk	245		3993 50
CC109	✓ Calcium Chloride	lb	1422		1493 10
CC102	✓ Cellulose	lb	747		543 90
CC130	✓ C-51	lb	2630 64		1600 00
CF253	✓ Guide shoe - Regular 8 5/8"	ea	1		380 00
CF1453	✓ Flapper type Insert Float Valve 8 5/8"	ea	1		280 00
CF4405	✓ Economizer Hinged, Welded Standard Box 8 5/8" - 12 1/4"	ea	14		2030 00
CF4109	✓ Stop Collar 8 5/8"	ea	1		100 00
CF105	✓ Stop Rubber Cement Plug - 8 5/8"	ea	1		225 00
E101	Heavy Equipment Mileage	mi	135		945 00
CE240	Blending & Mixing Service Charge	sk	585		819 00
E113	Proppant and Bulk Delivery Charges	tn	1240		2727 45
CE202	Depth Change - 1001' - 2000'	4Hrs	1		1500 00
SUB TOTAL					19845 40
					19407 90

CHEMICAL / ACID DATA:			

SERVICE & EQUIPMENT	%TAX ON \$	
MATERIALS	%TAX ON \$	
TOTAL		

SERVICE REPRESENTATIVE **Roger Brown** THE ABOVE MATERIAL AND SERVICE ORDERED BY CUSTOMER AND RECEIVED BY: _____
(WELL OWNER OPERATOR CONTRACTOR OR AGENT)

FIELD SERVICE ORDER NO. _____



BASIC
ENERGY SERVICES
Liberal, Kansas

Cement Report

Customer <i>Merit Energy</i>		Lease No. <i>Onion 'B' 5'</i>		Date <i>06-19-14</i>	
Lease <i>Onion 'B' 115'</i>		Well # <i>5</i>		Service Receipt <i>1117 05649A</i>	
Casing <i>8 5/8"</i>	Depth <i>1820'</i>	County <i>Haskell</i>		State <i>KS</i>	
Job Type <i>8 5/8" Surface</i>		Formation		Legal Description <i>2-29-34 AFE# 034375'</i>	
Pipe Data			Perforating Data		
Casing size <i>8 5/8"</i>	Tubing Size	Shots/Ft		Lead <i>340 sks 'A' Con</i>	
Depth <i>1820'</i>	Depth	From	To	<i>12.1 ppg 2.4 cu ft sk</i>	
Volume <i>113.6 BBLs</i>	Volume	From	To	<i>3% CaCl₂ 2% WCA-1</i>	
Max Press <i>2500 psi</i>	Max Press	From	To	<i>1/4" 8 1/4" flake</i>	
Well Connection	Annulus Vol.	From	To	Tail in <i>245 sks Premium</i>	
Plug Depth <i>1786'</i>	Packer Depth	From	To	<i>14.8 ppg 1.34 cu ft sk</i>	
		From	To	<i>2% CaCl₂</i>	
		From	To	<i>1/4" 8 1/4" flake</i>	
Time	Casing Pressure	Tubing Pressure	Bbls. Pumped	Rate	Service Log
<i>0500</i>					<i>Called Out</i>
<i>0800</i>					<i>On Location</i>
<i>1700</i>					<i>Set up Safety Meeting</i>
<i>1715</i>					<i>On Bottom Circulate with Rig</i>
<i>2000</i>					<i>Hook up Hoop & Planifold</i>
<i>2040</i>					<i>Test Liner to Rig Floor 2000 psi</i>
<i>2045</i>					<i>Pump 3 BBLs water ahead</i>
<i>2020</i>	<i>100</i>		<i>145</i>	<i>5</i>	<i>Mix & Pump Lead cement</i>
					<i>12.1 ppg - 2.4 cu ft sk 145 BBLs slurry</i>
<i>2050</i>	<i>200</i>		<i>58.5</i>	<i>5</i>	<i>Mix & Pump Tail Cement</i>
					<i>14.8 ppg - 1.34 cu ft sk 58.5 BBLs slurry</i>
<i>2105</i>	<i>200</i>				<i>Finished Mixing Cement</i>
					<i>Washup Drop Top Plug</i>
			<i>113.6</i>		<i>Displace at 5 BPM</i>
					<i>Last 10 BBLs slow down to 2 BPM</i>
<i>2130</i>	<i>1000</i>				<i>Set Plug 500 psi over</i>
<i>2132</i>					<i>Relaxed</i>
<i>2135</i>	<i>1500</i>				<i>Pressure back up hold for 30 mins</i>
					<i>Relaxed - Job Completed - Thank-e</i>
Service Units	<i>9/955</i>	<i>30463-19566</i>	<i>38700-19642</i>	<i>14359-37125</i>	
Driver Names	<i>Roger</i>	<i>Co star</i>	<i>Charles</i>	<i>Ismael</i>	

Jimmy Ballou

Customer Representative

Jersey Binnett

Station Manager

Roger Brown

Cementer