



BASICSM
ENERGY SERVICES
PRESSURE PUMPING & WIRELINE

1700 S. Country Estates Rd.
Liberal, Kansas 67905
Phone 620-624-2277

FIELD SERVICE TICKET
1717 05928 A

DATE _____ TICKET NO. _____

DATE OF JOB 6-23-14 DISTRICT 1717		NEW WELL <input checked="" type="checkbox"/> OLD WELL <input type="checkbox"/> PROD <input type="checkbox"/> INJ <input type="checkbox"/> WDW <input type="checkbox"/> CUSTOMER ORDER NO.:								
CUSTOMER Merit Energy		LEASE Onion 'B' WELL NO. 1								
ADDRESS		COUNTY Haskell STATE KS								
CITY STATE		SERVICE CREW Ruben - Carlos - Chad								
AUTHORIZED BY Tyce Davis		JOB TYPE: 2-42 5 1/2 Production								
EQUIPMENT#	HRS	EQUIPMENT#	HRS	EQUIPMENT#	HRS	TRUCK CALLED	DATE	AM	PM	TIME
				78940	7		6-23-14			1700
				38750/9842	7	ARRIVED AT JOB				1830
				-30463 19566	7	START OPERATION				2335
						FINISH OPERATION				2358
						RELEASED				2400
						MILES FROM STATION TO WELL				4.5

CONTRACT CONDITIONS: (This contract must be signed before the job is commenced or merchandise is delivered).

The undersigned is authorized to execute this contract as an agent of the customer. As such, the undersigned agrees and acknowledges that this contract for services, materials, products, and/or supplies includes all of and only those terms and conditions appearing on the front and back of this document. No additional or substitute terms and/or conditions shall become a part of this contract without the written consent of an officer of Basic Energy Services LP.

SIGNED: [Signature]
(WELL OWNER, OPERATOR, CONTRACTOR OR AGENT)

ITEM/PRICE REF. NO.	MATERIAL, EQUIPMENT AND SERVICES USED	UNIT	QUANTITY	UNIT PRICE	\$ AMOUNT
CL 104	50/50 Poz	SK	305		3355 00
CC 113	Gypsum	Lb	1285		963 75
CC 111	Salt	Lb	1877		938 50
CC 103	C-15	Lb	155		1937 50
CC 105	C-41P	Lb	65		260 00
CC 201	Gilsonite	Lb	1525		1021 25
CF 251	5 1/2 Guide shoe	Eg	1		250 00
CF 1481	5 1/2 Insert float Valve	Eg	1		215 00
CF 4452	5 1/2 Centralizers	Eg	20		1500 00
CF 4105	5 1/2 Stop Collar	Eg	1		84 00
CF 103	5 1/2 Cement Plug	Eg	1		105 00
CC 155	Super flush II	Gal	500		765 00
E 101	Heavy Equipment Mileage	M:	90		630 00
CE 240	Blending & Mixing Charge	SK	305		427 00
E 113	Proppant & Bulk Delivery Charge	TM	578		1272 15
CE 206	Depth Charge 500' - 6000'	Yhrs	1		2880 00
CE 304	Plug Container Utilization Charge	Job	1		250 00
E 100	Pickup Charge	M:	45		191 25
T 105	Cement Data	Eg	1		550 00
SUB TOTAL					13328 18

CHEMICAL / ACID DATA:			

SERVICE & EQUIPMENT	%TAX ON \$	
MATERIALS	%TAX ON \$	
TOTAL		

AFE# 034375

SERVICE REPRESENTATIVE <u>[Signature]</u>	THE ABOVE MATERIAL AND SERVICE ORDERED BY CUSTOMER AND RECEIVED BY: <u>[Signature]</u> (WELL OWNER OPERATOR CONTRACTOR OR AGENT)
---	---

FIELD SERVICE ORDER NO.



Cement Report

Customer	Merit Energy	Lease No.		Date	6-23-14
Lease	Orion B	Well #	1	Service Receipt	
Casing	5 1/2 17#	Depth	5671'	County	Haskell
Job Type	2-42	Formation		State	KS
				Legal Description	

Pipe Data		Perforating Data		Cement Data
Casing size	5 1/2 17#	Tubing Size		Lead 305 SX @ 13.5 ppG 5% W-60, 10% Salt, br. C-15, 1/4# Deframer, 5# Gilsontite 50/50 Poz Tail in
Depth	5671'	Depth	From To	
Volume	130.6 bbl	Volume	From To	
Max Press		Max Press	From To	
Well Connection		Annulus Vol.	From To	
Plug Depth	5631'	Packer Depth	From To	

Time	Casing Pressure	Tubing Pressure	Bbls. Pumped	Rate	Service Log
1830					On Location
2200					Rig up
2230					Safety Meeting
2235	2500				Pressure Test
2238	100		812	5	Pump 500 gallons of Superflush
2240	100		86	5	Pump 305 SX @ 13.5 ppG
2315					Drop Plug
2320				5	Start Displacement
2348	600		115	2	Slow Rate
2353	1250		130	2	Bump Plug
2358	0				Release Pressure - Float Held
					Shut Down Rig Down
					Final Lift Pressure = 750 PSI;
					Plug Pressure = 1250 PSI;
					HOC = 2750'
					TOC = 2923'
					HOSF = 3138'
					TOSF = 2535'

Service Units	78940	38750	19847	30963	19866
Driver Names	Ruben	Carlos	Chad		

Jimmy Customer Representative
 Jerry Bennett Station Manager
 Ruben Martinez Cementer