



**BASIC**<sup>SM</sup>  
ENERGY SERVICES  
PRESSURE PUMPING & WIRELINE

1700 S. Country Estates Rd.  
Liberal, Kansas 67905  
Phone 620-624-2277

FIELD SERVICE TICKET  
1717 05958 A

DATE \_\_\_\_\_ TICKET NO. \_\_\_\_\_

DATE OF JOB <b>7-15-14</b> DISTRICT <b>1717</b>		NEW WELL <input checked="" type="checkbox"/> OLD WELL <input type="checkbox"/> PROD <input type="checkbox"/> INJ <input type="checkbox"/> WDW <input type="checkbox"/> CUSTOMER ORDER NO.:				
CUSTOMER <b>Merit Energy</b>		LEASE <b>GRIFFIN "E" #1</b>		WELL NO.		
ADDRESS		COUNTY <b>Haskell</b>		STATE <b>KS</b>		
CITY STATE		SERVICE CREW <b>J. CHAVEZ, SAM, ISMAEL, EDGER</b>				
AUTHORIZED BY <b>Tony Bennett</b>		JOB TYPE: <b>242 8 3/8 Surface</b>				
EQUIPMENT#	HRS	EQUIPMENT#	HRS	EQUIPMENT#	HRS	TRUCK CALLED <b>7-15-14</b> DATE AM- TIME <b>100</b>
<b>78938</b>	<b>12</b>	<b>130463 -</b>	<b>12</b>	<b>14355</b>	<b>12</b>	ARRIVED AT JOB <b>7-15-14</b> AM- PM <b>400</b>
		<b>19566</b>	<b>1</b>	<b>37725</b>	<b>1</b>	START OPERATION <b>7-15-14</b> AM- PM <b>1000</b>
<b>✓ 7089*</b>	<b>12</b>					FINISH OPERATION <b>7-15-14</b> AM- PM <b>330</b>
<b>19570 -</b>	<b>1-</b>					RELEASED <b>7-15-14</b> AM- PM <b>445</b>
						MILES FROM STATION TO WELL <b>50</b>

CONTRACT CONDITIONS: (This contract must be signed before the job is commenced or merchandise is delivered).

The undersigned is authorized to execute this contract as an agent of the customer. As such, the undersigned agrees and acknowledges that this contract for services, materials, products, and/or supplies includes all of and only those terms and conditions appearing on the front and back of this document. No additional or substitute terms and/or conditions shall become a part of this contract without the written consent of an officer of Basic Energy Services LP.

SIGNED: *[Signature]*  
(WELL OWNER, OPERATOR, CONTRACTOR OR AGENT)

ITEM/PRICE REF. NO.	MATERIAL, EQUIPMENT AND SERVICES USED	UNIT	QUANTITY	UNIT PRICE	\$ AMOUNT
CL101	A-Com Blend	SK	400		7940 00
CL110	Premium Plus Cement	SK	245		3993 50
CL109	Calcium Chloride	LB	1590		1669 50
CC102	CelloFlake	LB	162		599 40
CC130	G-51	LB	76		1900 00
CF253	✓ Guide Shoe	EA	1		380 00
CF1453	✓ Insert Float Valve	EA	1		280 00
CF4405	✓ Centralizer 8 3/8	EA	14		2030 00
CF4109	✓ Stop Collar	EA	1		160 00
CF105	✓ Rubber Plug	EA	1		225 00
CC165	Stoploss Polymer	SOL	420		2520 00
CC166	Stoploss LCM	LB	160		840 00
E101	Heavy Equipment Mileage	mi	300		2100 00
CE240	Blending & Mixing Charge	SK	645		953 00
E113	Bulk Delivery Charge	+M	1518		3338 50
CE202	Depos. Charge	4 hrs	1		1500 00
CE504	Plus Container Charge	Job	1		250 00
E100	Pickup Mileage	mi	50		212 50
S003	Service Supervisor	EA	1		175 00
SUB TOTAL					<b>24567 30</b>

CHEMICAL / ACID DATA:			

SERVICE & EQUIPMENT	%TAX ON \$	
MATERIALS	%TAX ON \$	
TOTAL		

**APE 34376**

SERVICE REPRESENTATIVE <b>Tony Chavez</b>	THE ABOVE MATERIAL AND SERVICE ORDERED BY CUSTOMER AND RECEIVED BY: <i>[Signature]</i> (WELL OWNER OPERATOR CONTRACTOR OR AGENT)
---	---

FIELD SERVICE ORDER NO. \_\_\_\_\_





# Cement Report

Customer <i>Merit Energy</i>		Lease No.		Date <i>7-15-14</i>		
Lease <i>GRIFFIN "E"</i>		Well # <i>1</i>		Service Receipt <i>5958</i>		
Casing <i>8 5/8</i>		Depth <i>1730</i>		County <i>Haskell</i> State <i>KS</i>		
Job Type <i>242 Surface</i>		Formation		Legal Description		
<b>Pipe Data</b>			<b>Perforating Data</b>		<b>Cement Data</b>	
Casing size <i>8 5/8</i>		Tubing Size		<b>Shots/Ft</b>		
Depth <i>1757</i>		Depth <i>5539'</i>		From	To	
Volume <i>100615</i>		Volume		From	To	
Max Press <i>2000</i>		Max Press		From	To	
Well Connection <i>8 5/8</i>		Annulus Vol.		From	To	
Plug Depth <i>1600</i>		Packer Depth		From	To	
				Lead <i>400 SK A-6m</i>		
				<i>2.4 FT<sup>3</sup>-SK</i>		
				<i>14.06d-SK 12.1#</i>		
				<b>Tail in</b> <i>245 SK Class C</i>		
				<i>1.34 FT<sup>3</sup></i>		
				<i>6.336d-SK 14.8#</i>		
Time	Casing Pressure	Tubing Pressure	Bbls. Pumped	Rate	Service Log	
<i>400</i>					<i>Arrive On Location</i>	
<i>400</i>					<i>Safety Meeting - Rig Up</i>	
<i>400</i>					<i>WAIT For Perforations</i>	
<i>1010</i>	<i>2000</i>				<i>Pressure Test</i>	
<i>1015</i>	<i>500</i>		<i>10</i>	<i>4</i>	<i>Pump Stoploss Polymer</i>	
<i>1030</i>	<i>500</i>		<i>171</i>	<i>5</i>	<i>Pump Lead amt @ 12.1#</i>	
<i>1045</i>	<i>400</i>		<i>58</i>	<i>4</i>	<i>Pump Tail amt @ 14.8#</i>	
<i>1100</i>					<i>Drop Plug - Wash Up</i>	
<i>1105</i>	<i>900</i>		<i>102</i>	<i>5</i>	<i>Displace</i>	
<i>1130</i>					<i>Shut Down</i>	
					<i>WAIT 4 Hours</i>	
					<i>Check Flow Back</i>	
					<i>No Flow BACK</i>	
					<i>Job Complete</i>	
					<i>Cement To Surface</i>	
					<i>Thanks For Using Basic Energy Services</i>	
Service Units	<i>78938</i>	<i>70897-19570</i>	<i>30463-19566</i>	<i>14355-37725</i>		
Driver Names	<i>Jerry</i>	<i>Sam</i>	<i>Ismael</i>	<i>Edgar</i>		

*Jerry*  
Customer Representative

*Jerry Beath*  
Station Manager

*Jerry Chavez*  
Cementer  
Taylor Printing, Inc.