

Wednesday

810 E 7<sup>TH</sup>  
PO Box 92  
EUREKA, KS 67045  
(620) 583-5561



**Cement or Acid Field Report**  
Ticket No. 2802  
Foreman Kevin McCoy  
Camp EUREKA

Date	Cust. ID #	Lease & Well Number	Section	Township	Range	County	State
5-25-16	1180	Fulson B #10				CQ	KS
Customer			Unit #	Driver	Unit #	Driver	
SM OIL & GAS INC.			105	DAVE G			
Mailing Address							
P.O. Box 189			110	Kevin M.			
City			113	Zeni M.			
State			120 P.U.	Greg M.			
Zip Code							
SKIATOOK							
OK							
74070							

Job Type Longstring Hole Depth 1353' Slurry Vol. 26 BBL LIGHT 32 BBL TAIL Tubing \_\_\_\_\_  
 Casing Depth 1338' Hole Size 7 7/8 Slurry Wt. 13.2 - 14\* Drill Pipe \_\_\_\_\_  
 Casing Size & Wt. 5 1/2 17\* Cement Left in Casing 0' Water Gal/SK \_\_\_\_\_ Other \_\_\_\_\_  
 Displacement 31.5 BBL Displacement PSI 600 Bump Plug to 1100 BPM \_\_\_\_\_

Remarks: Safety Meeting: Rig up to 5 1/2 casing. Break circulation w/ fresh water, Pump 400\* Gel Flush w/ HULLS 5 BBL water spacer mixed 90 SKS 50/50 Pozmix Cement w/ 6% Gel, 1\* PhenoSeal /sk @ 13.2\*/gal = 26 BBL Slurry, TAIL in w/ 120 SKS OWC Cement w/ 1\* PhenoSeal /sk @ 14\*/gal = 32 BBL Slurry. Shut down, wash out Pump & Lines, Release Plug. Displace Plug to seat w/ 31.5 BBL Fresh water. FINAL Pumping Pressure 600 PSI. Bump Plug to 1100 PSI. wait 2 mins. Release Pressure. Float Held. Shut in @ 0 PSI. Good Cement Returns to SURFACE = 12 BBL Slurry to Pit. Job Complete. Rig

Code	Qty or Units	Description of Product or Services	Unit Price	Total
C 102	1	Pump Charge	1050.00	1050.00
C 107	30	Mileage	3.95	118.50
C 204	90 SKS	50/50 Pozmix Cement	11.25	1012.50
C 206	450 #	Gel 6%	.20*	90.00
C 208	90*	PhenoSeal 1*/sk	1.25*	112.50
C 202	120 SKS	OWC Cement	19.15	2298.00
C 208	120 #	PhenoSeal 1*/sk	1.25 #	150.00
C 108 A	10.02 Tons	Ton Mileage BULK TRUCKS X2	345.00	690.00
C 113		80 BBL VAC TRUCK (C&E OIL)		451.36
C 206	400 #	Gel Flush	.20*	80.00
C 214	40 #	HULLS	.45*	18.00
C 404	1	5 1/2 Top Rubber Plug	70.00	70.00
			Sub Total	6140.86
			Less 5%	323.33
			Sales Tax 8.5%	325.64
				6143.17

Authorization Witnessed By Joel Title \_\_\_\_\_ Total \_\_\_\_\_

I agree to the payment terms and conditions of services provided on the back of this job ticket. Any amendments to payment terms must be in writing on the front of this job ticket or in the Customer's records at ELITE's office.