

3180 +.50

Druck Hoop
11-1-16

Lease: <i>Page</i>	Well #: <i>24535</i>	API #: <i>13-011-24535-00-00</i>	County:
Owner:	Operator #:		
Sec: <i>18</i>	Tsp: <i>25</i>	R: <i>2DE</i>	Spot Location: <i>N2 NE SE</i>
Started: <i>10-24-2016</i>	Completed: <i>11-1-2016</i>		
Surface: <i>20' 7"</i>	Cemented: <i>6 sacks</i>	Hole Size: <i>10"</i>	
Longstring: <i>705' 27/8</i>	Cemented: <i>75</i>	Hole Size: <i>5 5/8</i>	
SN:	Packer:		
Plugged:	Bottom Plug: <i>TD 712</i>		

TKN	DEP	FORMATION	TKN	DEP	FORMATION
2	2	Top Soil	74	534	shale
8	10	Clay	1	535	Lime
16	36	Lime	139	674	shale
2	38	shale	3	677	Sand No oil
6	44	Lime	1	678	oil Sand Fair Blend
6	50	shale	3	681	oil Sand good Blend
17	67	Lime	10	691	oil Sand Heavy Blend
4	71	shale	2	693	Dark Soft Sand Fair Blend
2	73	Lime	4	697	Black Sand Poor Blend
8	81	shale		712	Sandy shale
2	83	Lime			
5	88	shale			
3	91	Lime		712	TD
35	126	shale			
3	129	Lime			
104	237	shale			
12	245	Lime			
13	258	shale			
5	263	Red Bed			678 to 690 12' 13 parts 1/2" holes
7	270	shale			
5	275	Lime			
3	278	shale			
10	288	Sand			
48	336	shale Shale Sandy			
18	354	Lime			
12	366	shale			
4	370	Sand			
17	387	shale			
2	389	Lime			
10	399	shale			
16	415	Lime			
6	421	shale			
4	425	Lime Fort Scott			
5	430	shale			
6	436	Sand Dry			
3	439	Sand oil chips			
2	441	oil Sand Fair Blend			
6	447	Dry Sand oil chip			
2	449	Dry Sand some shale oil			
2	451	Sandy shale slight oil			
9	460	Sandy shale			