

SM Oil & Gas, Inc.
P. O. Box 189
Skiatook, Oklahoma 74070
620-725-3200

June 16, 2016

*Kansas Corporation Commission
Conservation Division
266 N. Main Street – Suite #220
Wichita, Kansas 67202-1513*

Re: Fulsom "B" #5-1
API #15-019-27524-00-00
Cement Usage ACO-1

To Whom It May Concern:

SM Oil & Gas, Inc. buys quantities of Portland Type I cement, which comes on pallets of 35 sacks per pallet, for the companies usage. In this case, the required 10 sacks of cement is mixed by our own drilling rig personnel and is used to properly install the surface casing.

An invoice showing the bulk quantity of cement is available if needed.

Thank you,



Thomas H. Oast
Area Manager

810 E 7TH
 PO Box 92
 EUREKA, KS 67045
 (620) 583-5561



Cement or Acid Field Report
 Ticket No. 2813
 Foreman KEVIN MCCOY
 Camp EUREKA

Date	Cust. ID #	Lease & Well Number	Section	Township	Range	County	State	
6-23-16	1180	Fulson #B5-1				CQ	K	
Customer SM OIL & GAS, INC.			Safety Meeting KM DG AB RL SM		Unit #	Driver	Unit #	Driver
Mailing Address P.O. Box 189					105	DAVE G.		
City SKIATOOK			State OK		112	AMEN B.		
Zip Code 74070					113	RICK L.		
					145	STEVIE M.		

Job Type Longstring Hole Depth 2129' Slurry Vol. 54219AT 38 TAIL Tubing _____
 Casing Depth 2122.60' Hole Size 7 7/8 Slurry Wt. 13.2 - 13.9 Drill Pipe _____
 Casing Size & Wt. 5 1/2 17# Cement Left in Casing 0' Water Gal/SK _____ Other _____
 Displacement 51 BBL Displacement PSI 800 Bump Plug to 1200 PSI BPM _____

Remarks: Safety Meeting: Rig up to 5 1/2 casing w/ wash head. Break circulation w/ 60 BBL fresh water. Wash down 10' 5 1/2 to TD of 2122.60'. Pump 500# Gel flush w/ 15k hulls, 15 BBL water spacer. Shut down. Rig up cement head. Reload water trucks. Mixed 175 SKS 50/50 Pozmix cement w/ 6% Gel 1# PhenoSeal @ 13.2# / gal yield 1.70 = 54 BBL slurry. TAIL w/ w/ 135 SKS OWC cement w/ 1# PhenoSeal @ 13.9# / gal yield 1.58 = 38 BBL slurry. Wash out pump & lines. Shut down. Release plug. Displace plug to seat w/ 51 BBL fresh water. Final pumping pressure 800 PSI. Bump plug to 1200 PSI. wait 2 mins. Release pressure, float held shut in @ 0 PSI. Good cement returns to surface = 13 BBL slurry to pit. Job complete. Rig down.

Code	Qty or Units	Description of Product or Services	Unit Price	Total
C 102	1	Pump Charge	1050.00	1050.00
C 107	30	Mileage	3.95	118.50
C 204	175 SKS	50/50 Pozmix Cement	11.25	1968.75
C 206	880 #	Gel 6%	.20 #	176.00
C 208	175 #	PhenoSeal 1#/SK	1.25 #	218.75
C 202	135 SKS	OWC Cement	19.15	2585.25
C 208	135 #	PhenoSeal 1#/SK	1.25 #	168.75
C 108 A	14.37 TONS	TON Mileage BULK TRUCKS X 2	M/C	690.00
C 113	2.5 HRS	20 BBL VAC TRUCK	85.00	212.50
C 224	3300 gals	CITY WATER	10.00/1000	33.00
C 206	500 #	Gel Flush	.20 #	100.00
C 214	40 #	Cotton Seed Hulls	.45 #	18.00
C 404	1	5 1/2 Top Rubber Plug	70.00	70.00
			Sub Total	7409.50
			Less 5%	393.16
			Sales Tax	453.77
THANK YOU			8.5 %	
Authorization	Title		Total	7470.11

I agree to the payment terms and conditions of services provided on the back of this job ticket. Any amendments to payment terms must be in writing on the front of this job ticket or in the Customer's records at ELITE's office.