

Operator License # 31295  
 Operator Prairie Oil, LLC  
 Address 7553 W. 295th Street  
 City Louisburg, KS 66053  
 Contractor JTC Oil, Inc.  
 Contractor License # 32834  
 T.D. 600'  
 T.D. of pipe 592'  
 Surface pipe size 7"  
 Surface pipe depth 20'  
 Well Type Production

API # 15-121-30721-00-00  
 Lease Name LW  
 Well # I-17  
 Spud Date 11/4/2014  
 Cement Date 11/13/2014  
 Location Sec 4 T 18 R 22  
 1980 feet from N line  
 1980 feet from E line  
 County Miami

Driller's Log

Thickness	Strata	From	To	
2	soil	0	2	
24	clay	2	26	
14	lime	26	40	
10	shale	40	50	
29	lime	50	79	
5	coal	79	84	
23	lime	84	107	
5	coal	107	112	
12	lime	112	124	
169	shale	124	293	
11	lime	293	304	
51	shale	304	355	
7	lime	355	362	
11	shale	362	373	
3	lime	373	376	
15	black shale	376	391	
15	lime	391	406	
15	shale	406	421	
5	lime	421	426	
5	coal	426	431	
7	lime	431	438	
45	shale	438	483	
27	black shale	483	510	
4	sandy	510	514	
39	shale	514	553	
2	oil sand	553	555	ok
3	oil sand	555	558	v-good
3	oil sand	558	561	v-good
3	oil sand	561	564	v-good
2	oil sand	564	566	v-good
2	oil sand	566	568	good
32	black shale	568	600	