



**CONSOLIDATED**  
Oil Well Services, LLC

PO Box 884, Chanute, KS 66720  
620-431-9210 or 800-467-8676

TICKET NUMBER 50605

LOCATION Ottawa, KS

FOREMAN Casper Kennedy

**INVOICE #802295**

**FIELD TICKET & TREATMENT REPORT**  
**CEMENT**

1232  
1167

DATE	CUSTOMER #	WELL NAME & NUMBER	SECTION	TOWNSHIP	RANGE	COUNTY
11/12/14	4015	LW Wilson #117	NE4	18	22	MI
CUSTOMER JTL Oil Inc			TRUCK #			
MAILING ADDRESS 35790 Plum Creek			DRIVER			
CITY Ottawa, KS			STATE			
ZIP CODE 66064			TRUCK #			
JOB TYPE <u>Long String</u>			DRIVER			
HOLE SIZE <u>6"</u>			TRUCK #			
HOLE DEPTH <u>6000'</u>			DRIVER			
CASING SIZE & WEIGHT <u>2 7/8" EUE</u>			TRUCK #			
CASING DEPTH <u>392'</u>			DRIVER			
SLURRY WEIGHT			TRUCK #			
SLURRY VOL			DRIVER			
WATER gal/sk			TRUCK #			
CEMENT LEFT In CASING			DRIVER			
DISPLACEMENT <u>3.43 bbls</u>			TRUCK #			
DISPLACEMENT PSI			DRIVER			
MIX PSI			TRUCK #			
RATE <u>4.5 bpm</u>			DRIVER			

REMARKS: held safety meeting, established circulation, mixed & pumped 100# Premium Gel followed by 5 bbls fresh water, mixed & pumped 74 stks OWC cement w/ 1/4# Floreal per sk, cement to surface, flushed pump clean, pumped 2 1/2" rubber plug to casing TD w/ 3.43 bbls fresh water, pressured to 800 PSI, well held pressure for 30 min MIT, released pressure, shut in casing.

BTG

ACCOUNT CODE	QUANTITY or UNITS	DESCRIPTION of SERVICES or PRODUCT	UNIT PRICE	TOTAL
5401	1	PUMP CHARGE		1085.00
5406	25 mi	MILEAGE		105.00
5402	592'	casing footage		
5407	1/2 minimum	hour mileage		184.00
5502C	1 hr	80 Vac		100.00
1126	74 stks	owc cement	1461.50	
118B	100 #	Premium Gel	22.00	
1167	19 #	Floreal	46.93	
		materials	1530.43	
		-30%	459.13	
		subtotal		1071.30
1402	1	2 1/2" rubber plug		21.50
				3153.21
		7.65%	SALES TAX	84.21
			ESTIMATED TOTAL	2659.01

**completed**

13737 AUTHORIZATION No Co. Reg. on location TITLE \_\_\_\_\_ DATE \_\_\_\_\_  
knowledge that the payment terms, unless specifically amended in writing on the front of the form or in the customer's account records, at our office, and conditions of service on the back of this form are in effect for services identified on this form.