



**CONSOLIDATED**  
Oil Well Services, LLC

TICKET NUMBER 50717

LOCATION Chawna, KS

FOREMAN Casey Kennedy

PO Box 884, Chanute, KS 66720  
620-431-9210 or 800-467-8676

**FIELD TICKET & TREATMENT REPORT**  
**CEMENT**

DATE	CUSTOMER #	WELL NAME & NUMBER	SECTION	TOWNSHIP	RANGE	COUNTY
12/23/14	4015	Hahn #BSP-HN9	NW 23	18	21	M1
CUSTOMER JTC Oil Inc.			TRUCK #			
MAILING ADDRESS 35790 Oil Inc.			DRIVER			
CITY Osage townie			TRUCK #			
STATE KS			DRIVER			
ZIP CODE 66064			TRUCK #			
			DRIVER			

JTC Oil Inc.  
35790 Oil Inc.  
Osage townie  
KS  
66064

TRUCK # 729 DRIVER CasKen  
6666 KeiCar  
548 DawnWha  
370 MikFox

TRUCK # 1 Safety Meeting  
✓  
✓  
✓

JOB TYPE long string HOLE SIZE 6" HOLE DEPTH 560' CASING SIZE & WEIGHT 2 7/8" EUE  
 CASING DEPTH 533' DRILL PIPE \_\_\_\_\_ TUBING \_\_\_\_\_ OTHER \_\_\_\_\_  
 SLURRY WEIGHT \_\_\_\_\_ SLURRY VOL \_\_\_\_\_ WATER gal/sk \_\_\_\_\_ CEMENT LEFT in CASING \_\_\_\_\_  
 DISPLACEMENT 3.09 bbls DISPLACEMENT PSI \_\_\_\_\_ MIX PSI \_\_\_\_\_ RATE 4 bpm

REMARKS: held safety meeting, established circulation, mixed + pumped 100# Gel followed by 10 bbls fresh water, mixed + pumped 68 sks 60# cement w/ 1/2# Floseal per sk, cement to surface, flushed pump clean, pumped 2 1/2" rubber plug to casing TD w/ 3.09 bbls fresh water, pressured to 800 PSI, released pressure, shut in casing.

*Handwritten signature*

ACCOUNT CODE	QUANTITY or UNITS	DESCRIPTION of SERVICES or PRODUCT	UNIT PRICE	TOTAL
5401	1	PUMP CHARGE		1085.00
5406	an lease	MILEAGE		
5402	533'	casing footage		
5407	1/2 main	tax mileage		122.67
5502C	1 hrs	80 Vac		100.00
11216	68 sks	60# cement	1343.00	
1118B	200 #	Gel	44.00	
1107	7 #	Floseal	41.99	
		materials	1428.99	
		-30%	428.70	
		Subtotal		1000.29
4402	1	2 1/2" rubber plug		29.50
			2871.73	

Flavin 3737

SALES TAX 7.65% 78.78  
 ESTIMATED TOTAL 2415.24

SCANNED

AUTHORIZATION No Co. Rep on location TITLE \_\_\_\_\_ DATE \_\_\_\_\_

I acknowledge that the payment terms, unless specifically amended in writing on the front of the form or in the customer's account records, at our office, and conditions of service on the back of this form are in effect for services identified on this form