



TICKET NUMBER 50715

LOCATION Okawa, KS

FOREMAN Casper Kennedy

PO Box 884, Chanute, KS 66720
620-431-9210 or 800-467-8676

FIELD TICKET & TREATMENT REPORT
CEMENT

DATE	CUSTOMER #	WELL NAME & NUMBER	SECTION	TOWNSHIP	RANGE	COUNTY
12/21/14	4015	Hahn # BSP-HN 8	NW 23	18	21	MI
CUSTOMER			TRUCK #	DRIVER	TRUCK #	DRIVER
MAILING ADDRESS			729	Casper	✓ Safety	Madison
CITY			6666	KeiCar	✓	
STATE			548	Dan Gha	✓	
ZIP CODE			369	Mik Naa	✓	
JOB TYPE	HOLE SIZE	HOLE DEPTH	CASING SIZE & WEIGHT			
lighting	6"	560'	2 7/8" EUE			
CASING DEPTH	DRILL PIPE	TUBING	OTHER			
526'						
SLURRY WEIGHT	SLURRY VOL	WATER gal/sk	CEMENT LEFT in CASING			
DISPLACEMENT	DISPLACEMENT PSI	MIX PSI	RATE			
3.04 bbls			4.6pm			

REMARKS: held safety meeting, established circulation, mixed & pumped 106 # Gel followed by 10 bbls fresh water, mixed & pumped 108 sks OWC cement w/ 1/4 # Floseal per sk, cement to surface, flushed pump clean, pumped 2 1/2" rubber plug to casing TD w/ 3.04 bbls fresh water, pressured to 800 PSI, released pressure, shut in casing.

ACCOUNT CODE	QUANTITY or UNITS	DESCRIPTION of SERVICES or PRODUCT	UNIT PRICE	TOTAL
5401	1	PUMP CHARGE		1085.00
5406	25 mi	MILEAGE		105.00
5402	526'	Casing footage		
5407	1/3 min	1/3 mi mileage		122.67
5502C	1 hr	80 Use		100.00
1126	108 sks	OWC cement	1743.00	
1118	200 #	Premium Gel	44.00	
1107	17 #	Floseal	41.99	
		materials	1828.99	
		-3070	428.70	
		Subtotal		1000.29
4402	1	2 1/2" rubber plug		29.50
				2982.73
			7.65%	78.78
			ESTIMATED TOTAL	2521.24

Revin 3737

SCANNED

AUTHORIZATION No Co. Rep. on location

TITLE _____

DATE _____

I acknowledge that the payment terms, unless specifically amended in writing on the front of the form or in the customer's account records, at our office, and conditions of service on the back of this form are in effect for services identified on this form