



CONSOLIDATED
Oil Well Services, LLC

PO Box 884, Chanute, KS 66720
620-431-9210 or 800-467-8676

6855/6757

TICKET NUMBER, 50276

LOCATION Ottawa, KS

FOREMAN Casen Kennedy

**FIELD TICKET & TREATMENT REPORT
CEMENT**

Invoice # 98828

DATE	CUSTOMER #	WELL NAME & NUMBER	SECTION	TOWNSHIP	RANGE	COUNTY
10/18/14	7823	Elbert P1-2016	NW 1	17	23	MI
CUSTOMER <u>Town Oil Co.</u>						
MAILING ADDRESS <u>16205 W. 287th St.</u>						
CITY <u>Paola</u>		STATE <u>KS</u>	ZIP CODE <u>66071</u>			
			TRUCK #	DRIVER	TRUCK #	DRIVER
			<u>729</u>	<u>Cas Ken</u>	<u>✓</u>	<u>Sally Meeting</u>
			<u>495</u>	<u>Har Bec</u>	<u>✓</u>	
			<u>510</u>	<u>Mik Has</u>	<u>✓</u>	

JOB TYPE log string HOLE SIZE 6 3/4" HOLE DEPTH 730' CASING SIZE & WEIGHT 4 1/2"
 CASING DEPTH 715' DRILL PIPE _____ TUBING _____ OTHER _____
 SLURRY WEIGHT _____ SLURRY VOL _____ WATER gal/sk _____ CEMENT LEFT in CASING _____
 DISPLACEMENT 11.40 bbls DISPLACEMENT PSI _____ MIX PSI _____ RATE 4 bpm

REMARKS: held safety meeting, established circulation, mixed + pumped 100# gel followed by 5 bbls fresh water, mixed + pumped 10 bbls dye marker, mixed + pumped 105 sks Pozblend 1A cement, w/ 2% gel per sk, dye marker to surface, flushed pump clean, pumped 4 1/2" rubber plug to casing TD w/ 11.40 bbls fresh water, cement to surface, pressured to 800 PSI, released pressure.

Signature

ACCOUNT CODE	QUANTITY or UNITS	DESCRIPTION of SERVICES or PRODUCT	UNIT PRICE	TOTAL
CE0450	1	PUMP CHARGE	1500.00	
CE0002	on lease	MILEAGE		
CE0711	1/2 min	Tom mileage	330.00	
		Trucks	1830.00	
		-58%	1061.40	
		Subtotal		7168.60
10202 CC5840	105 sks	Pozblend 1A cement	1417.50	
CC5965	276 #	Gel	82.80	
CP8178	1	4 1/2" rubber plug	75.00	
		Materials	1575.30	
		-58%	913.67	
		Subtotal		661.63
		8%	SALES TAX	52.93
		ESTIMATED TOTAL		1483.16

RAVIN 3737 AUTHORIZATION Scott Rikland TITLE Driller DATE 10-18-16

I acknowledge that the payment terms, unless specifically amended in writing on the front of the form or in the customer's account records, at our office, and conditions of service on the back of this form are in effect for services identified on this form. (3531.32)

