

SWIFT Services, Inc.

J & Nelson	WELL NO. 1-21	LEASE Windy Hill - Darnell	JOB TYPE Port Collar	TICKET NO. 29482
------------	---------------	----------------------------	----------------------	------------------

TIME	RATE (BPM)	VOLUME (BBL) (GAL)	PUMPS		PRESSURE (PSI)		DESCRIPTION OF OPERATION AND MATERIALS
			T	C	TUBING	CASING	
900							On location
							RBP - 2972
							Port collar - 1780
945		9					SPOT SAND @ 2000'
1000							Pull PRR To Port Collar
1005		24			1500		Load Hole & TST - Held
	2.5				500		Open Port Collar & Get Rate
1020	4	0			500		START CMT @ 11.2 # - 170 SKS SAND
	4	95			500		Circulate CMT - Raise weight to 14.5 #
1105	4	9			650		Displace CMT
					1500		Close Port Collar & TST - Held
							Run 5 Joints
1130		15			300		Reverse out - Clean
1145		35					Run Tubing to Sand & Circulate SAND OFF PLUG
1245							- PLUG NOT Releasing - WAIT ON MORE WTR
1340							- Circulate on to plug & Release T.O.D.H
1350							JOB COMPLETE
							TOOK 170 SKS TO Circulate CEMENT TO SURFACE - Followed with 15 SKS CMT @ 14.5 PPG
							Thanks DAVID, JON H, PRUSTON