

JOB LOG

SWIFT Services, Inc.

DATE 12-27-14 PAGE NO.

CUSTOMER ~~Hess~~ Hess Oil Co WELL NO. 41 LEASE Yonger JOB TYPE 2-Stage TICKET NO. 26924

CHART NO.	TIME	RATE (BPM)	VOLUME (BBL) (GAL)	PUMPS		PRESSURE (PSI)		DESCRIPTION OF OPERATION AND MATERIALS
				T	C	TUBING	CASING	
	2100							on loc 4W /FE
								RTD 3925 5 1/2" x 15.5" x 3916' x 16' Turbo 1,3,5,7,9 cent 56 Basket 57 D.V. 57 @ 1434'
	2215							start FE
	0030							Break Circ
	0100	5	0				200	start 50 gal Mud Flush
	0102	5	12/0				200	start 20 bbl KCL Flush
	0106	5	20/0				200	start 150 sks EA-2 cent
	0113		36					End Cent Wash P+L Drop L.D. Plug
	0125	6	0				200	Start Displacement wtr
	0137	5	70				250	catch cent start mud
	0145		93				750/1400	Land Plug Release Pressure Hold / Drop Open Plug / washing Trk
	0200						1400	Open DV Circ 4 hrs
	0630							Plug RH 30 sks SMD
	0640	5	0				150	start 20 bbl KCL wtr Flush
	0645	5	20/0				150	start 170 sks SMD cent
	0705		100					End Cent Drop Closing Plug
	0715	5	0				150	Start Displacement
	0717	4	10				250	circ cent
	0725		34				500/1500	Land Plug Release Press DV closed
								circ 40 sks to pit
								Thank you Nick, Austin, & Craig