

Operator License # 32834  
 Operator JTC Oil, Inc.  
 Address 35790 Plum Creek Road  
 City Osawatomie, KS 66064  
 Contractor JTC Oil, Inc.  
 Contractor License # 32834  
 T.D. 700'  
 T.D. of pipe 690'  
 Surface pipe size 7"  
 Surface pipe depth 20'  
 Well Type Production

API # 15-121-30980-00-00  
 Lease Name Roy Beets  
 Well # P-2  
 Spud Date 4/9/2015  
 Cement Date 4/10/2015  
 Location Sec 12 T 18 S R 21 E  
 809 feet from N line  
 1125 feet from E line  
 County Miami

Driller's Log

Thickness	Strata	From	To	
2	soil	0	2	
3	lime	2	5	
30	shale	5	35	
20	lime	35	55	
95	shale	55	150	
20	lime	150	170	
17	shale	170	187	
7	lime	187	194	
43	shale	194	237	
15	lime	237	252	
10	shale	252	262	
30	lime	262	292	
6	coal	292	298	
22	lime	298	320	
5	coal	320	325	
12	lime	325	337	
166	shale	337	503	
13	lime	503	516	
46	shale	516	562	
11	lime	562	573	
9	shale	573	582	
2	lime	582	584	
17	black shale	584	601	
9	lime	601	610	
19	shale	610	629	
2	lime	629	631	
5	coal	631	636	
7	lime	636	643	
5	shale	643	648	
2	oil sand	648	650	good
3	oil sand	650	653	good
3	oil sand	653	656	good
3	oil sand	656	659	v-good
2	oil sand	659	661	ok

39

shale

661

700