

ALLIED OIL & GAS SERVICES, LLC 064801

Federal Tax I.D. # 20-8651475

REMIT TO P.O. BOX 93999
SOUTHLAKE, TEXAS 76092

SERVICE POINT:
Dekly, KS

DATE <u>1-3-15</u>	SEC <u>24</u>	TWP <u>26 S</u>	RANGE <u>34 W</u>	CALLED OUT	ON LOCATION <u>2:00 a.m.</u>	JOB START <u>6:30 a.m.</u>	JOB FINISH <u>7:30 p.m.</u>
LEASE <u>Stacy</u>	WELL # <u>124</u>	LOCATION <u>Garden City Sto TV Rel</u>			COUNTY <u>Finney</u>	STATE <u>KS</u>	
OLD OR <u>NEW</u> (Circle one)				<u>6 1/4 W, 5th Winto</u>			

CONTRACTOR <u>Berexco 1</u>	OWNER <u>Same</u>
TYPE OF JOB <u>Surface</u>	
HOLE SIZE <u>12 1/4</u>	T.D. <u>1792'</u>
CASING SIZE <u>8 5/8</u>	DEPTH <u>1792'</u>
TUBING SIZE	DEPTH
DRILL PIPE	DEPTH
TOOL	DEPTH
PRES. MAX	MINIMUM
MEAS. LINE	SHOE JOINT <u>42.20'</u>
CEMENT LEFT IN CSG. <u>42.20'</u>	
PERFS.	
DISPLACEMENT <u>111.46 bbl #20</u>	

CEMENT		
AMOUNT ORDERED <u>625 sks class A type I Lite, 150 sks Com 3.1 CC 1/4" Flo Seal</u>		
COMMON	<u>150 sks @ 17.90</u>	<u>2685.00</u>
POZMIX	@	
GEL	@	
CHLORIDE	<u>2255 # @ 1.10</u>	<u>2480.50</u>
ASC	@	
Flo-seal	<u>195 # @ 2.97</u>	<u>579.15</u>
gilsomite	<u>312.5 # @ .98</u>	<u>3062.50</u>
class A Lite	<u>625 sks @ 19.88</u>	<u>12425.00</u>
	@	
Material Total	@	<u>21,621.15</u>
	@	
	<u>(7,354.25 / 35%)</u>	
	@	
HANDLING <u>921.65 ft³</u>	<u>@ 2.48</u>	<u>2285.68</u>
MILEAGE <u>1927.76 @ 2.75</u>		<u>5301.35</u>
TOTAL		

EQUIPMENT	
PUMP TRUCK # <u>120</u>	CEMENTER <u>Paul Beaver</u>
	HELPER <u>Tyler Flipse / Juan 3</u>
BULK TRUCK # <u>810/241</u>	DRIVER <u>George Grant</u>
BULK TRUCK # <u>1009/239</u>	DRIVER <u>Pat Newell (Great Bend)</u>

REMARKS:
Run casing / Float equip / Drop ball, pump ball through @ 400 #, mix 625 sks Lite, tail w/ 150 sks Com, wash up to pit, release plug, Displace w/ water, plug did land, lift 500', Float did hold, cement did cure

Thank you!
Paul + Crew

CHARGE TO: Berexco

STREET _____

CITY _____ STATE _____ ZIP _____

SERVICE		
DEPTH OF JOB	<u>1792'</u>	
PUMP TRUCK CHARGE		<u>2213.75</u>
EXTRA FOOTAGE	@	
MILEAGE <u>MLLV 50</u>	<u>@ 7.70</u>	<u>385.00</u>
MANIFOLD <u>Head</u>	@	<u>N/C</u>
<u>MLLV</u>	@	<u>N/C</u>
	@	
	<u>(3565.02 / 35%)</u>	
TOTAL		<u>10,185.78</u>

PLUG & FLOAT EQUIPMENT		
<u>Industrial Rubber (8 5/8)</u>		
<u>Guide shoe</u>	@	<u>460.00</u>
<u>AFU Float valve</u>	@	<u>447.00</u>
<u>Top Rubber plug</u>	@	<u>131.00</u>
<u>Centralizers 3</u>	@ <u>75.00</u>	<u>225.00</u>
	@	
	<u>(378.90 / 30%)</u>	
TOTAL		<u>1,263.00</u>

To: Allied Oil & Gas Services, LLC.
You are hereby requested to rent cementing equipment and furnish cementer and helper(s) to assist owner or contractor to do work as is listed. The above work was done to satisfaction and supervision of owner agent or contractor. I have read and understand the "GENERAL TERMS AND CONDITIONS" listed on the reverse side.

SALES TAX (if Any)	
TOTAL CHARGES	<u>32,460.93</u>
DISCOUNT <u>11,098.17 (35/30)</u>	IF PAID IN 30 DAYS

PRINTED NAME Gilbert Davis Jr

SIGNATURE [Signature]

Bid 21,162.76 Net.