

# QUALITY OILWELL CEMENTING, INC.

Federal Tax I.D.# 20-2886107

Phone 785-483-2025  
Cell 785-324-1041

Home Office P.O. Box 32 Russell, KS 67665

No. 1083

Date	Sec.	Twp.	Range	County	State	On Location	Finish
1-28-2015	25	10	30	SHERIDAN	KANSAS		8:30 PM
Location GRINNELL KS. 2N 1/4 E INTD							

Lease	Well No.	Owner	
K-K FARMS	1-25	To Quality Oilwell Cementing, Inc. You are hereby requested to rent cementing equipment and furnish cementer and helper to assist owner or contractor to do work as listed.	
Contractor	Rig #	Charge To	
Discovery DRG	4	SAMUEL GARY JR. ASSOCIATES INC	
Type Job	(Ciac - cement)	Street	
PRODUCTION STRING			
Hole Size	T.D.	City	
7 7/8	4550	State	
Csg.	Depth	The above was done to satisfaction and supervision of owner agent or contractor.	
5 1/2 New	45 45	Cement Amount Ordered 480sx 8% QMDG 3% CC 3% GEL	
Tbg. Size	Depth	180sx Q-PRO-C 10% SALT, 5% GUMMITE 1/4" FLO-SEAL	
#CSG		Common 180	
Tool	Shoe Joint	POZ. MIX QMDG 8% 480	
LATCH Down Plug Assy @ 4501	43 1/4	Gel. 5	
Cement Left in Csg. 43.4	Displace 107.14 BBL	Calcium 5	
Meas Line		Hulls	

**EQUIPMENT**

Pumptrk	No.	Cementor	Glenn G.
18		Helper	CODY B.
Bulktrk	No.	Driver	CHAD M.
19		Driver	
Bulktrk	No.	Driver	TYLOR O.
15		Driver	

**JOB SERVICES & REMARKS**

Remarks: 4:15 pm  
Rat Hole  
~~Mouse Hole~~ TURBO Cent, 1, 3, 5, 7, 9, 11, 13, 15  
Centralizers 49, 66, 79, 89, 97  
Baskets 50, 67, 80, 90, 98  
D/V or Port Collar  
Set @ 4545 15.50" csg.  
Drop AFU Ball, Load csg. + Received CIRCULATION, ROTATE csg. + LOST CIRCULATION, MIXED MORE MUD w/ EXTRA LCM. + Received CIRCULATION Pump 500 GAL - MUD - CLR - 48, Plug Rot w/ 30 sx mouse w/ 15 sx. Mixed 435 sx QMDG + 180sx Q-PRO-C. w/ ROTATING. Clear-Line, Release LATCH DOWN Plug + Displaced A TOTAL OF 99/BBL + PRESSURED TO 4,000, STOP PUMPING + Release Pressure, (AFU - HELD).  
\* Cement DID CIRCULATE TO SURFACE. PUT APPROX 30 SX IN PIT.

Salt	16
Flowseal	285#
Kol-Seal	900#
Mud CLR 48	500 Gal
CFL-117 or CD110 CAF 38	
20 BBL KCL	
Handling	695
Mileage	

**FLOAT EQUIPMENT**

Guide Shoe	Reg. Centralizer	X 5
Centralizer	TURBO	X 8
Baskets	Blue	X 5
AFU Inserts		
Float Shoe	X 1	
Latch Down Plug Assy	X 1	
ROTATING HEAD		
Pumptrk Charge	prod string	
Mileage	24	

X Signature *[Signature]*

Tax	
Discount	
Total Charge	