



Operator:
Grand Mesa Operating Co.
Wichita, KS

Vesecky #1-6i

Douglas Co., KS
23-14S-20E
API: 045-22246

Spud Date:	4/8/2015	Surface Bit:	11.0"
Surface Casing:	7.0"	Drill Bit:	5.875"
Surface Length:	43.70'	Longstring:	752.8'
Surface Cement:	6 sx	Longstring Date:	4/10/2015
Longstring:	2 7/8 EUE - New Ltd. Service		

Driller's Log

Top	Bottom	Formation	Comments
0	16	Soil & clay	
16	26	Gravel w/clay	
26	29	Clay	Platey
29	56	Shale	
56	67	Lime	
67	70	Shale	
70	87	Lime	
87	95	Bl. Shale	
95	102	Lime	
102	108	Shale	
108	147	Lime	
147	161	Shale	
161	188	Lime	
188	245	Shale	
245	249	Lime	
249	251	Shale	
251	270	Lime	
270	289	Shale	
289	298	Lime	
298	329	Shale	
329	336	Lime	
336	340	Shale	
340	342	Lime	
342	350	Shale	

Vesecky #1-6i
Douglas Co., KS

350	380	Lime	
380	383	Bl. Shale	
383	410	Lime	
410	414	Bl. Shale	
414	428	Lime	
428	439	Shale	
439	447	Lime	
447	475	Shale	
475	479	Lime	
479	606	Shale	
606	612	Lime	
612	617	Shale	
617	620	Lime	
620	632	Shale	
632	642	Lime	
642	656	Shale	
656	660	Lime	
660	664	Shale	
664	680	Lime	
680	694	Shale	
694	698	Lime	
698	706	Shale	
706	708	Lime	
708	720	Shale	
720	731	Sand	720-722 Mostly shale, odor, no show
731	762	Shale	722-729 Laminated sand, good odor
762		TD	Good show in samples
			729-731 Mostly shale, odor

Run **Coring**
Footage **Rec.**