



PO Box 884, Chanute, KS 66720
620-431-9210 or 800-467-8676

TICKET NUMBER 50939
LOCATION Ottawa, KS
FOREMAN Casey Kennedy

FIELD TICKET & TREATMENT REPORT
CEMENT

DATE	CUSTOMER #	WELL NAME & NUMBER	SECTION	TOWNSHIP	RANGE	COUNTY
4/10/15	3372	Vescky # 1-6I	NW22	14	20	DG
CUSTOMER			TRUCK #	DRIVER	TRUCK #	DRIVER
Grand Mesa			729	Carlson	✓ Safety Meeting	Meeting
MAILING ADDRESS			308	Alabad	✓	
1700 W Waterfront Drury			558	KaiCar	✓	
CITY	STATE	ZIP CODE	369	Mikhaa	✓	
Wichita	KS					

JOB TYPE log string HOLE SIZE 5 7/8" HOLE DEPTH 762' CASING SIZE & WEIGHT 2 7/8" EVE
 CASING DEPTH 752' DRILL PIPE _____ TUBING _____ OTHER _____
 SLURRY WEIGHT _____ SLURRY VOL _____ WATER gal/sk _____ CEMENT LEFT in CASING _____
 DISPLACEMENT 4.36 bbls DISPLACEMENT PSI _____ MIX PSI _____ RATE 3 bpm

REMARKS: held safety meeting, established circulation, mixed & pumped 200# Gal followed by 105 bbls fresh water, mixed & pumped 110 sks 50/50 Pozmix cement w/ 2% gel, 5% salt, + 5# Kalseal per sk, cement to surface, flushed pump clean, pumped 2 1/2" rubber plug to casing TD w/ 4.36 bbls fresh water, pressured to 800 PSI, well held pressure for 30 min MT, released pressure, shut in casing.

PK

ACCOUNT CODE	QUANTITY or UNITS	DESCRIPTION of SERVICES or PRODUCT	UNIT PRICE	TOTAL
5401	1	PUMP CHARGE		
5406	25 mi	MILEAGE		
5402	753'	Casing footage		
5407	minimum	ton mileage		
5502	2 hr	80 Vac		
		trucks		
		Subtotal		
1124	110 sks	50/50 Pozmix cement		
118B	385 #	Gel		
1111	231 #	Salt		
1110A	550 #	Kalseal		
		materials		
		- 30%		
		Subtotal		
440	1	2 1/2" rubber plug		
			SALES TAX	
			ESTIMATED	
			TOTAL	

Ravin 3737

AUTHORIZATION No Co Rep on location TITLE _____ DATE _____

... that the payment terms, unless specifically amended in writing on the front of the form or in the customer's