



BASICSM
ENERGY SERVICES
PRESSURE PUMPING & WIRELINE

1700 S. Country Estates Rd.
Liberal, Kansas 67905
Phone 620-624-2277

FIELD SERVICE TICKET
1717 05516 A

DATE 5/1 TICKET NO. _____

DATE OF JOB <u>5-1-15</u>	DISTRICT	NEW WELL <input checked="" type="checkbox"/>	OLD WELL <input type="checkbox"/>	PROD <input type="checkbox"/>	INJ <input type="checkbox"/>	WDW <input type="checkbox"/>	CUSTOMER ORDER NO.:
CUSTOMER <u>Merit Energy</u>		LEASE <u>Wright</u>	WELL NO. <u>35-2</u>				
ADDRESS		COUNTY <u>Haskell</u>	STATE <u>Ks.</u>				
CITY	STATE	SERVICE CREW <u>Daniel, Carlos, Hector R., Rogelio</u>					
AUTHORIZED BY <u>Chad Hinz</u>		JOB TYPE: <u>Z42 Surface</u>					
EQUIPMENT#	HRS	EQUIPMENT#	HRS	EQUIPMENT#	HRS	TRUCK CALLED	DATE <u>5-1-15</u> AM <u>12:30</u> TIME
<u>78938</u>	<u>5</u>					ARRIVED AT JOB	<u>PM 3:35</u>
<u>38117/19919-5</u>	<u>5</u>					START OPERATION	<u>PM 5:30</u>
<u>27908/37725</u>	<u>5</u>					FINISH OPERATION	<u>PM 7:46</u>
<u>30464/37724</u>	<u>5</u>					RELEASED	<u>PM 8:30</u>
						MILES FROM STATION TO WELL	<u>50</u>

CONTRACT CONDITIONS: (This contract must be signed before the job is commenced or merchandise is delivered).

The undersigned is authorized to execute this contract as an agent of the customer. As such, the undersigned agrees and acknowledges that this contract for services, materials, products, and/or supplies includes all of and only those terms and conditions appearing on the front and back of this document. No additional or substitute terms and/or conditions shall become a part of this contract without the written consent of an officer of Basic Energy Services LP.

SIGNED: X
(WELL OWNER, OPERATOR, CONTRACTOR OR AGENT)

ITEM/PRICE REF. NO.	MATERIAL, EQUIPMENT AND SERVICES USED	UNIT	QUANTITY	UNIT PRICE	\$ AMOUNT
CL 101	A-Con Blend	sk	300		5580.00
CL 110	Premium Plus Cement	sk	240		3912.00
CC 109	Calcium Chloride	lb.	1,298		1362.90
CC 102	Celloflake	lb.	135		499.50
CC 130	C-51	lb.	57		1425.00
E 101	Heavy Equipment Mileage	mi	150		1125.00
CE 240	Blending & Mixing Service Charge	sk.	540		756.00
E 113	Proppant & Bulk Delivery Charges	tm	1,270		3175.00
CE 202	Depth Charge; 1001-2000'	4hrs.	1		1500.00
CE 504	Plug Container Utilization Charge	job	1		250.00
E 100	Unit Mileage Charge-Pickups, Small/V	mi	50		725.00
3003	Service Supervisor, first 8hrs. on loc.	ea	1		175.00
T 105	Cement Data Acquisition Monitor	ea	1		550.00

Well Wright 35-2

AFE 44850

GL 83001075

Office Olysses

Date 5/1/15

SUB TOTAL 10,267.70

CHEMICAL / ACID DATA	SERVICE & EQUIPMENT	%TAX ON \$	
	MATERIALS	%TAX ON \$	
	TOTAL		

SERVICE REPRESENTATIVE Daniel Beck THE ABOVE MATERIAL AND SERVICE ORDERED BY CUSTOMER AND RECEIVED BY: X
(WELL OWNER, OPERATOR, CONTRACTOR OR AGENT)

FIELD SERVICE ORDER NO.



Cement Report

Customer <i>Merit Energy</i>		Lease No.		Date <i>9-1-15</i>	
Lease <i>Wright</i>		Well # <i>35-2</i>		Service Receipt <i>1717 05516 A</i>	
Casing <i>8 5/8" 24#</i>	Depth	County <i>Haskell</i>		State <i>Ks.</i>	
Job Type <i>242 Surface</i>	Formation	Legal Description <i>35 27 33</i>			
Pipe Data			Perforating Data		Cement Data
Casing size <i>8 5/8" 24#</i>	Tubing Size	Shots/Ft		Lead 'A-Con' Blend <i>300sk</i>	
Depth <i>1,670.47 ft</i>	Depth	From	To		
Volume <i>103.39 bbl</i>	Volume	From	To	<i>2.40^{ft}/sk 14.00^{ft}/sk</i>	
Max Press <i>1500 psi</i>	Max Press	From	To	Tail in Premium Plus Cement <i>240sk</i>	
Well Connection <i>P.C.</i>	Annulus Vol.	From	To		
Plug Depth <i>1625.76 ft</i>	Packer Depth	From	To	<i>1.34^{ft}/sk 6.33^{ft}/sk</i>	
Time	Casing Pressure	Tubing Pressure	Bbls. Pumped	Rate	Service Log
<i>12:30</i>					<i>Call Out</i>
<i>15:35</i>					<i>On Location, wait on casing</i>
<i>16:45</i>					<i>Safety M. w/ BES Personnel</i>
<i>17:30</i>					<i>Rig Up Head & Circulate</i>
<i>18:00</i>					<i>Rig Up Pump</i>
<i>18:15</i>					<i>Safety M. w/ Rig Crew</i>
<i>18:20</i>	<i>100</i>			<i>5.0</i>	<i>Pressure test to 1500</i>
<i>18:40</i>	<i>100</i>			<i>5.0</i>	<i>Pump Lead</i>
<i>19:00</i>					<i>Pump Tail</i>
	<i>75</i>		<i>10</i>	<i>5.0</i>	<i>Shutdown/Wash Pump/Displace</i>
	<i>100</i>		<i>20</i>	<i>5.0</i>	<i>A+ 186bbl Cement Returns</i>
	<i>150</i>		<i>30</i>	<i>5.0</i>	
	<i>200</i>		<i>40</i>	<i>4.9</i>	
	<i>250</i>		<i>50</i>	<i>4.8</i>	
	<i>400</i>		<i>60</i>	<i>4.7</i>	
	<i>550</i>		<i>70</i>	<i>5.0</i> <i>4.7</i>	
	<i>600</i>		<i>80</i>	<i>4.6</i>	
	<i>650</i>		<i>90</i>	<i>4.5</i>	
<i>19:35</i>	<i>600</i>		<i>93</i>	<i>2.4</i>	<i>slow rate</i>
	<i>650</i>		<i>100</i>	<i>2.5</i>	
<i>19:46</i>	<i>1100</i>		<i>103.5</i>	<i>0</i>	<i>Plug Landed Pressure Up</i>
					<i>Float Held Job Complete</i>
Service Units	<i>78938</i>	<i>38117/19919</i>	<i>27808/37725</i>	<i>30464/37724</i>	
Driver Names	<i>Daniel</i>	<i>Carlos</i>	<i>Hector R.</i>	<i>Rogelio</i>	

Early Zion
Customer Representative

Tyce Davis
Station Manager

Daniel Beck
Cementer