



BASICSM
ENERGY SERVICES
PRESSURE PUMPING & WIRELINE

1700 S. Country Estates Rd.
Liberal, Kansas 67905
Phone 620-624-2277

FIELD SERVICE TICKET
1717 05385 A

DATE _____ TICKET NO. _____

DATE OF JOB: 3-18-15	DISTRICT: 1717	NEW WELL <input checked="" type="checkbox"/>	OLD WELL <input type="checkbox"/>	PROD <input type="checkbox"/>	INJ <input type="checkbox"/>	WDW <input type="checkbox"/>	CUSTOMER ORDER NO.:		
CUSTOMER: Merit Energy		LEASE: Warner G #3				WELL NO.:			
ADDRESS:		COUNTY: Haskell		STATE: KS					
CITY: STATE:		SERVICE CREW: G Echavaria, S Chavez, V Vasquez							
AUTHORIZED BY: T Davis		JOB TYPE: 242-80% Surface							
EQUIPMENT#	HRS	EQUIPMENT#	HRS	EQUIPMENT#	HRS	TRUCK CALLED	DATE	AM	TIME
78940	3	30464	3				3-18-15	AM	6:00
37223	3	37724	3			ARRIVED AT JOB		AM	10:00
37226	3					START OPERATION		PM	12:00
19827	3					FINISH OPERATION		PM	1:00
37725	3					RELEASED		PM	2:00
						MILES FROM STATION TO WELL	50 mi		

CONTRACT CONDITIONS: (This contract must be signed before the job is commenced or merchandise is delivered).

The undersigned is authorized to execute this contract as an agent of the customer. As such, the undersigned agrees and acknowledges that this contract for services, materials, products, and/or supplies includes all of and only those terms and conditions appearing on the front and back of this document. No additional or substitute terms and/or conditions shall become a part of this contract without the written consent of an officer of Basic Energy Services LP.

SIGNED: _____
(WELL OWNER, OPERATOR, CONTRACTOR OR AGENT)

ITEM/PRICE REF. NO.	MATERIAL, EQUIPMENT AND SERVICES USED	UNIT	QUANTITY	UNIT PRICE	\$ AMOUNT
CL101	VACen	sk	310		5746.00
CL110	Premium Plus	sk	240		3912.00
CC109	Calcium Chloride	lb	1378		1394.40
CC102	Well Plate	lb	138		510.60
CC130	C-51	lb	59		1475.00
CF912	80% Non Rotating Plug	ea	1		950.00
E101	Heavy Equipment Mileage	mi	150		1125.00
CE240	Blending + Bulk	sk	550		770.00
E113	Proppant + Bulk Delivery	ton/mi	1290		3237.50
CE202	Pump Depth: 1001-2000'	hr	1		1500.00
CE503	High Head 8	ea	1		300.00
CE504	Poly Container	ea	1		250.00
E100	Unit Mileage	mi	50		225.00
S003	Service Supervisor	ea	1		175.00
T105	Cement Data Acquisition	ea	1		550.00
Well: Warner G-3					
AFE: 334813					
GL: 53001073					
					SUB TOTAL: 11165.00

CHEMICAL / ACID DATA:

Office: Ulysses KS

Date: 3/19/15

<i>Apco</i>		
SERVICE & EQUIPMENT	%TAX ON \$	
MATERIALS	%TAX ON \$	
TOTAL		

SERVICE REPRESENTATIVE: <i>Paul Swera</i>	THE ABOVE MATERIAL AND SERVICE ORDERED BY CUSTOMER AND RECEIVED BY: <i>Jim [Signature]</i>
FIELD SERVICE ORDER NO.:	(WELL OWNER OPERATOR CONTRACTOR OR AGENT)



Cement Report

Customer	Merit Energy	Lease No.		Date	3-18-15
Lease	Warner G	Well #	3	Service Receipt	05385
Casing	8 5/8" 24#	Depth	1705'	County	Maskell
Job Type	242-8 5/8" Surface	Information		State	KS
		Legal Description	26-27-33		

Pipe Data		Perforating Data		Cement Data
Casing size	8 5/8" 24#	Tubing Size		Lead 310 sk
Depth	1705'	Shots/Ft		Alcon
Volume	Disp-106.26bbl	From	To	
Max Press	1500 #	From	To	Tail in 240 sk
Well Connection	ID-1705'	Annulus Vol.	From	To
Plug Depth	ST-37.55'	Packer Depth	From	To
				Premium Plus

Time	Casing Pressure	Tubing Pressure	Bbls. Pumped	Rate	Service Log
10:30					on loc-site assessment spot trucks rig up safety meeting - JSA pressure test @ 1500 #
12:15	200		132.5	5	Mix + pump 310 sk Alcon w/ 3% CC, 1/4# PF @ 2% W/A-1 @ 12.1# - 240 sk
	100		57.3	5	switch to 240 sk Class C w/ 2% CC, 1/4# PF @ 14.8# - 1.34 sk
	100		0	5	drop plug, disp csg
	500		9.5	2	slow rate
1:20	1500		10.6	0	land plug, float held - job complete c/cr. just to surface held 1500# - 15 min ok

Service Units	78940	37223-37126	14821-37125	30464-37124
Driver Names	Adrian	G. Echavarran	V. Vasquez	S. Chavez

James Customer Representative
 T Davis Station Manager
 A. Rivera Cementer