



BASICSM
ENERGY SERVICES
PRESSURE PUMPING & WIRELINE

1700 S. Country Estates Rd.
Liberal, Kansas 67905
Phone 620-624-2277

FIELD SERVICE TICKET
1717 05297 A

DATE 3/26 TICKET NO. _____

DATE OF JOB <u>3/26/15</u>	DISTRICT	NEW WELL <input checked="" type="checkbox"/>	OLD WELL <input type="checkbox"/>	PROD <input type="checkbox"/>	INJ <input type="checkbox"/>	WDW <input type="checkbox"/>	CUSTOMER ORDER NO.:
CUSTOMER <u>Merit Energy</u>		LEASE <u>Syrasser "A"</u>	WELL NO. <u>3</u>				
ADDRESS		COUNTY <u>Finney</u>	STATE <u>KS</u>				
CITY	STATE	SERVICE CREW <u>Tommy, Carlos, Hector, Rajelio</u>					
AUTHORIZED BY <u>Tyler Davis</u>		JOB TYPE: <u>742 Surface</u>					
EQUIPMENT#	HRS	EQUIPMENT#	HRS	EQUIPMENT#	HRS	TRUCK CALLED	DATE <u>3/23</u> AM/PM <u>AM</u> TIME <u>4:00</u>
<u>86573</u>	<u>5 1/2</u>					ARRIVED AT JOB	<u>3/26</u> AM/PM <u>AM</u> <u>6:00</u>
<u>38750/19847</u>	<u>5 1/2</u>					START OPERATION	AM/PM <u>AM</u> <u>9:06</u>
<u>38119/37547</u>	<u>5 1/2</u>					FINISH OPERATION	AM/PM <u>AM</u> <u>10:34</u>
<u>30463/19566</u>	<u>5 1/2</u>					RELEASED	AM/PM <u>AM</u> <u>11:30</u>
						MILES FROM STATION TO WELL	<u>50 mi</u>

CONTRACT CONDITIONS: (This contract must be signed before the job is commenced or merchandise is delivered).

The undersigned is authorized to execute this contract as an agent of the customer. As such, the undersigned agrees and acknowledges that this contract for services, materials, products, and/or supplies includes all of and only those terms and conditions appearing on the front and back of this document. No additional or substitute terms and/or conditions shall become a part of this contract without the written consent of an officer of Basic Energy Services LP.

SIGNED: [Signature]
AFE#44577 (WELL OWNER, OPERATOR, CONTRACTOR OR AGENT)

ITEM/PRICE REF. NO.	MATERIAL, EQUIPMENT AND SERVICES USED	UNIT	QUANTITY	UNIT PRICE	\$ AMOUNT	
CL101	✓ Acon Blend	sk	310		5766.00	
CL110	✓ Premium Plus cement	sk	230		3749.00	
CC109	✓ Calcium Chloride	lb	1310		1375.50	
CL102	✓ Cellotake	lb	136		503.20	
CL130	✓ C-51	lb	59		1479.00	
CF912	8 5/8 No Rotating Plug	ea	1		950.00	
CF4405	✓ Econimizer Hinged W/etched Standard Centralizer	ea	10		900.00	
E101	Heavy Equipment Mileage	mi	150		1125.00	
CE240	Blending & Mixing Service Charge	sk	540		756.00	
E113	Proppant and Bulk Delivery Charge	tm	1273		3181.25	
CE202	Depth Charge 1001-2000	4hrs	1		1500.00	
CE504	Plug Container Utilization Charge	Job	1		250.00	
E100	Unit Mileage Charge "Pickup"	mi	50		225.00	
5003	Service Supervisor first 8hrs on loc	ea	1		175.00	
					SUB TOTAL	11150.47

Well STRASSER A-3
AFE 44577
GL 83001025
Office Holcomb KS
Date 3/26/15

SERVICE & EQUIPMENT	%TAX ON \$
MATERIALS	%TAX ON \$
TOTAL	

SERVICE REPRESENTATIVE Tommy Marcellus THE ABOVE MATERIAL AND SERVICE ORDERED BY CUSTOMER AND RECEIVED BY: [Signature]
(WELL OWNER OPERATOR CONTRACTOR OR AGENT)

FIELD SERVICE ORDER NO.



Cement Report

Customer	Merit Energy		Lease No.			Date	3/26/15		
Lease	Strasser A		Well #	3		Service Receipt	1417-05297A		
Casing	8 5/8 24#	Depth	1737.25		County	Finney		State	KS
Job Type	Surface		Formation			Legal Description	28/23/32		

Pipe Data		Perforating Data		Cement Data		
Casing size	8 5/8 24#	Tubing Size	Shots/Ft		Lead	310 SK Acon @ 12.1
Depth	1737.25	Depth	From	To		
Volume	104.24	Volume	From	To	240	14.00
Max Press	2500 psi	Max Press	From	To	Tail in	230 SK Prem. @ 14.8
Well Connection	PC	Annulus Vol.	From	To		
Plug Depth	1686.18	Packer Depth	From	To	1.34	6.33

Time	Casing Pressure	Tubing Pressure	Bbls. Pumped	Rate	Service Log
0600					On location
0800					Safety mtg w/ Rig crew
0815					Rig up
09:06					Press. test 2500 - failed Replace Single
09:12					Pressure test again 2500
09:15	170		132.5 BBL	5.4	Start cementing lead
09:40	200		54.89	5.1	Switch to tail cement
09:53					Cement returns to Pit 6 BBL rem. on tail
09:55					Shut down drop plug
09:58					Start displacement Washup on plug
	20		10	2.5	
	100		20	5.4	
	120		30	5.3	
	160		40	5.1	
	210		50	4.8	110 BBLs to Pit
	290		60	5.3	259 SKS.
	348		70	5.0	
	430		80	5.2	
	500		90	5.0	
	550		97	5.0	
	460		100	3.0	
10:19	500		104 107	0	Pressured up to 1500 and hold for 15 min
10:34					Released back floor held Job Complete

Service Units	86573	38750/19842	38119/37547	30463/19566	
Driver Names	Tommy M.	Carlos Thoma	Hector Rotiaga	Rojelio Mesta	

James
Customer Representative
Tyce Davis
Station Manager
Tommy Marcellos
Cementer

