

Operator License # 32834
 Operator JTC Oil, Inc.
 Address 35790 Plum Creek Road
 City Osawatomie, KS 66064
 Contractor JTC Oil, Inc.
 Contractor License # 32834
 T.D. 420'
 T.D. of pipe 398'
 Surface pipe size 7"
 Surface pipe depth 20'
 Well Type Injection

API # 15-121-31072-00-00
 Lease Name Feebeck-Thompson
 Well # I-5
 Spud Date 7/22/2015
 Cement Date 7/24/2015
 Location Sec 29 T 17 R 22
 1170 feet from S line
 4620 feet from E line
 County Miami

Driller's Log

Thickness	Strata	From	To	
2	soil	0	2	
16	clay	2	18	
18	lime	18	36	
23	shale	36	59	
7	lime	59	66	
40	shale	66	106	
16	lime	106	122	
9	shale	122	131	
27	lime	131	158	
8	coal	158	166	
23	lime	166	189	
5	coal	189	194	
12	lime	194	206	
132	shale	206	338	
4	red bed	338	342	
6	shale	342	348	
2	oil sand	348	350	good
2	oil sand	350	352	v-good
2	oil sand	352	354	v-good
2	oil sand	354	356	v-good
2	oil sand	356	358	v-good
2	oil sand	358	360	v-good
2	oil sand	360	362	v-good
2	oil sand	362	364	v-good
1	lime	364	365	
5	shale	365	370	
15	lime	370	385	
35	shale	385	420	