



250 N. Water, Ste 200 - Wichita, Ks 67202

### HURRICANE SERVICES INC

104 Prairie Plaza Parkway - Garnett, Ks 66032

<b>Customer:</b> J.T.C.		<b>Customer Name:</b>		<b>Ticket No.:</b> 500323			
<b>Address:</b>		<b>AFE No.:</b>		<b>Date:</b> 7/24/2015			
<b>City, State, Zip:</b>		<b>Job type:</b> long string					
<b>Service District:</b>		<b>Well Details:</b> Hole 5-5/8 @ 420' TD 2-7/8" tubing 402'					
<b>Well name &amp; No.:</b> Feedback I-6		<b>Well Location:</b> County: Miami State: Ks.					
<b>Equipment #</b>	<b>Driver</b>	<b>Equipment #</b>	<b>Driver</b>	<b>Equipment #</b>	<b>Hours</b>		
201	Jerry	25	Dwayne				
240	Troy						
110	Junior						
148-157	Jessie						
Cyclone	Bryan						
<b>TRUCK CALLED</b>							
<b>ARRIVED AT JOB</b>							
<b>START OPERATION</b>							
<b>FINISH OPERATION</b>							
<b>RELEASED</b>							
<b>MILES FROM STATION TO WELL</b>							
<b>Job Summary</b>							
Hook onto well and establish circulation then pump 5 bbrl gel spacer followed by a 5 bbrl pad and start cement Pump 58 sacks of cement stop and flush pump then pump wiper plug to bottom and set pressure @ 750 psi and watch for 15 mins for M.I.T. (pressure held steady) release psi to set float shoe and shut in well. (3 bbrl slurry to pit)							
<b>Product/Service Code</b>	<b>Description</b>	<b>Unit of Measure</b>	<b>Quantity</b>	<b>List Price/Unit</b>	<b>Gross Amount</b>	<b>Item Discount</b>	<b>Net Amount</b>
p01605	O.W.C. Cement	sack	58.00	\$17.95	\$1,041.10	25.00%	\$780.83
p02000	H2O	gal	2,500.00	\$0.01	\$32.50	10.00%	\$29.25
p01631	Rubber Plug 2 7/8	ea	1.00	\$30.00	\$30.00	10.00%	\$27.00
p01607	Bentonite Gel	lb	100.00	\$0.30	\$30.00	25.00%	\$22.50
c00101	Heavy Equip. One Way	mi	25.00	\$3.25	\$81.25	75.00%	\$20.31
c00102	Light Equip. One Way	mi	25.00	\$1.50	\$37.50	75.00%	\$9.38
c24000	Cement Bulk Truck	tm	71.25	\$1.30	\$92.63	10.00%	\$83.36
c11000	Vacuum Truck 80 bbl	ea	1.25	\$84.00	\$105.00	10.00%	\$94.50
c15700	Transports 150 bbl	ea	1.25	\$105.00	\$131.25	28.00%	\$94.50
c20103	Cement Pump	ea	1.00	\$675.00	\$675.00	10.00%	\$607.50
				<b>Gross:</b>	\$ 2,256.23	<b>Net:</b>	\$ 1,769.13
				<b>Total Taxable</b>	\$ -	<b>Tax Rate:</b>	7.400%
TERMS: Cash in advance unless Hurricane Services Inc has approved credit prior to sale. Credit terms of sale for approved accounts are total invoice due on or before the 30th day from the date of invoice. Past due accounts may pay interest on the balance past due at the rate of 1 1/4% per month or the maximum allowable by applicable state or federal laws if such laws limit interest to a lesser amount. In the event it is necessary to employ an agency and/or attorney to affect the collection of said account. Customer hereby agrees to pay all fees directly or indirectly incurred for such collection. In the event that Customer's account with HSI becomes delinquent, HSI has the right to revoke any and all discounts previously applied in arriving at net invoice price. Upon revocation, the full invoice price without discount will become immediately due and owing and subject to collection.				Frac and Acid service treatments designed with intent to increase production on newly drilled or existing wells are not taxable.		<b>Sale Tax:</b> \$ -	
						<b>Total:</b> \$ 1,769.13	
<input checked="" type="checkbox"/> _____		<b>CUSTOMER AUTHORIZED AGENT</b>		<b>Date of Service:</b> 7/24/2015			
				<b>HSI Representative:</b> Dwayne			
				<b>Customer Representative:</b> Dean			
<b>Customer Comments or Concerns:</b>							

Hurricane Services appreciates any Comments, Concerns or Criticism's from our valuable customers as Safety and Customer Satisfaction are our Number 1 goal. All Comments are confidential and will be used in a constructive manner to improve our Safety and Job Performance.