



**BASIC**<sup>SM</sup>  
ENERGY SERVICES  
PRESSURE PUMPING & WIRELINE

1700 S. Country Estates Rd.  
Liberal, Kansas 67905  
Phone 620-624-2277

FIELD SERVICE TICKET  
1717 05518 A

DATE 5/9/15 TICKET NO. \_\_\_\_\_

DATE OF JOB <u>5-8-15</u> DISTRICT _____		NEW WELL <input checked="" type="checkbox"/> OLD WELL <input type="checkbox"/> PROD <input type="checkbox"/> INJ <input type="checkbox"/> WDW <input type="checkbox"/> CUSTOMER ORDER NO.: _____				
CUSTOMER <u>Merit Energy</u>		LEASE <u>McNerney</u>		WELL NO. <u>1</u>		
ADDRESS _____		COUNTY <u>Haskell</u>		STATE <u>Ks.</u>		
CITY _____ STATE _____		SERVICE CREW <u>Daniel, Carlos, Victor, Rogelio</u>				
AUTHORIZED BY <u>Chad Hinz</u>		JOB TYPE: <u>Z42 Surface</u>				
EQUIPMENT#	HRS	EQUIPMENT#	HRS	EQUIPMENT#	HRS	TRUCK CALLED <u>5-8-15</u> <sup>DATE</sup> <u>AM 4:30</u> <sup>TIME</sup>
<u>78938</u>	<u>2hr.30min</u>					ARRIVED AT JOB <u>AM 7:30</u>
<u>38117 / 19919</u>	<u>2hr.38min</u>					START OPERATION <u>5-8-15</u> <u>AM 11:30</u>
<u>30464 / 37724</u>	<u>2hr.38min</u>					FINISH OPERATION <u>5-9-15</u> <u>PM 1:08</u>
<u>27808 / 37725</u>	<u>2hr.38min.</u>					RELEASED <u>5-9-15</u> <u>AM 2:00</u>
						MILES FROM STATION TO WELL <u>50</u>

CONTRACT CONDITIONS: (This contract must be signed before the job is commenced or merchandise is delivered).

The undersigned is authorized to execute this contract as an agent of the customer. As such, the undersigned agrees and acknowledges that this contract for services, materials, products, and/or supplies includes all of and only those terms and conditions appearing on the front and back of this document. No additional or substitute terms and/or conditions shall become a part of this contract without the written consent of an officer of Basic Energy Services LP.

SIGNED: X  
(WELL OWNER, OPERATOR, CONTRACTOR OR AGENT)

ITEM/PRICE REF. NO.	MATERIAL, EQUIPMENT AND SERVICES USED	UNIT	QUANTITY	UNIT PRICE	\$ AMOUNT
CL 101	A-Con Blend	sk	300		9580 00
CL 110	Premium Plus Cement	sk	240		3912 00
CC 109	Calcium Chloride	lb.	1298		1362 90
CC 102	Kelloflake	lb.	135		499 50
CC 130	C-51	lb.	57		1425 00
E 101	Heavy Equipment Mileage	mi	150		1125 00
CE 240	Blending & Mixing Service Charge	sk	540		796 00
E 113	Proppant & Bulk Delivery Charges	tm	1,270		3175 00
CE 202	Depth Charge; 1001'-2000'	4hrs	1		1500 00
CE 504	Plug Container Utilization Charge	job	1		250 00
E 100	Unit Mileage Charge-Pickups Small V.	mi	50		225 00
S 003	Service Supervisor, first 8hrs. on loc.	ea	1		175 00
T 105	Cement Data Acquisition Monitor	ea	1		550 00
	<u>Well McNerney 1</u>				
	<u>AFE 44638</u>				
	<u>GL 83001075</u>				
	<u>Office Ulysses</u>				

SUB TOTAL 10,267 70

CHEMICAL / ACID DATA:			

Date 5/9/15

SERVICE & EQUIPMENT	%TAX ON \$
MATERIALS	%TAX ON \$
TOTAL	

SERVICE REPRESENTATIVE Daniel Beck THE ABOVE MATERIAL AND SERVICE ORDERED BY CUSTOMER AND RECEIVED BY: X

(WELL OWNER OPERATOR CONTRACTOR OR AGENT)

FIELD SERVICE ORDER NO.



# Cement Report

Customer <b>Merit Energy</b>	Lease No.	Date <b>5-8-15</b>
Lease <b>McNerney</b>	Well # <b>1</b>	Service Receipt <b>1717 05518 A</b>
Casing <b>8 5/8" 24#</b>	Depth <b>1668.64 ft</b>	County <b>Haskell</b> State <b>Ks.</b>
Job Type <b>242 Surface</b>	Formation	Legal Description <b>3 28 34</b>

Pipe Data		Perforating Data		Cement Data
Casing size <b>8 5/8" 24#</b>	Tubing Size	Shots/Ft		Lead 'A-Con' Blend <b>300sk</b>
Depth <b>1668.64'</b>	Depth	From	To	
Volume <b>103.28 bbl</b>	Volume	From	To	<b>2.40<sup>ft<sup>3</sup>/sk</sup></b> <b>14.00<sup>gal</sup>/sk</b>
Max Press <b>1500 psi</b>	Max Press	From	To	Tail in Premium Plus Cement <b>240sk</b>
Well Connection <b>PC</b>	Annulus Vol.	From	To	
Plug Depth <b>1623.98'</b>	Packer Depth	From	To	<b>1.34<sup>ft<sup>3</sup>/sk</sup></b> <b>6.33<sup>gal</sup>/sk</b>

Time	Casing Pressure	Tubing Pressure	Bbls. Pumped	Rate	Service Log
16:30					Call Out
19:30					On Location, wait on casers
21:00					Safety Meeting w/BES Personnel
21:55					Rig Up
22:45					Safety Meeting w/Rig Crew
23:00					Rig Up Head
23:20					Pressure Test to 1500psi
23:30	200		128.23 bbl	5.0	Pump Lead 300sk
23:56	50		57.27 bbl	2.5	Pump Tail 240sk
0:20					Shutdown / Drop Plug / Wash Up
	50		10	5.1	Disp
	50		20	5.1	
	150		30	4.6	
	200		40	4.6	
	250		50	4.4	
	400		60	4.1	
	500		70	3.8	
	550		80	3.6	
	580		90	3.4	
0:55	580		93	1.6	Slow Rate
	600		100	1.6	
1:00	1300		103	0	Pressure Up
1:08					Release Back Float Held Job Complete

Service Units	78938	38117/19919	30464/37724	27808/37725
Driver Names	Daniel	Carlos	Victor	Regelio

Early Zion Customer Representative     
 Tyce Davis Station Manager     
 Daniel Beck Cementer