

Operator License # 32834
 Operator JTC Oil, Inc.
 Address 35790 Plum Creek Road
 City Osawatomie, KS 66064
 Contractor JTC Oil, Inc.
 Contractor License # 32834
 T.D. 420'
 T.D. of pipe 400'
 Surface pipe size 7"
 Surface pipe depth 20'
 Well Type Injection

API # 15-121-31074-00-00
 Lease Name Feebeck-Thompson
 Well # I-7

Spud Date 8/7/2015
 Cement Date 8/17/2015
 Location Sec 29 T 17 R 22
 2480 feet from S line
 3965 feet from E line
 County Miami

Driller's Log

Thickness	Strata	From	To	
2	soil	0	2	
13	clay	2	15	
23	shale	15	38	
20	lime	38	58	
23	shale	58	81	
6	lime	81	87	
41	shale	87	128	
15	lime	128	143	
9	shale	143	152	
27	lime	152	179	
11	coal	179	190	
18	lime	190	208	
5	coal	208	213	
13	lime	213	226	
137	shale	226	363	
2	oil sand	363	365	ok
2	oil sand	365	367	good
2	shale	367	369	
2	oil sand	369	371	v-good
3	oil	371	374	v-good
2	oil	374	376	good
2	oil	376	378	good
2	mix/shale/sand	378	380	good
9	shale	380	389	
16	lime	389	405	
15	shale	405	420	