



FIELD TICKET & TREATMENT REPORT CEMENT

FOREMAN Casey, Kennedy

REMARKS: Held safety meetings, established circulation, mixed & pumped 100 # Gel followed by 5 bbls fresh water mixed & pumped 45 sks 5% Portland cement w/ 2% gel, 5% salt, + 5 # Kelgel per sk, cement to surface, flushed pump clean, purged 2 1/2" rubber plug to casing, TD 101/ 1.71 bbls fresh water, pressured to 800 PSI, ~~well~~ well held pressure for 30 min MIT, released pressure, shot in casing.

Bayin 3737

DATE _____

I acknowledge that the payment terms, unless specifically amended in writing on the front of the form or in the customer's account records, at our office, and conditions of service on the back of this form are in effect for services identified on this form.