



TICKET NUMBER 49725
 LOCATION Obama, KS
 FOREMAN Casey Kennedy

PO Box 884, Charute, KS 66720
 620-491-9210 or 800-467-8676

FIELD TICKET & TREATMENT REPORT
CEMENT

DATE	CUSTOMER #	WELL NAME & NUMBER	SECTION	TOWNSHIP	RANGE	COUNTY
7/14/15	3372	Craig #13-5	SW23	14	20	DG
MATERIALS			TRUCK #	DRIVER	TRUCK #	DRIVER
Grand Mesa			729	Casey Ken	✓ 3609	Meeting
Mailing Address			467	Ken Car	✓	
1700 N Underbent Pkwy Bldg 600			503	Art McD	✓	
CITY			369	Art McD	✓	
Wichita						
STATE						
KS						
ZIP CODE						
67206						

JOB TYPE Longstring HOLE SIZE 5 7/8" HOLE DEPTH 770' CASING SIZE & WEIGHT 2 7/8" EUE
 CASING DEPTH 760' DRILL PIPE TUBING baffle - 750' OTHER _____
 SLURRY WEIGHT _____ SLURRY VOL _____ WATER gal/sk _____ CEMENT LEFT in CASING 10'
 DISPLACEMENT 4.34 bbls DISPLACEMENT PSI _____ MIX PSI _____ RATE 4 bbls

REMARKS: held safety meeting, established circulation, mixed & pumped 200# Gel followed by 5 bbls fresh water, mixed & pumped 122 sks 50/50 Pozblend cement w/ 2% gel, 5% salt, + 5# Kalsol per sk, cement to surface, flushed pump clean, pumped 2 1/2" rubber plug to baffle w/ 4.34 bbls fresh water, pressured to 800 PSI, released pressure, shut in casing.

[Handwritten signature]

ACCOUNT CODE	QUANTITY OF UNITS	DESCRIPTION of SERVICES or PRODUCT	UNIT PRICE	TOTAL
CE0450	1	PUMP CHARGE		
CE0002	25 mi	MILEAGE		
CE0411	non	non mileage		
WF0853	2 hrs	2 hr		
CC5840	122 sks	50/50 Pozblend		
CC5965	405 #	Gel		
CC5326	256 #	Salt		
CC6077	610 #	Kalsol		
PD8176	1	2 1/2" rubber plug		
			SALES TAX	
			ESTIMATED	
			TOTAL	

Revin 9797

AUTHORIZATION NoCo Rep. TITLE _____ DATE _____

I acknowledge that the payment terms, unless specifically amended in writing on the front of the form or in the customer's